

For Reference

NOT TO BE TAKEN FROM THIS ROOM

Ex LIBRIS
UNIVERSITATIS
ALBERTAENSIS



THE UNIVERSITY OF ALBERTA

RELEASE FORM

NAME OF AUTHOR

PAULO BRANCO JR.

TITLE OF THESIS

BEHAVIOUR OF A SHALLOW
TUNNEL IN TILL

DEGREE FOR WHICH THESIS WAS PRESENTED MASTER OF SCIENCE

YEAR THIS DEGREE GRANTED FALL 1981

Permission is hereby granted to THE UNIVERSITY OF ALBERTA LIBRARY to reproduce single copies of this thesis and to lend or sell such copies for private, scholarly or scientific research purposes only.

The author reserves other publication rights, and neither the thesis nor extensive extracts from it may be printed or otherwise reproduced without the author's written permission.



Digitized by the Internet Archive
in 2019 with funding from
University of Alberta Libraries

<https://archive.org/details/Branco1981>

THE UNIVERSITY OF ALBERTA

BEHAVIOUR OF A SHALLOW TUNNEL IN TILL

by

© PAULO BRANCO JR.

A THESIS

SUBMITTED TO THE FACULTY OF GRADUATE STUDIES AND RESEARCH
IN PARTIAL FULFILMENT OF THE REQUIREMENTS FOR THE DEGREE
OF MASTER OF SCIENCE

CIVIL ENGINEERING

EDMONTON, ALBERTA

FALL 1981

THE UNIVERSITY OF ALBERTA
FACULTY OF GRADUATE STUDIES AND RESEARCH

The undersigned certify that they have read, and recommend to the Faculty of Graduate Studies and Research, for acceptance, a thesis entitled BEHAVIOUR OF A SHALLOW TUNNEL IN TILL submitted by Paulo Branco Jr in partial fulfilment of the requirements for the degree of MASTER OF SCIENCE.



TO LUCILA

ABSTRACT

The characteristic elements of the behaviour of a large diameter, shallow tunnel, constructed for the extension of the Light Rail Transit System in the City of Edmonton have been documented and analysed in this thesis.

A comprehensive monitoring program that included the measurement of the displacements of the soil and primary lining and the measurement of loads in the primary lining was used in the analysis of the factors that affect the behaviour of the tunnel lining and surrounding soil mass.

The monitoring of ground displacements indicated that most of the soil movements occurred immediately above the tunnel crown and that the tunnel construction did not affect the nearby structures.

The measurement of loads on the primary lining system showed that the steel ribs, at the tunnel crown, carried loads from 9% to 26% of the overburden and that these loads are 85% to 213% higher than the average loads carried by the timber lagging.

The coupled analysis of the soil and lining behaviour of the tunnel reported herein and of other tunnels constructed in Edmonton indicated that there is no simple theoretical design method, such as Closed Form Solutions or Convergence-Confinement Method, applicable to the study of shallow tunnels.

ACKNOWLEDGEMENTS

I would like to express my deepest appreciation and profound thanks to Lucila, my wife, for her immense contribution over the past two years. Lucila unselfishly stopped her studies and left her family and friends to come with me to Canada. Without her love and overwhelmingly enthusiastic support many of the frustrations and difficulties could not have been overcome. To her I dedicate this degree.

To my daughters, Patricia and Renata, I owe the happiest moments during the past couple of years. With their love and happiness, they contributed to make our stay in Canada unforgettable.

I wish to thank my research supervisor and friend, Prof. Z. E. Eisenstein, for his guidance and enthusiastic encouragement during the period we worked together. To him I am grateful.

The financial support provided by the City of Edmonton and the Department of Civil Engineering of the University of Alberta is gratefully acknowledged.

My thanks are extended to the staff within the Department of Civil Engineering, in particular to G. Cyre and A. Muir. They worked on the manufacturing of most equipments used in the monitoring program. G. Cyre provided invaluable help during all phases of the field investigation.

Prof. S. Thomson, C. Mackay, F. El-Nahhas and D. Hutchinson edit this thesis and provided many valuable comments and suggestions. Their contribution is greatly appreciated.

I owe special thanks to A. Negro and D. Hutchinson for the many hours they spent at the site installing instruments, taking readings and pictures for me. Their contribution through stimulating discussions on topics related to tunneling, played an important role in the development of this research.

I also wish to thank the academic staff in the Dept. of Civil Engineering, in special Prof. P. K. Kaiser with whom I have had fruitful discussions on tunneling.

My thanks are extended to the members of my examining committee who provided interesting comments during the final oral examination.

The help provided by Sergio and Helena, who helped us to settle in Edmonton and get adjusted to the new life, will never be forgotten.

To my friends Jose Roberto and Claudia I owe the best of my feelings. Their warm friendship taught me many things about life and made my stay in Canada very pleasant. I hope they go back home soon so we can spend more time together. To them I extend my utmost appreciation and thanks.

I wish to thank my brother, Luiz, and sisters, Helena and Cristina, for the moral support and love they have dedicated to me.

In closing, I would like to express profound thanks to my parents, Paulo and Maria Helena, who gave me the desire and opportunity to undertake this work. I hope I can reflect to my daughters all the love and care they have dedicated to me.

I am extremely happy that now I will be able to spend more time together with my lovely family.

Table of Contents

Chapter	Page
1. INTRODUCTION	1
1.1 General	1
1.2 Aim of this Thesis	2
1.3 Scope of this Thesis	3
2. THE L.R.T. SOUTH EXTENSION	5
2.1 The L.R.T. System	5
2.2 LRT South Extension Construction Procedure	5
2.2.1 The Tunnel Section	7
2.2.2 Stations	8
2.2.3 The Portal Section	9
2.3 Geological and Geotechnical Description in the Edmonton and the LRT System Area	9
2.3.1 Geology of the Edmonton Area	10
2.3.2 Stratigraphy Along the LRT Track Centreline in the Area of the Present Study	13
2.3.3 Geotechnical Properties of the Soil Surrounding the Tunnel	13
2.4 Detailed Description of the Construction of the Tunnel Sections	17
2.4.1 Tunnel Boring Machine	17
2.4.2 The Lining System	17
2.4.3 Construction Procedure	21
2.4.4 Rates of Excavation	30
3. SOIL DISPLACEMENTS DUE TO TUNNELING	33
3.1 Introduction	33
3.2 Currently Available Ground Displacement Measurement Techniques	34
3.2.1 Vertical Displacements	35

3.2.1.1	Surface Vertical Displacements	35
3.2.1.2	Subsurface Vertical Displacements	36
3.2.2	Horizontal Displacements	38
3.2.2.1	Surface Horizontal Displacements	38
3.2.2.2	Subsurface Horizontal Displacements	39
3.3	Ground Displacement Monitoring in the LRT South Extension	43
3.3.1	Instruments Location	43
3.3.2	Vertical Displacements	46
3.3.2.1	Bench Mark	46
3.3.2.2	Settlement Point	50
3.3.2.3	Magnetic Multipoint-Extensometer	68
3.3.3	Horizontal Displacements	88
3.3.3.1	Inclinometer	88
3.4	Discussion of Soil Movements	101
3.4.1	Surface Vertical Displacements	101
3.4.2	Deep Vertical Displacements	109
3.4.3	Deep Horizontal Displacements	111
3.4.4	Loss of Ground Around Tunnels	113
3.5	Summary and Conclusions on Ground Displacements	120
4.	LINING LOADS AND DISPLACEMENTS	122
4.1	Introduction	122
4.2	Direct Pressure Measurement	124
4.2.1	Pressure Cells	124
4.3	Indirect Pressure Measurement	125
4.3.1	Strain Gauges	125
4.3.2	Load Cells	130

4.3.3	Lining Deformation	132
4.3.3.1	Rod or Tape Extensometer	132
4.3.3.2	Integrated Measuring Technique	133
4.4	The L.R.T. South Extension Tunnel Liner Instrumentation	134
4.4.1	Load Cells	135
4.4.1.1	Load Cell Design Details	136
4.4.1.2	Load Cell Calibration	138
4.4.1.3	Load Cell Installation	140
4.4.1.4	Measurement Procedure	142
4.4.1.5	Field Data	144
4.4.1.6	Data Reduction	144
4.4.2	Steel Lagging	155
4.4.2.1	Steel Lagging Design Details	157
4.4.2.2	Steel Lagging Calibration Tests	160
4.4.2.3	Steel lagging Installation	163
4.4.2.4	Measurement Procedure	166
4.4.2.5	Field Data	167
4.4.2.6	Data Reduction	181
4.4.3	Overcoring Measurement	187
4.4.4	Lining Deformation	189
4.4.4.1	Details of Instrumentation	189
4.4.4.2	Eye-Bolts Installation	191
4.4.4.3	Measurement Procedure	192
4.4.4.4	Field Data	193
4.5	Discussion of the LRT South Extension Tunnel Liner Instrumentation	193
4.5.1	Discussion of Loads and Displacements of	

the Steel Ribs	193
4.5.2 Discussion on Steel Lagging Results	198
4.5.3 Discussion of the Convergence / Divergence Measurements	200
4.5.4 General Discussion of the Lining Behaviour	201
4.6 Summary and Conclusions	207
5. SOIL-STRUCTURE INTERACTION AT TUNNELS	209
5.1 Introduction	209
5.2 Closed Form Solutions	211
5.2.1 Deep Tunnels	211
5.2.2 Shallow Tunnels	220
5.3 The Convergence Confinement Method (Characteristic Lines Method)	223
5.3.1 The Convergence Curve for the Ground Surrounding the Opening (Ground Reaction Curve)	224
5.3.2 The Confinement Curve for the Support (Support Reaction Curve)	226
5.3.3 Determination of the Support Pressure and Ground Displacement at the Soil-Structure Interface	228
5.3.4 Advantages of the Convergence-Confinement Method	232
5.4 Application of Simple Solutions to Tunnels Driven in Edmonton Till	233
5.4.1 Analysis of the Results Obtained from Closed Form Solutions	236
5.4.2 Comments on the Evaluation of Ground Support Interaction by the Closed Form Solution by Einstein and Schwartz (1979, 1980)	239
5.4.3 Analysis of the results obtained from the Convergence-Confinement Method	241
5.4.4 Comments on the Evaluation of the Ground Support Interaction by the	

Convergence-Confinement Method	249
5.5 Summary and Conclusions of the Evaluation of Soil-Structure Interaction by "Simple Solutions"	252
6. CONCLUSIONS	255
6.1 Introduction	255
6.2 Soil Response to Tunneling	255
6.2.1 Surface Vertical Displacements	255
6.2.2 Deep Vertical Displacements	256
6.2.3 Deep Horizontal Displacements	257
6.2.4 Loss of Ground	258
6.3 Lining Loads and Displacements	258
6.4 Soil-Structure Interaction	259
6.5 Recommendations for Further Studies	260
REFERENCES	261
A. APPENDIX - LABORATORY TEST RESULTS	267
B. APPENDIX - GROUND INSTRUMENTS - FIELD DATA	274
C. APPENDIX - LINING INSTRUMENTS - FIELD DATA	323
D. APPENDIX - SUPPORT COMPRESSIVE STIFFNESS	350

List of Tables

Table	Page
2.1 GEOTECHNICAL PROPERTIES OF EDMONTON TILL (AFTER THOMSON AND EL-NAHHAS, 1980)	14
2.2 SPECIFICATIONS OF THE TUNNEL BORING MACHINE (LOVAT MODEL M-246 SERIES 2100)	18
3.1 SETTLEMENT POINTS - DETAILS OF INSTALLATION	51
3.2 SETTLEMENT POINTS - CHANGE IN ELEVATION	58
3.3 DETAILS OF MULTIPOINT EXTENSOMETERS	78
3.4 INCLINOMETER SPECIFICATIONS (AFTER SAVIGNY 1980)	90
3.5 INCLINOMETERS - DETAILS OF INSTALLATION	93
4.1 STRAIN GAUGES - TYPES AND FEATURES (AFTER CORDING ET AL, 1975)	127
4.2 LOADS ACTING ON THE STEEL RIBS AT 36.4M FROM THE SHIELD TAIL	156
4.3 LOADS ON THE S.L. AT 36.4m FROM SHIELD TAIL	186
4.4 STRESSES ON STEEL RIBS AND LAGGING AT 36.4m FROM THE SHIELD TAIL	202
4.5 SOIL PRESSURE ON THE PRIMARY LINING IN EDMONTON TUNNELS (AFTER EL-NAHHAS 1980)	206
5.1 LINER AND GROUND PARAMETERS FOR THE LRT AND EXPERIMENTAL TUNNELS	235
5.2 LINING THRUSTS AND DISPLACEMENTS CALCULATED WITH THE CLOSED FORM SOLUTION PROPOSED EINSTEIN AND SCHWARTZ (1979, 1980) FOR THE LRT AND EXPERIMENTAL TUNNELS	238
5.3 ESTIMATION OF THE GROUND DISPLACEMENTS AT THE SOIL-STRUCTURE INTERFACE THAT OCCUR BEFORE THE LINING EXPANSION	245
5.4 CALCULATION OF THE RATIO $U_{b1-meas}/U_o$	247
5.5 CALCULATION OF THE RATIO $U_{final-meas}/U_o$	248

Table	Page
A.1 SUMMARY OF LABORATORY TEST RESULTS - LAKE EDMONTON SEDIMENTS	268
A.2 SUMMARY OF LABORATORY TEST RESULTS - BROWN TILL	269
A.3 SUMMARY OF LABORATORY TEST RESULTS - GREY TILL	270
A.4 SUMMARY OF LABORATORY TEST RESULTS - GREY TILL (cont)	271
A.5 SUMMARY OF LABORATORY TEST RESULTS - INTER-TILL SANDS	272
A.6 SUMMARY OF LABORATORY TEST RESULTS - SASKATCHEWAN SANDS AND GRAVELS	273
B.1 DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE	275
B.2 DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE (cont)	276
B.3 DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE (cont)	277
B.4 DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE (cont)	278
C.1 LOAD CELLS #3 AND #5 - CALIBRATION	324
C.2 LOAD CELLS #1 AND #4 - CALIBRATION	325
C.3 LOAD CELLS #2 AND #7 - CALIBRATION	326
C.4 LOAD CELLS #6 AND #8 - CALIBRATION	327
C.5 EQUATIONS RELATING LOADS TO MICROSTRAINS FOR THE LOAD CELLS 1 TO 8	328
C.6 LOAD CELL #1 - FIELD DATA	329
C.7 LOAD CELL #2 - FIELD DATA	330
C.8 LOAD CELL #3 - FIELD DATA	331
C.9 LOAD CELL #4 - FIELD DATA	332
C.10 LOAD CELL #5 - FIELD DATA	333

Table	Page
C.11 LOAD CELL #6 - FIELD DATA	334
C.12 LOAD CELL #7 - FIELD DATA	335
C.13 LOAD CELL #8 - FIELD DATA	336
C.14 STEEL LAGGING CALIBRATION - SL1 & SL2	337
C.15 STEEL LAGGING CALIBRATION - SL3 & SL4	338
C.16 STEEL LAGGING CALIBRATION - SL5 & SL6	339
C.17 STEEL LAGGING CALIBRATION - SL7 & SL8	340
C.18 STEEL LAGGING CALIBRATION - SL9 & SL10	341
C.19 STEEL LAGGING CALIBRATION - SL11 & SL12	342
C.20 STEEL LAGGING SL1 AND SL2 - FIELD DATA	343
C.21 STEEL LAGGING SL3 AND SL4 - FIELD DATA	344
C.22 STEEL LAGGING SL5 AND SL6 - FIELD DATA	345
C.23 STEEL LAGGING SL7 AND SL8 - FIELD DATA	346
C.24 STEEL LAGGING SL9 AND SL10 - FIELD DATA	347
C.25 STEEL LAGGING SL11 AND SL12 - FIELD DATA	348
C.26 LINING DISPLACEMENTS MEASUREMENTS	349

List of Figures

Figure	Page
2.1 THE L.R.T. SOUTH EXTENSION - PLAN VIEW	6
2.2 QUARTERNARY GEOLOGY OF EDMONTON AREA (AFTER MAY AND THOMSON, 1978)	12
2.3 GENERALIZED GEOLOGIC EAST-WEST CROSS SECTION THROUGH EDMONTON (AFTER KATHOL AND McPHERSON, 1975)	15
2.4 PLAN AND PROFILE FROM CENTRAL STATION TO 103 STREET (AFTER THURBER, 1980)	16
2.5 SECTION THROUGH THE SHIELDED MOLE (AFTER LOVAT TUNNELING EQUIPMENT INC.)	19
2.6 L.R.T. TUNNEL LINING SYSTEM	20
2.7 SIMPLIFIED FLOW CHART OF THE TUNNEL CONSTRUCTION PROCEDURE	29
2.8 MOLE POSITION VERSUS TIME	32
3.1 INSTRUMENTS LOCATION - PLAN VIEW	45
3.2 INSTRUMENTS LOCATION - TRANSVERSE SECTION	47
3.3 BENCH MARK BM1 - DESIGN DETAILS	49
3.4 SETTLEMENT POINT - DESIGN DETAILS	53
3.5 SETTLEMENT POINT FIELD SHEET	56
3.6 SURFACE SETTLEMENT VERSUS TIME	59
3.7 SURFACE SETTLEMENT VS DIST FROM FACE OF MOLE	60
3.8 SETTLEMENT POINT SP2	61
3.9 SETTLEMENT POINT SP3	61
3.10 SETTLEMENT POINT SP4	62
3.11 SETTLEMENT POINT SP8	62
3.12 SETTLEMENT POINT SP11	63
3.13 SETTLEMENT POINT SP13	63
3.14 SETTLEMENT POINT SP14	64

Figure	Page
3.15 SETTLEMENT POINT SP15	64
3.16 SETTLEMENT POINT SP16	65
3.17 SURFACE SETTLEMENT TROUGH - CONTOUR LINES	66
3.18 SURFACE SETTLEMENT TROUGH - TRANSVERSE SECTIONS	67
3.19 MAGNETIC MULTIPOINT EXTENSOMETER - DESIGN DETAILS	69
3.20 MAGNETIC MULTIPOINT EXTENSOMETER - ANCHOR POINT	72
3.21 MAGNETIC MULTIPOINT EXTENSOMETER - MAGNETIC RING DETAIL	73
3.22 MAGNETIC FIELDS AROUND THE RING (AFTER EL-NAHHAS, 1980)	74
3.23 INSTALLATION OF MULTIPOINT EXTENSOMETERS (AFTER EL-NAHHAS, 1980)	75
3.24 MULTIPOINT EXTENSOMETER FIELD SHEET	80
3.25 MULTIPOINT EXTENSOMETER ME5 - VERT. DISPL. X DIST. FROM FACE OF MOLE	82
3.26 MULTIPOINT EXTENSOMETER ME9 - VERT. DISPL. X DIST. FROM FACE OF MOLE	83
3.27 MULTIPOINT EXTENSOMETER ME10 - VERT. DISPL. X DIST. FROM FACE OF MOLE	84
3.28 MULTIPOINT EXTENSOMETER ME17 - VERT. DISPL. X DIST. FROM FACE OF MOLE	85
3.29 SETTLEMENT AT 1.2M AHEAD OF THE FACE OF THE MOLE	86
3.30 SETTLEMENT AT 43M BEHIND THE FACE OF MOLE	87
3.31 INSTALLATION OF SLOPE INDICATORS (AFTER EL-NAHHAS, 1980)	94
3.32 SLOPE INDICATOR FIELD SHEET	96
3.33 ZERO READINGS: SI6 (6.4M FROM TUNNEL AXIS)	98

Figure	Page
3.34 ZERO READINGS: SI7 (4.3M FROM TUNNEL AXIS)	99
3.35 ZERO READINGS: SI12 (TUNNEL CENTRELINE)	100
3.36 SLOPE INDICATOR SI6 (6.4M FROM TUNNEL AXIS)	102
3.37 SLOPE INDICATOR SI7 (4.3M FROM TUNNEL AXIS)	103
3.38 SLOPE INDICATOR SI12 (TUNNEL CENTRELINE)	104
3.39 HORIZONTAL DISPLACEMENTS - PERPENDICULAR TO TUNNEL AXIS AT 11.58M BELOW SURFACE FOR SLOPE INDICATORS SI6, SI7 AND SI12	105
3.40 HORIZONTAL DISPLACEMENTS - PARALLEL TO TUNNEL AXIS AT 11.58M BELOW SURFACE FOR SLOPE INDICATORS SI6, SI7 AND SI12	106
3.41 THREE DIMENSIONAL GROUND MOVEMENTS ABOUT TUNNELS (HANSMIRE, 1975)	114
3.42 RELATIONSHIP OF SURFACE SETTLEMENT VOLUME TO LATERAL DISPLACEMENT VOLUME (AFTER HANSMIRE, 1975)	118
3.43 COMPARISON OF SETTLEMENT AND LATERAL DISPLACEMENT VOLUMES	119
4.1 LOCATION OF STRAIN GAUGES ON RIB CROSS-SECTION - LRT NORTH-EAST LINE (AFTER EISENSTEIN ET AL, 1977)	129
4.2 LOAD CELL - DESIGN DETAILS	137
4.3 LOAD CELL LOCATION	141
4.4 LOAD CELL FIELD SHEET	143
4.5 LOAD CELLS - UPPER JOINTS - LOAD VS TIME	145
4.6 LOAD CELLS - UPPER JOINTS - LOAD VS LOG.TIME	146
4.7 LOAD CELLS - UPPER JOINTS - LOAD VS DISTANCE FROM TAIL OF MOLE	147
4.8 LOAD CELLS - LOWER JOINTS - LOAD VS TIME	148

4.9	LOAD CELLS - LOWER JOINTS - LOAD VS LOG.TIME	149
4.10	LOAD CELLS - LOWER JOINTS - LOAD VS DISTANCE FROM TAIL OF MOLE	150
4.11	LOAD DISTRIBUTION AROUND TUNNEL LINERS: SYMMETRIC TO VERTICAL AND HORIZONTAL AXIS	151
4.12	GROUND STRESS DISTRIBUTION ON STEEL RIBS TAKING INTO ACCOUNT SHEAR ALONG THE SOIL-LINER INTERFACE	153
4.13	EQUILIBRIUM EQUATIONS FOR THE LOAD DISTRIBUTION OF FIG 4.12	154
4.14	STEEL LAGGING DESIGN DETAILS	159
4.15	STEEL LAGGING - MEAN CALIBRATION CURVE	161
4.16	STEEL LAGGING LOCATION	164
4.17	SL AND LC RELATIVE POSITION	165
4.18	STEEL LAGGING FIELD SHEET	168
4.19	STEEL LAGGING - #1 AND #8 - STRAIN VS TIME	169
4.20	STEEL LAGGING - #1 AND #8 - STRAIN VS DIST. FROM TAIL OF MOLE	170
4.21	STEEL LAGGING - #10 AND #11 - STRAIN VS TIME	171
4.22	STEEL LAGGING - #10 AND #11 - STRAIN VS DIST. FROM TAIL OF MOLE	172
4.23	STEEL LAGGING - #9 AND #12 - STRAIN VS TIME	173
4.24	STEEL LAGGING - #9 AND #12 - STRAIN VS DIST. FROM TAIL OF MOLE	174
4.25	STEEL LAGGING - #2 AND #7 - STRAIN VS TIME	175
4.26	STEEL LAGGING - #2 AND #7 - STRAIN VS DIST. FROM TAIL OF MOLE	176

Figure	Page
4.27 STEEL LAGGING - #3 AND #6 - STRAIN VS TIME	177
4.28 STEEL LAGGING - #3 AND #6 - STRAIN VS DIST. FROM TAIL OF MOLE	178
4.29 STEEL LAGGING - #4 AND #5 - STRAIN VS TIME	179
4.30 STEEL LAGGING - #4 AND #5 - STRAIN VS DIST. FROM TAIL OF MOLE	180
4.31 STEEL LAGGING STRESS DISTRIBUTION CALCULATED FROM STRAIN GAUGES	183
4.32 SIMPLIFIED STEEL LAGGING STRESS DISTRIBUTION ASSUMED ON THE DATA REDUCTION	184
4.33 STRESS DISTRIBUTION ON THE LAGGING AT 36.4m FROM THE SHIELD TAIL	188
4.34 LINING DEFORMATION MEASUREMENT - POSITION OF THE EYE-BOLTS AND MEASURED CHORDS	190
4.35 LINING DEFORMATION MEASUREMENT - FIELD DATA SHEET	194
4.36 LINING DEFORMATION RESULTS	195
4.37 STRESS DISTRIBUTION ON RIB AND LAGGING AT 36.4M FROM THE SHIELD TAIL	204
5.1 FIELD STRESSES IN BURNS AND RICHARD'S CLOSED FORM SOLUTION	214
5.2 FULL SLIP CASE - EINSTEIN AND SCHWARTZ, 1979-1980	217
5.3 NO-SLIP CASE - EINSTEIN AND SCHWARTZ, 1979-1980	218
5.4 MINDLIN'S CLOSED FORM SOLUTION FOR UNLINED TUNNELS	222
5.5 SUPPORT REACTION CURVE - COMBINED SUPPORT STIFFNESS	227
5.6 SOLUTION FOR THE SOIL-STRUCTURE INTERACTION BY THE CONVERGENCE-CONFINEMENT METHOD	229

5.7	CHARACTERISTIC CURVES FOR THE LRT AND EXPERIMENTAL TUNNELS	242
B.1	ME5 MP#1 D=2.35m	279
B.2	ME5 MP#2 D=4.88m	280
B.3	ME5 MP#3 D=6.85m	281
B.4	ME5 MP#4 D=8.13m	282
B.5	ME5 MP#5 D=10.86m	283
B.6	ME5 MP#6 D=12.91m	284
B.7	ME5 MP#7 D=14.81m	285
B.8	ME5 MP#8 D=16.78m	286
B.9	ME5 MP#9 D=18.08m	287
B.10	ME9 MP#1 D=1.43m	288
B.11	ME9 MP#2 D=2.93m	289
B.12	ME9 MP#3 D=4.89m	290
B.13	ME9 MP#4 D=7.01m	291
B.14	ME9 MP#5 D=8.93m	292
B.15	ME9 MP#6 D=11.16m	293
B.16	ME9 MP#7 D=13.89m	294
B.17	ME9 MP#8 D=15.61m	295
B.18	ME9 MP#9 D=16.92m	296
B.19	ME9 MP#10 D=18.36m	297
B.20	ME10 MP#1 D=2.53m	298
B.21	ME10 MP#2 D=4.58m	299
B.22	ME10 MP#3 D=6.38m	300
B.23	ME10 MP#4 D=8.40m	301
B.24	ME10 MP#5 D=10.22m	302

Figure		Page
B.25	ME10 MP#6 D=12.28m	303
B.26	ME10 MP#7 D=14.29m	304
B.27	ME10 MP#8 D=16.25m	305
B.28	ME17 MP#1 D=3.01m	306
B.29	ME17 MP#2 D=4.20m	307
B.30	ME17 MP#3 D=5.24m	308
B.31	ME17 MP#4 D=6.69m	309
B.32	ME17 MP#5 D=7.59m	310
B.33	SI6-FIELD DATA	311
B.34	SI6-FIELD DATA	312
B.35	SI6-FIELD DATA	313
B.36	SI6-FIELD DATA	314
B.37	SI7-FIELD DATA	315
B.38	SI7-FIELD DATA	316
B.39	SI7-FIELD DATA	317
B.40	SI7-FIELD DATA	318
B.41	SI12-FIELD DATA	319
B.42	SI12-FIELD DATA	320
B.43	SI12-FIELD DATA	321
B.44	SI12-FIELD DATA	322
D.1	DERIVATION OF THE SUPPORT COMPRESSIVE STIFFNESS	351

List of Plates

Plate	Page
2.1 T.B.M. - CUTTING HEAD	22
2.2 EXPANDED LONGITUDINAL JACKS	22
2.3 GENERAL VIEW INSIDE THE MOLE	24
2.4 CONVEYOR BELT STRUCTURE	24
2.5 LAGGING INSTALLATION	27
2.6 RIB EXPANSION	27
3.1 MULTIPOINT EXTENSOMETER - ANCHOR POINT	70
3.2 MULTIPOINT EXTENSOMETER - INSTALLATION	70
3.3 INCLINOMETER - INSTALLATION	91
3.4 INCLINOMETER - READINGS	91
4.1 LOAD CELL DETAIL	139
4.2 LOAD CELL INSTALLATION	139
4.3 STEEL LAGGING DETAIL	162
4.4 STEEL LAGGING INSTALLATION	162

1. INTRODUCTION

1.1 General

The need for tunnels for transportation, drainage and sanitary purposes has increased in the last decade due to the growth of the cities. The increase in tunneling activities is not proportional to the improvement in the understanding of the complex phenomena involved in the transfer of load from the excavated ground to the support during and after the tunnel construction. The need for a better understanding of the factors affecting the development of lining loads and displacements and ground displacements is reflected by the fact that the available tunnel design methods do not take into account factors that directly affect the lining and ground behaviour, such as minor construction details. The need for a better knowledge of factors affecting the interaction between tunnel support system and the surrounding soil mass enhances the importance of full scale field observations.

The City of Edmonton is presently constructing the extension of its Light Rail Transit System. This extension crosses the city core with two parallel, large diameter tunnels, bored close to the ground surface. The lack of detailed, full-scale, field observations on large diameter tunnels excavated in the Edmonton till led to a comprehensive monitoring program.

In this thesis, the monitoring program that involved measurements of soil displacements and primary lining loads and deformations carried out during the construction of the north tunnel of the South Extension of the L.R.T. System of Edmonton is documented and interpreted.

1.2 Aim of this Thesis

The field data presented in this study should enable the analysis of the influence of the construction procedure, the effect of the soil and lining strength and deformation properties on the magnitude and distribution of loads on the lining and on the displacement field in the soil mass surrounding the instrumented tunnel. The analysis of the factors affecting the lining and ground behaviour should provide an insight into the interaction between the elements of the lining system and the surrounding soil mass and the effect of soil movements on the structures near the tunnel.

The comparison of the field data documented here with the data collected from another monitoring program carried out in Edmonton, in a deeper, small diameter tunnel (El-Nahhas, 1980) should enable the analysis of the influence of the depth ratio (depth of the tunnel axis/tunnel diameter) on the mode of deformation and plastic behaviour of the soil and how these affect the lining behaviour.

1.3 Scope of this Thesis

A brief outline of the Light Railway Transit System (LRT) presently being extended in the City of Edmonton is presented in Chapter 2. This chapter gives an overview of the geology of the Edmonton area, a description of the subsurface soil profile close to the instrumented section and the construction procedure employed in the tunnel construction.

Chapter 3 summarizes the ground displacement measurement techniques. It presents a detailed description of the design, installation and measurement procedure of the instruments chosen for the measurement of ground movements used in the monitoring program carried out during the construction of the north tunnel of the LRT South Extension. The measured soil displacements are presented and interpreted in this Chapter.

In Chapter 4, the methods available to obtain the magnitude and distribution of ground loads on linings are presented and discussed. A detailed description of the design, installation and measurement procedure of the instruments used in the study of the LRT primary lining behaviour is presented. The results obtained from the lining instrumentations are presented and discussed in this Chapter.

Chapter 5 presents an analysis of the interaction between the soil and the tunnel support system based on the data presented in Chapter 3 and Chapter 4. In this chapter,

the applicability of Closed Form Solutions and the Convergence-Confinement Method for the evaluation of the soil and structure behaviour in shallow-tunnels is analysed. This analysis enables insights into the factors affecting the ground and lining interaction to be discussed.

Finally, conclusions are offered in Chapter 6.

2. THE L.R.T. SOUTH EXTENSION

2.1 The L.R.T. System

The City of Edmonton is presently building the South Extension of the Light Rail Transit System - LRT. The South Extension completes the connection of the southern region of the City with the City core.

The North-East line, already built, connects the LRT Central Station, located in the downtown core, with the north-eastern suburbs while the "South Extension", under construction, will connect the Central Station with the Canadian Pacific Railway right-of-way, south of 100th avenue, parallel to 109th street.

A schematic representation of the LRT South Extension is shown on Figure 2.1.

2.2 LRT South Extension Construction Procedure

The construction of the South Extension is divided into three different sections:

- The tunnel section
- The stations
- The portal section

Each of these sections is described in the following section.




Figure 2.1 THE L.R.T. SOUTH EXTENSION - PLAN VIEW

2.2.1 The Tunnel Section

Due to the fact that the construction area is intensively developed and that the obstruction of the traffic would lead to serious problems, it was decided that the LRT Central Station, the 104th St and 107th St Stations (Fig 2.1) were to be connected by two parallel tunnels, employing the same construction procedure as that used for the construction of the underground portions of the North-East line.

The north tunnel excavation was planned to begin from the LRT Central Station and proceed westwards under Jasper Avenue. This procedure would facilitate the disposal of spoil material that would be transported in rail cars to the north-eastern region of Edmonton, using the existing LRT line.

The tunnelling boring machine (TBM), later described in this chapter, was planned to proceed to 106th Street where an access shaft is to be constructed. The TBM will be dismantled in this shaft and taken back through the existing tunnel to the Central Station, to begin the excavation of the second tunnel (south tunnel).

Section 2.4 specifically, deals with the tunnel section since the north tunnel construction between Central Station and 104th Street Station is the major focus of this thesis.

2.2.2 Stations

Three stations will be built between the LRT Central Station and the river crossing:

104th St Station

107th St Station

Government Station

The 104th St and the 107th St Stations will be built using a cut and cover method. The walls of the excavation will consist of cast in place concrete tangent piles.

The concrete piles will be installed to a depth of about 18 metres below the existing grade (street level) and will carry the lateral earth pressure from the soil, as well as the vertical loads from the station and street above. Permanent horizontal struts will be provided at the street level, the mezzanine level, and at the base of the station.

The first of the LRT tunnels (North tunnel) will be bored through the 104th St Station after installation of the tangent pile walls. The excavation of the station itself will be finished after the first one of the two tunnels has been completed.

The Government Station will be constructed near 98th Avenue on the existing CP rail right of way. The LRT tracks at this station will be near the existing CP rail track level.

2.2.3 The Portal Section

The Portal Section will consist of twin tunnels which curve southwards from the 107th St Station and pass under 109th Street (Fig 2.1). In this section, the tunnels rise to emerge on the existing CP rail right of way south of 100th Avenue where , at the location of the proposed tunnel portals, the LRT tracks will be approximately 5 metres below the existing CP rail track level.

From the tunnel portals the LRT tracks rise at a constant grade and merge with the existing CP rail track level, between 98th and 99th Avenues, immediately north of the proposed Government Station.

2.3 Geological and Geotechnical Description in the Edmonton and the LRT System Area

Experience has shown that a knowledge of the geologic origin of glacial deposits can provide a framework for an analysis and interpretation of geotechnical data (May and Thomson, 1978).

Based on this experience, a summary of the geology of the Edmonton area is presented in this section. The geotechnical properties of the soil deposits in the vicinity of the ground and lining instrument installation are also presented in this section.

2.3.1 Geology of the Edmonton Area

The City of Edmonton is located in an area of low relief, with elevations ranging from 700 metres to 830 metres. The surficial material is a glacial lake sediment that caps a succession of Pleistocene deposits that infilled a preglacial valley system. The present North Saskatchewan river has eroded through the Pleistocene deposits and into the bedrock.

The pre-glacial channels were eroded into the Horseshoe Canyon Formation of the Edmonton Formation. The material composing this Formation is of the Upper Cretaceous age (140 to 190 metres thick) and consists of mudstones, clayshales and sandstones, deposited in brackish to fresh water of a shallow inland sea. The presence of bentonite in form of seams and admixtures in this Formation is ascribed to volcanic ash deposition.

After the uplift early in the Cenozoic, the bedrock surface was eroded by a well integrated river system (Kathol and McPherson, 1975). Portions of these pre-glacial channels were filled with late Tertiary sands and gravels termed Saskatchewan Sands and Gravels the thickness of which varies from 4 metres to 20 metres in the Edmonton area.

The advance of ice into the Edmonton area during the late Pleistocene laid down two till sheets. The lower unit, up to 6 metres thick, rests directly on the Saskatchewan Sands and Gravels. It was laid down by an ice lobe moving from somewhat west of north. The ice advance direction can

be evaluated from elongated pebbles with the longer axis oriented in the NW-SE direction. The lower till is characterized by its greyish colour and rectangular joint system. The upper till was derived from an ice lobe advancing from east of north. The ice reworked the upper metre of the lower till. The upper till, of brownish colour and with a columnar system of joints, is in some areas separated from the lower till by stratified sand lenses, called Tofield Sands. These lenses vary in size and shape, varying from contorted inclusions, less than 10cm in size, to more lenticular shaped bodies, continuous over distances in excess of 50 metres (May and Thomson, 1978). These sand lenses often are water bearing and might be a source of problems during tunneling activities. The two till layers have similar geotechnical properties the lower one being slightly stiffer than the upper one. Dejong and Morgenstern (1973) reported blow counts (SPT) higher in the lower till.

Above the upper till are silty clays, deposited in glacial Lake Edmonton. Within these sediments, large pieces of till-like material are found and have been termed diamicton by Westgate (1969) or lacustro-till by Kathol and McPherson (1975).

The lake deposits are covered in some areas by fill material, generally consisting of clay, mixed topsoil, sand and occasionally rubble.

Figure 2.2 presents a summary of the Quaternary geology of the Edmonton area.

Cenozoic	Quaternary	Holocene	Alluvium, Organic deposits, recent lake deposits.
		Pleistocene	Lacustrine sand, silt and clay, organic deposits, aeolian sand and silt, river Alluvium
			Till
			Sand and sandy gravel, some silt and clay
			Till
	Tertiary (undivided)	Saskatchewan gravels and sands	

Figure 2.2 QUATERNARY GEOLOGY OF EDMONTON AREA (AFTER MAY AND THOMSON, 1978)

A generalized east-west section through central Edmonton is shown on Figure 2.3.

2.3.2 Stratigraphy Along the LRT Track Centreline in the Area of the Present Study

The stratigraphy along the LRT track centreline, close to the region where the ground and lining instruments were installed is presented in Figure 2.4.

The boreholes indicated in Fig 2.4 have been reported by Thurber Consultants Ltd.(1980).

2.3.3 Geotechnical Properties of the Soil Surrounding the Tunnel

The results from laboratory tests carried out on undisturbed samples extracted from the boreholes drilled along the LRT South Extension are presented in Tables A1 to A6 in Appendix A. The location of the boreholes from which the samples were removed is given in drawing no. 14-31-1-6 in the report by Thurber Consultants Ltd.(opt. cit.)

The geotechnical properties of the Edmonton till have been extensively studied and a summary of some properties is presented in Table 2.1. The lab tests results presented in Tables A1 to A6 are summarized in the last column of Table 2.1.

Reference	Morgenstern and Thomson (1970)	DeJong and Harris (1971)	Thomson and Yacyszyn (1977)	El-Nahhas (1977)	Eisenstein and Thomson (1978)	LRT South Extension
Density (kN/m ³)	-	19-22	-	22	20.6-21.2	19.7-23.3
Natural Moisture Content %	12-22	11-19	15	12	12-20	10.1-28.7
Liquid Limit %	28-48	22-42	40	31	20-40	26.8-66.8
Plastic Limit %	12-22	9-20	20	15	12-20	13.6-22.7
% Clay	20-30	20	20-30	42	20-30	7.5-55
% Sand	-	42	40-50	27	40-50	9.0-47.5
Void Ratio	-	0.35-0.4	-	0.36	-	-
Degree of Saturation %	-	75-95	-	89	-	-
Undrained Strength (kPa)	345-828	140-240	140-245	-	140-245	94-662
Peak Angle of Shearing Resistance	-	-	37	-	-	-
Peak Cohesion (kPa)	-	28	-	-	-	-
Standard Penetration (blows/0.3 m)	-	60-150	-	-	40-60 some over 100	-

TABLE 2.1 - GEOTECHNICAL PROPERTIES OF EDMONTON TILL (AFTER THOMSON AND EL-NAHHAS, 1980)




Figure 2.3 GENERALIZED GEOLOGIC EAST-WEST CROSS SECTION THROUGH EDMONTON (AFTER KATHOL AND McPHERSON, 1975)




Figure 2.4 PLAN AND PROFILE FROM CENTRAL STATION TO 103 STREET (AFTER THURBER, 1980)

2.4 Detailed Description of the Construction of the Tunnel Sections

2.4.1 Tunnel Boring Machine

The tunnel sections of the existing north east line of the LRT System were excavated with the tunnelling boring machine (TBM) built by Lovat Tunnel Equipment Inc., Ontario, Toronto (Model M-246 Series 2100). The machine is owned by the City of Edmonton and a section illustrating its operation is presented in Figure 2.5.

The decision to use this TBM in the construction of the LRT South Extension was based on the convenience of using an equipment already owned by the City (initial investment, experienced operating crew) and on the successful construction of the existing tunnels of the subway system of the City of Edmonton.

The specifications of the TBM are given in Table 2.2 and more details will be given in the construction method description, later in this section.

2.4.2 The Lining System

The system chosen for the LRT South Extension tunnel is the same as that previously used in the construction of the tunnels of the existing lines. The system is a two-phase lining that comprises a primary, or temporary, and a secondary, or final, lining. As shown in Figure 2.6, the primary lining is composed of segmented steel ribs W6x25

BORE	: 6.27 m
CUTTING HEAD TORQUE	: 2412.5 KN.m
PROPULSION THRUST	: 22.24 MN
FRONT UNITIZED CONVEYOR	: 1.2m wide x 7.5m long
POWER	: 995 HP
ROTATIONAL SPEED	: 7 RPM
LENGTH	: 5.5m
MAXIMUM ADVANCE PER THRUST	: 1.68m
TOTAL WEIGHT	: 1174 KN

TABLE 2.2 - SPECIFICATIONS OF THE TUNNEL BORING MACHINE
(LOVAT MODEL M-246 SERIES 2100)




Figure 2.5 SECTION THROUGH THE SHIELDED MOLE (AFTER LOVAT TUNNELING EQUIPMENT INC.)




Figure 2.6 L.R.T. TUNNEL LINING SYSTEM

(yield point 300MPa), 1.22m centre to centre and 10x15cm timber lagging placed between the webs of successive ribs. The secondary lining consists of cast in place reinforced concrete and is planned to be installed after the construction of the second (south) tunnel .

Since, throughout this thesis, the measured ground and lining displacements and loads on the lining are taken before installation of the secondary lining installation, detailed description of lining installation will only refer to the primary lining.

2.4.3 Construction Procedure

The first phase of the tunnel construction (i.e. before the installation of the final lining) is discussed in detail, in the following paragraphs because its role in the tunnel lining and ground behaviour is of utmost importance.

The tunnel construction procedure basically consists of:

1. Ground excavation
2. Excavated material disposal
3. Material supply
4. Primary lining erection
5. Parallel activities

Each of these activities is described below:

Ground Excavation

The ground is excavated by the TBM described in Section 2.4.1. The cutting head of the TBM (Plate 2.1) is furnished



Plate 2.1 T.B.M. - CUTTING HEAD



Plate 2.2 EXPANDED LONGITUDINAL JACKS

with six spokes that give support to the slide gates. These doors are hydraulically operated and are designed to prevent any major flow of soil towards the face of the tunnel.

The advance of the mole is provided by a set of 20 hydraulic propulsion jacks located circumferentially around the perimeter of the mole. These jacks have an internal diameter of 20.32cm (8") and a maximum working pressure of 17237.5 KN/m² (2500 psi). The distance travelled by the mole, after one push is controlled by the depth of the jack pistons that goes up to 167.64cm (Plate 2.2).

The individual control of each jack makes possible the steering of the mole. The mole alignment is guided by a laser installed in the mezzanine level of the Central Station.

To reduce drag friction, the cutting profile of the mole is 19mm (in straight portions of the tunnel) larger than the diameter of the shield.

All the hydraulic systems and electric motors are controlled by the mole operator from the control panel shown in Plate 2.3. Individual controls open the front doors, turn the front wheel, advance the mole, activate the conveyor belt and expand or retract the rib expansion ring.

During the excavation, there is one person in charge of the face control. This person is responsible for stopping excavation whenever the behaviour of the soil at the face departs from normal.

Excavated Material Disposal



Plate 2.3 GENERAL VIEW INSIDE THE MOLE



Plate 2.4 CONVEYOR BELT STRUCTURE

The rotating cutting head delivers the soil to a conveyor belt system composed of two independent conveyor belts: the primary and the secondary. The primary conveyor is supported by the structure of the mole and delivers the soil cuttings to the secondary belt which is supported by a heavy steel structure pulled by the mole (Plate 2.4).

From the conveyor belt system, the excavated material falls into track mounted hopper cars that are pulled back to the Central Station by a small electric tractor.

The loading of the cars is a three man operation: the mole operator, controlling the conveyor belt system; the tractor driver who advances the car when a portion of it is filled and the third man stationed at the end of the secondary conveyor belt controlling the muck level inside the cars.

Material Supply

The basic material necessary for the first phase of the tunnel construction is the material for the primary lining erection (steel ribs and lagging) and for the tracks, used by the muck cars. This material comes from the eastern end of the North-East line, together with the empty muck cars, pushed by the subway trains. This material is brought to the face of the tunnel and unloaded by four men.

Lining Erection

After the mole advances a distance slightly longer than the required spacing between ribs, the longitudinal hydraulic propulsion cylinders are retracted and so is the

mounting ring that remains between the propulsion jacks and the last installed steel ribs. This ring is provided with a chain that runs around its circumference and is connected to an electric motor that rotates the chain.

The first steel rib section is placed at the invert of the shield and its ends are attached to the chain in the mounting ring. The chain is rotated by 90° and the second steel section is placed at the invert, attached to the chain in the mounting ring and has one of the ends connected to the first rib section. This procedure is repeated until the fourth rib section is installed. Sometimes it is necessary to cut a few inches off the fourth rib in order to make it fit within the space left between the first and the third rib sections. The four ribs are connected to one another through end plates with two sets of bolts and nuts for each joint.

After the four ribs are installed, the pieces of wood lagging are placed between the webs of the successive ribs as shown in Plate 2.5. The spacing left between the last two installed steel ribs rings is slightly larger than the timber length (121.9cm) to facilitate its installation in between the ribs. The lagging installation starts from the invert and proceeds to the crown and is done by four men.

After all pieces of lagging are installed the longitudinal jacks are activated to close the additional space initially left between the last two steel rings to facilitate the lagging installation.



Plate 2.5 LAGGING INSTALLATION




Plate 2.6 RIB EXPANSION

The expansion of the steel ribs follows the lagging installation. The rib expansion is done immediately after these are exposed to the ground with the help of the rib expansion ring. The rib expansion ring has its diameter increased by the expansion of four jacks that can be individually activated (Plate 2.6). Each expansion jack has an internal diameter of 15.24cm and a maximum working pressure of 10343 kN/m². In the north tunnel of the LRT South Extension, the two upper joints were expanded and a 15.24cm spacer was placed in each of them.

After the rib expansion, the excavation proceeds with the mole jacking against the lining, repeating the cycle described in this section.

Parallel Activities

Several activities occur simultaneously with those previously described in this section. Some of these parallel activities are listed below:

1. Extension of the power supply and telephone cable
2. Verification of the laser alignment
3. Installation of the steel clamps that provide guidance for the conveyor belt structure
4. Installation of the tracks for the muck cars
5. Extension of the ventilation plastic pipe to the head of excavation.

The activities related to the tunnel construction are in the flow chart presented in Figure 2.7.




Figure 2.7 SIMPLIFIED FLOW CHART OF THE TUNNEL CONSTRUCTION PROCEDURE

2.4.4 Rates of Excavation

As explained in Section 2.2.1, the excavation of the north tunnel, LRT South Extension, was planned to start from the west end of the Central Station and proceed to the 104th St Station. The excavation beyond the east end of the 104th St Station would depend on the end of the construction of the tangent pile walls, later incorporated to the structure of that station. The critical path on the construction flow chart of the first stages of the south extension construction was determined by the work done in the 104th St Station since, well before the beginning of the construction of this station, the mole was in position to start digging. The beginning of the tangent pile construction occurred in early March, 1981, whereas the mole was ready to start digging in late November, 1980. The distance to be excavated before the mole reached the 104th St Station is 166 metres. This distance could be excavated in approximately 10 days if the excavation proceeded with three shifts of eight hours per day. The choice of excavating at a slower rate of advance in this first stage of the tunnel construction was encouraging because it would benefit all parts involved in the tunnel construction. As far as the monitoring program was concerned, the decrease in the mole advance rate would permit a greater number of readings and give more time, if necessary, to solve eventual problems with instruments.

The beginning of excavation was January 19, 1981, with one crew working eight hours a day, and the 104th St Station

was reached on March 16, 1981. The tunnel construction was shut down until the completion of the tangent pile walls of this station.

The rates of excavation measured in the construction of the first stage of the tunnel construction described in this section can be obtained from Figure 2.8 where the position of the mole is plotted versus time.




Figure 2.8 MOLE POSITION VERSUS TIME

3. SOIL DISPLACEMENTS DUE TO TUNNELING

3.1 Introduction

Observational and instrumentation programs on tunneling are extremely helpful for an understanding of the ground response, for the evaluation of the stability of the opening of the adequacy of design and in the determination of the sources of eventual problems related to the tunnel construction.

Studies of the prediction of ground behaviour before and after tunnel construction have enhanced the importance of full scale field observations. Field observations have shown that uncharted ground conditions are common and the effects of the construction procedure on the surrounding soil is not easily predicted.

The monitoring of soil movements around tunnels in the City of Edmonton is relatively modest when compared to the tunneling activity in this area. El-Nahhas (1980) carried out a comprehensive observational program to measure soil movements in a small diameter, deep tunnel dug in the lower till of Edmonton. Eisenstein and Thomson (1978) monitored surface settlements at the construction of the North-East section of the LRT System. Thomson and El-Nahhas (1980) presented surface settlements due to the construction of a small diameter tunnel in the Horseshoe Canyon Formation, in Edmonton. The few data available on the ground displacement

around large and shallow tunnels in Edmonton and the necessity to accurately predict the effects of tunneling on the nearby structures along Jasper Avenue (Fig 2.1) made the ground instrumentation in the early stages of the construction of the LRT South Extension, north tunnel, of utmost value.

This chapter presents a brief description of ground displacement measurement techniques and a more detailed description of the instruments utilized in the LRT South Extension ground displacement monitoring program are presented.

3.2 Currently Available Ground Displacement Measurement Techniques

The movement of a point in the soil mass can be described by a displacement vector. This vector can be resolved into three perpendicular vectors: one vertical and two horizontal, parallel and perpendicular to the tunnel axis.

The knowledge of the displacement vectors within the soil mass during tunneling enables the construction of a spatial displacement field that is the main tool for interpreting the ground behaviour. Vertical and horizontal ground movements recorded in different stages of the tunnel construction provide data for the calculation of the three displacement vectors mentioned above.

3.2.1 Vertical Displacements

3.2.1.1 Surface Vertical Displacements

- Settlement Points

Vertical movements at the surface are obtained by comparing the elevation of a measuring point, anchored to the soil surface, to the elevation of a bench mark. The bench mark must not be affected by the tunnel excavation, must be installed outside the range of the construction influence and isolated from the overlying strata by casing.

The measuring points (settlement points) should be robust, well protected from damage, isolated from movements associated with other phenomena other than tunnel construction ones and solidly anchored to the soil in order to yield accurate and repeatable results.

There are many different designs of surface settlement points. Some of these designs are described by Burland and Moore (1973), USBR Earth Manual (1963) and Cording et al. (1975).

The accuracy of the elevation measurements is affected by the optical levelling. The surveying techniques can be improved by limiting the sight distances, balancing sights, carefully plumbing the rod, using a clearly marked staff as well as selecting stable turning points. Further improvements in accuracy can be obtained by locating the bench mark so that it is directly visible, by using invar rods and self levelling levels.

3.2.1.2 Subsurface Vertical Displacements

- Single-Point Extensometer

Simple deep settlement points are used in the measurement of settlements at various depths below the ground surface.

The requirements for the Single Point Extensometer are the same for the Surface Settlement Point, cited in the previous section. Special care should be taken to prevent the interference of the soil layer above the anchored tip in the readings.

Detailed description of the installation and design details of Single Point extensometers is given by Cording et al. (1975), El-Nahhas (1980), Hanna (1973) and Burland and Moore (1973).

Terzaghi (1938) introduced the "hose level" manometer to be used in locations where the installation of the "traditional" Single Point Extensometer, composed of a steel rod anchored to the soil, is not possible. The shortcomings and further developments of "hose level" settlement point are discussed in Hanna (opt.cit.).

- Multi-Point Extensometers

The same principle, proposed by Terzaghi in the "hose level" settlement points, can be applied to the measurement of settlements at several depths and positions by adding several cells to the manometer tube (Ward et al. 1968).

The commonest multi-point extensometers are those installed in a vertical borehole, called borehole

extensometers, where displacements related to the top of the borehole can be obtained at different depths of a vertical line.

According to Cording et al. (1975) borehole extensometers are basically divided in three types:

- Rod type
- Wire type
- Probe type

There are many drawbacks of the Wire type extensometers and most of them were reported by Hedley (1969) and Hansmire (1975). The inaccuracy of the wire type extensometer is ascribed to the friction existing between its components (wires, casing, anchors). Hansmire (1975) reported inaccuracy of up to 10mm in the Wire type extensometer.

The friction between the components is minimized in the rod type extensometer by individually encasing the rods with oil filled tubes (Cording et al., opt. cit.).

The friction problem present in the Wire and Rod extensometers does not exist in the Probe type extensometers. In the Probe extensometers there is no connection between anchored points in the borehole. Instead, a probe, that transmits signals to the surface when an anchor point is passed, is lowered down the hole. The depth of the probe, related to a reference point at the top of the borehole, is read from a calibrated cable connected to its top.

Three are the most commonly used Probe extensometers:

- the Radio transmitter probe extensometer
- the Impedance coil probe extensometer
- the Magnetic reed switch probe extensometer

In the first two types of extensometers the intensity of signals transmitted to the surface changes when the probe goes through a circular plate.

In the magnetic extensometer, the reed switch closes when in the presence of the axial magnetic field existing around the circular magnets anchored to the borehole walls and activates an indicator light or buzzer at the surface.

The use of magnetic extensometers has increased since it was first developed in the Building Research Station (Burland et al. 1972)).

The success of the magnetic extensometer for ground displacement measurements is ascribed to the simplicity of its construction and use, to its reliability and low cost.

More details concerning the Magnetic extensometer are given in Section 3.3.2.3.

3.2.2 Horizontal Displacements

3.2.2.1 Surface Horizontal Displacements

Cording et al. (1975) recognize four principal methods of measuring surficial horizontal movements.

1. offsets from a transit line
2. direct chaining with a steel tape or a portable

extensometer

3. electronic distance measuring

4. triangulation

Hanna (1973) also describes the photogrammetric method which can be used when an accuracy not better than 5mm is required.

All the methods mentioned above are described by Cording et al. (opt.cit.) and Hanna (opt.cit.).

The major use for measurements of surficial horizontal movements is to check the results obtained from slope indicators, described later in this chapter.

3.2.2.2 Subsurface Horizontal Displacements

- *Extensometers*

The Wire, Rod and Magnetic extensometers discussed in Section 3.2.1.2 can be used in the measurement of horizontal displacements provided an horizontal borehole can be drilled within the soil mass.

In tunneling, the installation of horizontal extensometers is often made from inside the tunnel which limits its utility because displacements ahead of the tunnel are difficult to obtain.

For the measurement of horizontal movements within the soil ahead of the tunnel face, the inclinometers or slope indicators, described in the next section are more commonly used.

- *Inclinometers*

Inclinometers or slope indicators are installed in the ground or structure to measure inclinations and change in inclinations at several levels which, when integrated over the length of the vertical line defined by the casing, yield horizontal displacements.

Inclinometers are divided into two major types:

- Portable borehole inclinometers
- Fixed borehole inclinometers

Irrespective of the inclinometer type, the bottom of the casing, or guide, must be anchored in the ground well below the area affected by the construction, thus ensuring that the bottom is fixed.

- Portable Borehole Inclinometers

Portable borehole inclinometers have been extensively used due to their relatively low cost, good quality results, easy installation and reading procedure.

It is basically composed of three units:

- casing
- sensing unit and cable
- electrical readout

The aluminium or plastic casings are provided with four vertical slots which are positioned at the quarter points of its inside circumference and serve as guide for the torpedo or sensing unit.

The sensing unit is usually provided with four wheels, two of which are spring-loaded which track within opposite grooves of the casing and align the sensing unit in stable

and repeatable positions.

The electrical readout supplies voltage to the sensing unit and displays the measured inclinations as numerical readings. A multi-wired, reinforced cable connects the readout unit to the sensing unit and provides an indication of depth through its colored neoprene markers, usually attached at 30.5cm spacings.

The various systems used in the sensing unit transducers differentiate the types of portable borehole inclinometers.

Cording et al. (1975) cited five different kinds of transducers:

1. pendulum actuated resistors
2. vibrating wire strain gauges
3. differential transformers
4. servo-accelerometers
5. photographic cameras

The commonest of these are the pendulum actuated resistors and, more recently, the servo-accelerometers that are less vulnerable to temperature effects and zero drift.

The inclinometers that use the pendulum actuated resistors, known as Wilson Slope Indicator (Wilson, 1962), convert inclinations into electrical measurements with the help of a conventional Wheatstone bridge circuit. A precision-wound resistance coil is subdivided into two resistances by a pendulum, that remains vertical, making up one half of the bridge. The remainder of the bridge and

associated circuitry is contained in the control box. The precision of this device is reported (Savigny, 1980) to vary between 1.7×10^{-4} to 8.3×10^{-4} (Precision given in units of shear strain or simply metres of deflection per metre of depth, defined by Gould and Dunnicliff, 1971).

A more accurate type of transducer is the servo-accelerometer. A servo-accelerometer is composed of a "proof mass" that is free to swing within a magnetic field. The proof mass is provided with a coil or torquer that allows a lineal force to be applied to the "proof mass" in response to a current passed through the coil. (Savigny, opt.cit.). The sensor is energized by an applied voltage and quickly stabilized in response to tilt by a change of current flow. The resulting voltage output is proportional to the sine of the angle of inclination. Precision between 0.4×10^{-4} to 1.3×10^{-4} has been reported in cases where the servo-accelerometer inclinometer has been used.

Savigny (opt.cit.) performed extensive lab and field tests with the Digitilt (servo-accelerometer type, made by Slope Indicator Co.) and reported the internal and external factors affecting its accuracy. Sensor axis rotation, casing spiral and temperature are some of the internal factors whereas recovery of equilibrium conditions around the casing, changing the degree of non parallelism of grooves are defined as external factors. More details concerning the Servo-accelerometer Inclinometer is given in Section 3.3.3.1.

- Fixed Borehole Inclinerometers

As opposed to the portable borehole inclinometers, the fixed borehole inclinometers remain in place in the borehole in order to continually monitor inclination at discrete points along the borehole.

The sensing units used in the torpedo of the portable inclinometers are also used in the fixed inclinometers.

The major advantage of the fixed borehole inclinometers is that the inaccuracy coming from "tracking" and repeatable positioning is eliminated. In most cases, the fixed sensors can be removed and re-used.

Some of the potential problems are the loss of accuracy if the sensor units are removed from the borehole for repairs and danger of buckling of the elements in the case of settlement of the casing.

3.3 Ground Displacement Monitoring in the LRT South Extension

3.3.1 Instruments Location

The importance of observational and instrumentation programs in tunneling is mentioned in the introduction of this chapter. The effectiveness of the ground instrumentation on the study of the effects of construction of the LRT South Extension, north tunnel, on the buildings situated nearby the excavation was favoured by the scheduled

LRT South Extension construction sequence. The construction sequence described in Chapter 2 states that the tangent pile walls of the 104th Street Station should be completed before the mole excavates through this station. As the critical path on the early stages of the LRT South Extension construction was governed by the end of the construction of the tangent pile walls of the 104th Street Station, there was a choice of either starting the tunnel excavation as soon as possible from the Central Station (Sta.200 + 0.0) and stopping the mole at the east wall of the 104th St Station (Sta.200 + 164.0) until wall construction finished or to time the beginning of excavation with the end of construction in order not to stop the mole.

The first alternative was chosen because the anticipation of the tunnel excavation would present time to analyse the data collected from ground displacement measuring devices and to verify whether special care would be necessary in the construction of the remaining portions of the tunnel west of the 104th St Station.

The ground instruments were located at the east side of the intersection of 102nd Street and Jasper Avenue (Fig 3.1). This intersection is situated approximately 60 metres away from the west wall of the Central Station and tunneling in this area is considered not to be affected by the proximity of the Station.

As shown in Fig 3.1, ground instruments were installed between Sta.200 + 43.6 and Sta.200 + 57.1, and has been




Figure 3.1 INSTRUMENTS LOCATION - PLAN VIEW

termed the "Instrumented Section".

The ground instruments, discussed later in this chapter, were located in positions that would enable the analysis of the strain field at the south side of the north tunnel, during and after its construction, to be carried out.

Figure 3.2 depicts a transverse section of the "Instrumented Section".

Detailed description of the design, installation, measurement procedure and field data related to the ground instruments used in the LRT South Extension program is presented in the following sections.

3.3.2 Vertical Displacements

Vertical displacements were measured close to the surface, at 3 metres depth, using settlement points and at several other depths with magnetic multipoint extensometers.

All readings presented in this section are referred to a bench mark, described below.

3.3.2.1 Bench Mark

Several Bench Marks (BM) were available at the site (Alberta Survey Control Monuments) but they were shallow and close to the excavated area or too far from the "Instrumented Section".

An ideal BM should be installed close to the "Instrumented Section", in order to minimize the number of




Figure 3.2 INSTRUMENTS LOCATION - TRANSVERSE SECTION

turning points and to keep the sight distance short (during levelling), and anchored in a region not affected by tunneling.

The depth and location of the BM installed for the LRT South-Extension ground monitoring program, indicated in Figures 3.1 and 3.2, fulfill the requirements mentioned.

Bench Mark Design Details

The details of the BM installed at 35m from the axis of the north tunnel are presented in Fig 3.3.

The BM is basically composed of a 7.93 metres long steel pipe (3.34cm O.D.) which has on its lower end a 15cm long nail, to provide good anchorage in the bottom of the hole. A pvc pipe (5.85cm I.D.) surrounds the steel inner pipe to prevent the interference of the soil layers above the anchored tip.

Bench Mark Installation

A 10.2cm diameter borehole was drilled with a solid auger to a depth of approximately 8 metres. The auger was retrieved and the steel pipe (3.34cm O.D.) lowered into the borehole. No sloughing of the borehole walls had occurred. By slowly applying downward forces to the top of the steel pipe, with the help of the drilling rig, the bottom of the steel pipe was pushed 15cm into the bottom of the borehole, ensuring a good anchorage.

The pvc casing was inserted into the borehole, surrounding the steel pipe. The void between the borehole walls and the pvc pipe was filled with clean sand.

The protection of the bench mark after installation was provided by a square steel plate (25.4cm x 25.4cm) fixed to the pavement.

3.3.2.2 Settlement Point

Nine settlement points (SP) were installed at different distances from the tunnel axis according to Table 3.1. These distances were chosen in order to obtain the complete shape of the settlement trough at surface due to tunneling.

As mentioned in Section 3.2.1.1, settlement points should be well protected from damage, isolated from movements associated with phenomena other than tunneling and solidly anchored to the soil.

Protection from damage was successfully provided by a steel plate cover. Movements associated with phenomena not related to tunneling might be the effects of the traffic and the frost penetration into the soil. Traffic problems were believed not to be of significant importance due to the good quality of the pavement but the frost penetration recorded in several locations in the City of Edmonton showed depths up to 2.4 metres where the snow drift had been removed due to traffic operations. This value (2.4m) was used as an upper boundary of frost penetration because most of the data analysed showed frost penetration no deeper than 1.8 metres.

By the time the decision to anchor the settlement points at 3.0 metres below surface was made, the settlement point SP4 had already been installed at 1.5 metre of depth.

SETTLEMENT POINT NO	DISTANCE FROM TUNNEL AXIS (m)	ANCHORAGE DEPTH (m)	INSULATION
SP2	27.7	3.0	PG
SP3	17.6 SOUTH	3.0	PG
SP4	10.4	1.5	N.I.
SP8	4.37	3.0	Z.
SP11	0.00	3.0	PG
SP13	6.80	3.0	PG
SP14	9.80 NORTH	3.0	PG
SP15	14.5	3.0	PG
SP16	34.7	3.0	PG

PG = Polystyrene foam guides
Z = Zonalite
NI = No insulation

TABLE 3.1 - SETTLEMENT POINTS - DETAILS OF INSTALLATION

Low temperatures inside the borehole where settlement points were installed, were prevented by the installation of polystyrene foam guides inside the pvc pipe (Fig 3.4) and by filling the void left under the protective plate with zonalite insulation.

Settlement Point Design Details

Figure 3.4 depicts the design details of the settlement points used to monitor surface vertical displacements.

The settlement points are basically composed of a steel rod (1.0cm diameter and 305cm long), and a pvc pipe (5.1cm I.D.). The steel rod has an end plate welded to it at 14.5cm from the lower end (Fig 3.4) and an aluminium cap attached to the upper end. This cap is provided with a cone shaped depression that fits the lower end of the levelling rod. The pvc pipe is installed around the steel rod to prevent the contact between the ground and the steel rod.

The protection of the settlement points against damage was accomplished with the installation of a square steel plate at the surface.

Settlement Point Installation

A 10.2cm diameter, 320cm long borehole was drilled and the inner steel rod inserted into the hole. The anchorage of the steel rod to the borehole bottom was accomplished by hammering its end plate (Fig 3.4) from the surface with a heavy steel pipe. The use of the heavy steel pipe enabled the application of the pushing force from the surface without touching the inner steel rod.




Figure 3.4 SETTLEMENT POINT - DESIGN DETAILS

The pvc pipe was inserted in the borehole, surrounding the inner steel rod and the void between the pvc pipe and the borehole walls filled with clean sand. Two cylindrical polystyrene foam guides (5.1cm diameter and 5.0cm long) were pushed into the pvc pipe with the inner steel rod passing through its centre (Fig 3.4) due to reasons discussed previously in this chapter. The middle hole passing through the polystyrene guides were slightly larger than the diameter of the inner steel rod and were carefully greased before insertion in order to avoid interference between the steel rod and the surrounding pvc pipe.

SP8 had the void between the steel rod and the pvc pipe filled with zonalite. Zonalite is a very light and deformable insulating material.

Settlement Point Measurement Procedure

The settlement points (SP) had their elevations compared to the elevation of the bench mark (BM1) through a very careful levelling technique. To ensure accuracy and repeatability of level measurements, sight distances were less than 10 metres. A special surveying rod, provided with a level bubble and 1mm divisions, and a self leveling optical level were used.

Gould and Dunnicliff (1971) suggest a maximum error of closure of 0.6mm for leveling procedures similar to the ones followed in the present study. Mendes et al. (1970) suggested a permissible error in elevation measurements, in Manicouagan 5 Dam of $0.01\sqrt{N}$ feet, where N is the number of

instrument set-ups. The limitation of the sight distance (between the level and surveying rod) results in an increase in the number of instruments set-ups. To level the settlement points of the LRT South Extension, north tunnel, four level set-ups were necessary:

1st set up: between SP2 and SP3

2nd set up: between SP8 and SP4

3rd set up: between SP13 and SP14

4th set up: between SP15 and Sp16

Level readings were recorded on the field data sheet presented in Figure 3.5. This field sheet is provided with columns that enabled the level calculations to be made immediately after the readings were taken.

Settlement Point Field Data

The ground instruments (settlement points, multipoint extensometers and slope indicators) were levelled three times before the beginning of the tunnel excavation. These readings were taken in November 29, and December 14, 1980 and January 18, 1981. Most of the SP elevations obtained from the zero readings had to be disregarded due to reasons discussed later in this chapter. The SP elevations, related to the bench mark BM1, obtained on February 01, 1981 were then taken as reference. At this date, the nose of the mole was 19.1 metres away from the closest ground instrument. It is believed that, at this distance from the face of the mole, no ground deformation due to tunneling had occurred.

SETTLEMENT POINT FIELD SHEET

DATE: TIME: TEMP: TUNNEL FACE AT: RECORDED BY:

BASE		READINGS				FORWARD RUN		READINGS				BACKWARDS RUN		FORWARD		BACKWARD		FORWARD		BACKWARD		ADJ	
S.P.		M	T	B	AV.	M	T	B	AV.	M	T	B	AV.	δ_{1-i}									
P ₁		1																					
		2																					
		3																					
P ₂		3																					
		4																					
		5																					
		6																					
		7																					
		8																					
		9																					
		10																					
		12																					
		11																					
P ₃		11																					
		13																					
		14																					
		15																					
P ₄		15																					
		16																					


NOTE: δ_{i-j}  IF i' BELOW j'
IF i' ABOVE j'

Figure 3.5 SETTLEMENT POINT FIELD SHEET

Table 3.2 depicts the difference in elevation between the settlement points and the bench mark BM1. The settlement point elevation data presented in Table 3.2 were obtained in sets of readings where the error of closure was always less than 1mm except those obtained in February 11, 1981 when the error of closure was 1.6mm. This increase in error of closure is probably due to the proximity of the mole to the "Instrumented Section"; settlements were probably taking place while settlement points were being levelled.

There were occasions that levelling had to be carried out during the evening. When this happened the levelling accuracy was found to be poorer than that obtained during daylight.

Figures 3.6 and 3.7 present the settlement point elevations plotted versus time and versus distance from the face of the mole, respectively. Individual settlement points elevations versus distance from nose of mole are plotted in Figures 3.8 to 3.16.

The combination of the data from Table 3.2 and Tables B1 to B4 (in Appendix B) made possible the construction of graphs where elevations were plotted versus distance from tunnel face.

Figures 3.17 and 3.18 present contour lines and settlement through transverse sections, respectively.

Discussions of the results presented in this section are presented in section 3.4.1.

VERTICAL DISPLACEMENTS (mm)

DATE (1981)	REF. DATE*	SP2	SP3	SP4	SP8	SP11	SP13	SP14	SP15	SP16
FEB 01	76	0.0	0.0	0.0	0.0	0.0	0.0	0.0	**	**
03	78	+0.55	+0.15	+0.20	+0.20	-0.10	+0.15	+0.35	+0.00	+0.00
05	80	+0.25	+0.00	+0.30	+0.30	+0.15	+0.40	+0.80	+0.55	+0.10
06	81	+0.30	+0.15	+0.25	+0.45	+0.70	+0.95	+1.40	+1.25	-
08	83	+0.05	-0.30	-0.45	+0.30	-0.25	-0.15	+0.20	+0.00	-0.05
09	84	+0.10	-0.30	-0.45	+0.25	-0.10	+0.30	+0.70	+0.35	+0.15
10	85	-0.05	-0.75	-1.15	+0.25	-0.55	+0.40	+1.15	+1.05	+1.10
10	85	-0.35	-1.05	-1.40	-1.10	-1.90	-0.85	-0.15	-0.35	-0.95
11	86	-0.40	-0.80	-1.35	-0.80	-1.60	+0.00	+0.70	+0.45	+0.65
11	86	+0.20	-0.45	-1.10	-1.45	-3.15	-0.45	+1.20	+1.00	+1.90
12	87	-0.75	-1.10	-2.10	-3.90	-5.35	-1.35	+0.30	+0.35	+0.10
13	88	-0.80	-1.05	-2.40	-4.00	-6.05	-0.90	-0.70	+1.05	+1.35
13	88	-0.80	-1.75	-3.30	-5.80	-8.25	-2.90	-	-0.55	-1.00
16	91	-1.10	-1.15	-2.10	-5.20	-7.75	-1.70	-0.25	+0.45	+0.40
17	92	-0.90	-1.35	-2.30	-6.10	-8.65	-2.05	-0.45	+0.05	+0.20
18	93	-0.75	-1.10	-1.80	-5.80	-8.40	-1.85	-0.40	+0.20	+0.70
19	94	-0.95	-1.05	-1.80	-6.00	-8.55	-1.90	-0.60	-0.05	-0.05
23	98	-0.80	-1.10	-1.50	-6.35	-8.95	-2.00	-0.65	+0.25	+0.65
26	101	-0.75	-1.45	-2.15	-7.20	-9.65	-2.90	-1.25	-0.50	+0.95
MAR 19	122	+0.30	-0.40	-1.40	-7.65	-10.0	-3.55	-1.60	-0.55	-

* Day Zero = NOV 16, 1980

** Readings disregarded FEB 03 = Zero reading for this point

TABLE 3.2 - SETTLEMENT POINTS - CHANGE IN ELEVATION




Figure 3.6 SURFACE SETTLEMENT VERSUS TIME




Figure 3.7 SURFACE SETTLEMENT VS DIST. FROM FACE OF MOLE




Figure 3.8 SETTLEMENT POINT SP2




Figure 3.9 SETTLEMENT POINT SP3




Figure 3.10 SETTLEMENT POINT SP4




Figure 3.11 SETTLEMENT POINT SP8




Figure 3.12 SETTLEMENT POINT SP11




Figure 3.13 SETTLEMENT POINT SP13




Figure 3.14 SETTLEMENT POINT SP14




Figure 3.15 SETTLEMENT POINT SP15




Figure 3.16 SETTLEMENT POINT SP16




Figure 3.17 SETTLEMENT TROUGH - CONTOUR LINES




Figure 3.18 SURFACE SETTLEMENT TROUGH - TRANSVERSE SECTIONS

3.3.2.3 Magnetic Multipoint-Extensometer

Three magnetic multipoint extensometers (ME) were initially installed to measure vertical displacements at several depths. Their location and the magnets positions are shown in Figures 3.1 and 3.2. They were installed on the south side of the north tunnel to measure ground deformations in locations not affected by the building to the north of the tunnel.

Another multipoint extensometer (ME17) was later installed further west, at the tunnel centreline due to reasons explained later in this section.


Multipoint Extensometer design details

The successful use of the magnetic multipoint extensometer in Edmonton is reported by El-Nahhas (1980).

The magnetic extensometer (ME) is a probe type extensometer basically composed of four components:

1. anchor points (magnet points)
2. guide casing(access tube)
3. probe (reed switch)
4. buzzer or light indicator

The anchor points (Plate 3.1) have a ring of magnets in the lower end and move with the material (soil or rock) they are embedded in, independent of other assemblies and the probe guide pipe (Figure 3.19). The guide pipe, a flush jointed pvc pipe, enables the reed switch probe to be lowered through each of the magnet ring assemblies. As the probe reaches the magnet field the reed switch, carried by



units: cm

Figure 3.19 MAGNETIC MULTIPOINT EXTENSOMETER - DESIGN DETAILS



Plate 3.1 MULTIPOINT EXTENSOMETER
ANCHOR POINT




Plate 3.2 MULTIPOINT EXTENSOMETER
INSTALLATION

the probe, closes and activates a buzzer or a light at surface. With a tape measure attached to the probe, the location of the magnet ring assemblies can be determined.

The anchor points are fixed to the borehole walls with four steel springs equally spaced around its perimeter (Figure 3.20).

The magnet rings, carried by the anchor points are composed of 14 ceramic magnets inserted between split steel washers (Figure 3.21). These washers concentrate and better define the magnetic fields of the magnet rings. Figure 3.22 illustrates the magnetic fields set up by the magnet rings. The buzzer (or light) is activated when the reed switch passes through any of the 3 magnetic fields. The absence of any of these fields indicates that at least two of the ceramic magnets were placed upside down (El-Nahhas, 1980). Ryzwk (1977) reported that the magnetic field is not altered with changes in temperature, with time, with mechanical action or when placed in any liquid short of a strong acidic solution.

The reed switch that sensed the magnetic field is encased in silicone and is carried inside a torpedo shaped weight, made of non-magnetic material (brass) and is heavy enough to ensure that the tape measure attached to it is kept taut during measurements.

Multipoint Extensometer Installation

Figure 3.23 illustrates the multipoint extensometer installation procedure.




Figure 3.20 MAGNETIC MULTIPOINT EXTENSOMETER - ANCHOR POINT





Figure 3.21 MAGNETIC MULTIPOINT EXTENSOMETER - MAGNETIC RING
DETAIL




Figure 3.22 MAGNETIC FIELDS AROUND THE RING (AFTER EL-NAHHAS, 1980)





Figure 3.23 INSTALLATION OF MULTIPOINT EXTENSOMETERS (AFTER EL-NAHHAS, 1980)

For the three multipoint extensometers installations, ME5, ME9 and ME10, 15.2cm diameter boreholes, 20 metres deep, were drilled. The continuous flight solid auger was withdrawn and the boreholes were filled with bentonite grout before or after the insertion of the access tubes (Fig 3.23). The joints of the access tubes (guide pipe) were cemented with water tight fast setting adhesive and sealed at the bottom with an end cap so no material would get into it. The bentonite grout, a mixture of 36kg of bentonite and 0.3m³ of water, used to fill the borehole was thick in order to prevent sloughing of the borehole walls.

Once the access pipe was in place and the borehole filled with bentonite grout the magnet assemblies (magnetic points) were individually pushed down the hole to the required depth with the help of a 5cm diameter pvc pipe (Plate 3.2).

After inserting the first magnetic point in ME9 it was realized that the steel springs were not wide enough to provide good anchorage. The diameter of the steel springs were increased the insertion of 2cm thick pieces of wood between the body of the magnetic points and the steel springs. After this modification, the magnetic points anchored tight in the borehole walls.

During the installation, most of the magnetic points had to be hammered down to force them through very tight portions of the borehole. When these tight portions were found to be close to the planned depth of installation the

magnets were left there, hence a good anchorage was ensured. The orientation of the steel springs of each magnet was changed in cases where the installation of the previous magnetic points in the same vertical resulted in a considerable increase in the borehole diameter (Fig 3.23)

For the multipoint extensometers, a special protection system was installed at the surface in order to protect the borehole from low temperatures and damage (Fig 3.19).

ME17 was installed at the tunnel centreline at Sta.200 + 133.5, west of the Instrumented Section, because ME10 had been damaged by the mole, no readings were taken in extensometer ME10. Extensometer ME17 was drilled to a depth approximately 1 metre above the tunnel crown to avoid damage.

The details of installation of the multipoint extensometers are depicted in Table 3.3.

Multipoint Extensometers Measurement Procedure

Readings of the multipoint extensometers are taken in two separate stages:

1. Levelling to the top of the access pipe to establish its elevation
2. Measurement of the depth of the magnetic points related to the top of the access pipe.

To improve the levelling accuracy, a special pvc cap, with a cone shaped depression machined in the middle, was installed on the top of the access pipe. The levelling of the access pipe was run simultaneously with the levelling of

ME	NO. OF MAGNETS	LOCATION	LOCATION FROM CL (m)	DATE OF INST.	DATE THE MOLE PASSED BY	MAGNETS DEPTH OF INSTALLATION (m)									
						MP1	MP2	MP3	MP4	MP5	MP6	MP7	MP8	MP9	MP10
5	9	ST200 +44.6	10.4	17-10-80	10-02-81	2.35	4.88	6.86	8.12	10.86	12.91	14.85	16.77	18.08	-
9	10	ST200 +43.4	4.3	16-10-80	10-02-81	1.44	2.93	4.89	7.01	8.93	11.16	12.89	15.61	16.92	18.37
10	8	ST200 +48.7	0	19-10-80	11-02-81	2.53	4.58	6.38	8.40	10.22	12.28	14.29	16.25	-	-
17	5	ST200 +133.5	0	03-03-81	10-03-81	3.01	4.20	5.24	6.69	7.59	-	-	-	-	-

TABLE 3.3 - DETAILS OF MULTIPOINT EXTENSOMETERS

the settlement points and slope indicators. Details of the levelling are described in Section 3.3.2.2.

The depth of each magnet point was measured with a tape measure connected to the reed switch probe. The probe was lowered into the access pipe and the depth of the upper and lower limits of the magnetic field 2 (Fig 3.22) of each magnetic point recorded in the field sheet presented in Figure 3.24. The difference between the depths of the upper and lower limits of the magnetic field 2 should be approximately constant for all magnetic points. This constancy in the difference between limits of the magnetic field 2 was used as a check of the quality of the readings.

Multipoint Extensometer Field Data

The data collected in the field was reduced by a computer program written by El-Nahhas (1980) and modified by the author.

Four sets of readings were taken for ME5, ME9 and ME10 before the beginning of the tunnel excavation. These readings were taken on November 16 and 29, December 14 and 22, 1980. The analysis of the data collected on these days allowed the verification of the repeatability of readings. The repeatability of the measurements of elevation of the top of the access tube was 1mm and the repeatability of the magnet points depth measurements was 0.5mm for the shallower magnets (less than 7 metres deep) and 1.5mm for the deeper ones. However the repeatability of readings in ME17 was 3mm which is worse than those mentioned above. ME17 was

MULTIPOINT EXTENSOMETER												
FIELD SHEET												
PROJECT : LRT TUNNEL												
DATE :												
READ BY: RECORDED BY:												
GENERAL COMMENTS :												
NO. MAGNET	M.E. * MOLE :				M.E. * MOLE				M.E. * MOLE			
	TIME : TO				TIME : TO				TIME : TO			
	TEMPERATURE :				TEMPERATURE :				TEMPERATURE :			
	READINGS		CENTRE	✓	READINGS		CENTRE	✓	READINGS		CENTRE	✓
	TOP	BOTTOM			TOP	BOTTOM			TOP	BOTTOM		
1												
2												
3												
4												
5												
6												
7												
8												
9												
10												
X	SURVEYING CORREC: (cm)				SURVEYING CORREC: (cm)				SURVEYING CORREC: (cm)			

Figure 3.24 MULTIPOINT EXTENSOMETER FIELD SHEET

installed at approximately 80 metres from bench mark BM1 resulting in a poorer repeatability in the measurement of the elevation of the top of the access tube.

Chatterji et al. (1979) reported reproducibility of magnetic extensometer readings varying between 2mm and 10mm. El-Nahhas (1980) reported an accuracy of 1mm for magnetic multipoint extensometers installed in Edmonton.

The major source of errors in the magnetic point depth measurements is the presence of two components attached to the reed switch probe namely, the tape measure and the lead connected to the buzzer or light at the surface. At greater depths these two components may get entwined yielding unrealistic depths measurements. Differences as great as 50mm in depth measurements, at depth greater than 30 meters, have been observed (Figueiredo and Negro, 1981) and ascribed to the reasons noted. Figueiredo and Negro (opt.cit.) proposed a new sensing system in which the presence of the lead connecting the sensing probe to the buzzer is eliminated. This elimination is possible by using a coupled oscillator that is activated by the reed switch and generates waves that are conducted through the steel tape measure to the surface.

The reduced data obtained from multipoint extensometers are presented in Figures 3.25 to 3.28 and in Figures B1 to B32 in the Appendix B. Figures 3.29 and 3.30 depict the transverse section of the settlement troughs at different depths.




Figure 3.25 MULTIPPOINT EXTENSOMETER ME5 - VERT. DISPL. X
DIST. FROM FACE OF MOLE




Figure 3.26 MULTIPPOINT EXTENSOMETER ME9 - VERT. DISPL. X
DIST. FROM FACE OF MOLE




Figure 3.27 MULTIPOINT EXTENSOMETER ME10 - VERT. DISPL. X
DIST. FROM FACE OF MOLE




Figure 3.28 MULTIPOINT EXTENSOMETER ME17 - VERT. DISPL. X
DIST. FROM FACE OF MOLE

ME : MULTIPOINT EXTENSOMETER
SP : SETTLEMENT POINT




Figure 3.29 SETTLEMENT AT 1.2M AHEAD OF THE FACE OF THE MOLE




Figure 3.30 SETTLEMENT AT 43M BEHIND THE FACE OF MOLE

Comments on the data presented in this section are made in Section 3.4.2 of this thesis.

3.3.3 Horizontal Displacements

3.3.3.1 Inclinator

Three inclinometers, or slope indicators were installed at three different distances from the tunnel axis as shown in Figures 3.1 and 3.2.

A SINCO Digitilt inclinometer, Model 50320, was used due to its adequate accuracy, precision and proven reliability (Savigny 1980).

Digitilt Inclinator - Specification

Two servo-accelerometer sensing elements, mounted at 90° to one another, are housed in a 92.7cm long probe. This probe (torpedo) has two pairs of wheels, 61cm apart. Each pair consists of one fixed wheel and one spring-loaded wheel located in diametrically opposite directions. The torpedo is connected to the readout unit by a 0.95cm (O.D.) neoprene-coated six-strand cable. This cable has coloured neoprene markers spaced at 30.5cm intervals.

The readout device, SINCO model 50306, contains a 6 volt rechargeable battery which operates continuously for up to eight hours at room temperature and supplies voltage to the sensor elements.

ABS-plastic casings (70mm O.D.x50mm I.D.) with four longitudinal grooves equally spaced were assembled in 3

metre long sections. The casing sections were joined by special SINCO couplings, Model 57512, which do not require cement and rivets for their installation. Water tightness is provided by two "O" rings located on the inner walls of the couplings. Two nylon strings run simultaneously through grooves machined in the inside wall of the couplings and outside wall of the casing to prevent the separation of the casings due to traction. The lower end of the deepest casing section was provided with a SINCO grout shoe. This grout shoe has a check valve that enables the grouting of the borehole from within the casing.

Specifications for the inclinometer mentioned above are shown in Table 3.4.

Inclinometer Installation

The 20.3cm diameter boreholes were drilled with a hollow stem auger, to a depth of 28 metres. The 3.0 metre long casing sections were assembled and inserted in the borehole through the hollow stem (Plate 3.3). No special care was taken to position the grooves in directions perpendicular and parallel to the tunnel axis. After the whole casing was installed the auger was withdrawn and the void between the borehole walls and the casing was grouted.

The boreholes were grouted through a pipe inserted beside the inclinometer casing. The grouting started from the bottom of the boreholes and the grout pipe was slowly withdrawn to ensure that its tip was always immersed in grout. The grout shoe was not used to avoid the risk of

SENSOR: Slope Indicator Company Model 50320

Sensitivity:	+ 0.0015 m per 30 m casing
Total System Accuracy:	+ 0.0076 m per 30 m casing
Wheel Base:	61 cm
Overall Length:	93 cm
Outside Diameter (not including wheels):	4.3 cm
Sensors:	Two 0.5 g closed loop force-balanced servo accelerometers
Operating Range:	0° to 30° (from vertical)

CABLE: Slope Indicator Company 1.07 cm O.D., six conductor with 0.16 cm stranded-steel core; waterproof neoprene cover with external marks at 0.31 m intervals.

INDICATOR: Slope Indicator Company Model 50306

Dimensions:	14.3 x 6.0 x 22.9 cm
Weight:	2.27 kg
Internal Power:	6V, 6 Ah
Charger:	External; 6 VDC
Operating Time on Batteries:	8 hours
Digital Display:	4 digits
Recording:	Manual

CASING: Slope Indicator Company ABS Plastic Casing & Couplings

Casing Length:	3.05 m
O.D.:	7.0 cm
I.D.:	5.9 cm
Coupling Length:	0.15 m
O.D.:	7.0 cm
I.D.:	6.5 cm

Table 3.4 INCLINOMETER SPECIFICATIONS (AFTER SAVIGNY 1980)



Plate 3.3 INCLINOMETER - INSTALLATION




Plate 3.4 INCLINOMETER - READINGS

discharging of grout inside the casing in the case of malfunctioning of the check valve. The grout was mixed on the site with a bentonite/cement ratio equal to 0.1 and a water/cement ratio equal to 1.4 (weight ratios). These weight ratios were chosen based on local experience.

The angle between the groove directions and the tunnel axis (angular rotation θ) shown in Figure 3.31(d) was measured at the surface with the aid of a compass. The spiral distortion of the grooves along the casing (Fig 3.31(c)) with respect to the groove alignment at the surface was obtained at 1.5 metre intervals with a SINCO spiral checking device. The "SPIRAL CORRECTION" column in Table 3.5 is the average angle between the "A" groove direction and the tunnel axis, measured anticlockwise from "A" to the tunnel axis. The "A" direction is the direction defined by the four wheels of the torpedo, parallel to the tunnel axis, and the "B" direction is perpendicular to the "A" direction.

The inclinometer casings were protected at the surface with a square (25.4cm x 25.4cm) steel plate.

More details of the three inclinometers are presented in Table 3.5.


Inclinometer Measurement Procedure

No readings were taken until 30 days after the inclinometers were grouted in order to allow a complete setting of the grout.

To facilitate cable maneuvering, a 0.6 metre long casing extension was assembled to the shallower casing

INCLINO-METER	LOCATION	LOCATION FROM TUNNEL ϕ (m)	DATE OF INSTALLATION	DATE THE MOLE PASSED BY	DEPTH OF DEEPEST READING (m)	NO. OF READING POINTS	SPIRAL CORRECTION	NOTES
SI6	ST200 + 43.4	6.4	16-10-80	10-02-81	26.8	44	21.90'	
SI7	ST200 + 48.7	4.3	17-10-80	11-02-81	26.8	44	3.18'	
SI12	ST200 + 43.6	0.0	19-10-80	10-02-81	26.8	44	2.32'	(DAMAGED 10-02-81)

TABLE 3.5 - INCLINOMETERS - DETAILS OF INSTALLATION



INSTALLATION STEPS
(a)




Figure 3.31 INSTALLATION OF SLOPE INDICATORS (AFTER EL-NAHHAS, 1980)

section. A removable pulley and clamp system was attached to the upper end of this casing extension and the probe inserted in the casing with the spring-loaded wheels facing west (Plate 3.4). The probe was initially lowered to a depth of 27.4 metres measured from the clamp, and left at this position for approximately 5 minutes to allow the sensors to achieve temperature stabilization. The probe was then lifted and readings taken in intervals equal to the distance between the upper and lower wheels (0.6 metre). The depth of readings were chosen to ensure that during readings, the wheels were never placed on couplings. Once the probe reached the surface it was rotated 180° (spring loaded wheels facing east) and the whole procedure just described was repeated to minimize the errors due to irregularities in the casing and instrument calibration.

The readout unit remained switched on during the entire operation and was kept at temperatures above 10° Celsius.

The readings were recorded on the field sheet presented in Figure 3.32.

Inclinometer Field Data

The data obtained from the inclinometers were reduced with the help of a computer program written by Savigny (1980). The program provides plots of horizontal displacements versus depth in any two desired perpendicular directions, and produces tables with the reduced displacements and the sums of the readings taken at each depth in both, "A" and "B" directions. These values, SUM A

SLOPE INDICATOR FIELD SHEET

PROSECT : LRT TUNNEL

DATE :

SI No. :

READ BY :CABLE CONTROL :

TEMP :

TIME: SENSOR INS.= START READ: END:

(+ 180') SENSOR INS = START READ END:

DEPTH (FT)	A		B		DEPTH (FT)	A		B	
	SPRING W	SPRING E	SPRING W	SPRING E		SPRING W	SPRING E	SPRING W	SPRING E
93					33				
91					31				
89					29				
87					27				
85					25				
83					23				
81					21				
79					19				
77					17				
75					15				
73					13				
71					11				
69					9				
67					7				
65									
63									
61									
59									
57									
55									
53									
51									
49									
47									
45									
43									
41									
39									
37									
35									

Figure 3.32 SLOPE INDICATOR FIELD SHEET

and SUM B, are helpful in the verification of the input data. A statistical analysis may be carried out with the "SUM" values and a standard deviation of the "SUM" values obtained in different sets of readings might reflect a change in the degree of non-parallelism of grooves or any malfunction of the instruments.

For the three slope indicators, three zero readings were taken before the tunnel excavation began. These zero readings are presented in Figures 3.33, 3.34 and 3.35. The repeatability of the inclinometers readings can be calculated from the zero readings. The rate, defined by Gould and Dunnicliff (1971), metres of deflection per metre of depth, can be used to check the repeatability. The repeatabilities calculated to points at the springline level (11.8 metres deep) are:

INCLINOMETER	CHANNEL A	CHANNEL B
SI 6	1.19×10^{-4}	1.3×10^{-4}
SI 7	2.79×10^{-4}	1.9×10^{-4}
SI 12	2.73×10^{-4}	4.5×10^{-4}

The inclinometer repeatabilities are within the range of repeatabilities specified by SINCO, 5.06×10^{-4} or $\pm 7.6\text{mm}$ per 30 metres of casing. The Digitilt Model 50320 had been previously used by El-Nahhas (1980) and Savigny (opt.cit.). They reported repeatability of $\pm 0.67 \times 10^{-4}$.

Figures 3.33 to 3.35 indicate that the three inclinometers used in the present study present erratic movements of points located close to the bottom of the





Figure 3.33 ZERO READINGS: SI 6 (6.4M FROM TUNNEL AXIS)





Figure 3.34 ZERO READINGS: SI7 (4.3M FROM TUNNEL AXIS)





Figure 3.35 ZERO READINGS: SI12 (TUNNEL CENTRELINE)

casing which might be a major source of error. The statistical analysis carried out with the values of SUM A and SUM B, explained earlier in this section, indicated no major change in the standard deviation values, reflecting the good performance of the inclinometers throughout the monitoring period. Figures 3.36, 3.37 and 3.38 depict the position of an initially vertical line, at different phases of the tunnel construction, for SI6, SI7 and SI12, respectively, when the readings taken on December 22, 1980, are used as reference.

Figures 3.39 and 3.40 depict the horizontal displacements, perpendicular and parallel to the tunnel axis, of points located at 11.58 metres below surface (approximately at the springline level).

Tables B33 to B44 in Appendix B present the inclinometer readings and reduced data.

Comments on the inclinometers data are presented in Section 3.4.2 of this thesis.

3.4 Discussion of Soil Movements

3.4.1 Surface Vertical Displacements

The settlement point elevations obtained on November 29, December 14, 1980 and January 18, 1981 were disregarded due to erratic movements of SP11, used as a "turning point" between the second and third set-ups (Section 3.3.2.2 -




Figure 3.36 SLOPE INDICATOR SI6 (6.4M FROM TUNNEL AXIS)




Figure 3.37 SLOPE INDICATOR SI7 (4.3M FROM TUNNEL AXIS)




Figure 3.38 SLOPE INDICATOR SI12 (TUNNEL CENTRELINE)




Figure 3.39 HORIZONTAL DISPLACEMENTS - PERPENDICULAR TO TUNNEL AXIS AT 11.58M BELOW SURFACE FOR SLOPE INDICATORS SI6, SI7 AND SI12




Figure 3.40 HORIZONTAL DISPLACEMENTS - PARALLEL TO TUNNEL AXIS AT 11.58M BELOW SURFACE FOR SLOPE INDICATORS SI6, SI7 AND SI12

Settlement Point Measurement Procedure). The erratic movements observed in SP11 were probably due to the presence of ice between the pvc pipe and the inner rod. The ice was probably restricting the free movement of the inner rod. In order to avoid the presence of ice inside the settlement points, they were filled with anti-freeze solution. It was noticed that the erratic movements ceased after this measure was taken.

The "loss" of the zero readings made the calculation of the repeatability of elevation difficult. The fluctuation of $\pm 1\text{mm}$ in the elevations of SP2, SP15 and SP16 might be an indication of the repeatability of the elevation readings because negligible change in elevation was expected to occur at these points. The heavy traffic and adverse climatic conditions during levelling of settlement points probably affected to a great degree the repeatability of elevation. Figure 3.18 shows that the construction of the north tunnel of the LRT South Extension should not affect the buildings located at 10 meters north of the tunnel axis.

The analysis of Figures 3.17 and 3.18 indicate that the surface settlement trough is not symmetric to the tunnel axis. This asymmetry might be due to the presence of inter-till sand pockets, non-symmetric to the tunnel axis or due to the presence of the buildings at the north side of the tunnel axis as opposed to open area to the south. The shallow foundations of these buildings (2.8 metres deep) might locally increase the soil stiffness resulting in

smaller settlements. The asymmetry observed in the surface settlement troughs indicates that these troughs do not fit the Gaussian distribution of surface settlements proposed by Litviniszyn (1956) and Peck (1969).

Hansmire (1975) reported that the surface settlement data obtained in the Washington D.C. Metro construction did not fit the probabilistic curve but would better fit a curve composed of two superimposed normal probabilistic curves.

The association of the shape of the settlement with a Gaussian curve is criticized by Mello (1981). The Gaussian distribution of surface settlements was obtained from a stochastic model proposed by Litviniszyn (opt.cit.) to simulate the subsidence in a loess due to local underground collapse. Mello (opt.cit.) states that Litviniszyn's model has no direct association with the change in the state of stress in the ground and corresponding strains and displacements associated with tunnel construction. Figure 13 of Mello's paper (opt.cit.) depicts several theoretical surface settlement distributions obtained from stress relief at a given depth. These settlement distributions are different from that proposed by Litviniszyn (opt.cit.).

The author believes that Peck's proposal for studying surface settlements based on Gaussian distribution is only justified as a first estimate of settlement distributions in the early stages of tunnel design where the detailed stratigraphy, the effects of construction procedure on the ground and the stress-strain behaviour of the soil under

different stress paths are not well known.

The longitudinal section of the surface settlement trough, along the tunnel axis, presented in Figure 3.12, indicates that negligible surface vertical displacements occurred ahead of the face of the mole and that the stabilization of these settlements occurred at approximately 15 metres from the face of the mole. The decrease in the rate of surface settlements at 15 metres from the face of the mole, 9 metres from the position where the lining is expanded, indicates that the effects of the lining expansion are not immediately noticed at the surface.

3.4.2 Deep Vertical Displacements

The analysis of the surface settlement data obtained from settlement points and surficial magnet points indicated that the difference in settlement obtained from the two instruments (settlement point and multipoint extensometer) is always less than 2mm.

Figures B1 to B32 in Appendix B indicate that deep vertical displacements stabilize at approximately 15 metres from the tunnel face. This had been also observed in the settlement point data.

Extensometer ME5 situated at 10.4m from the tunnel axis did not detect significant soil movements due to tunneling.

Figure 3.26 shows that, in ME9, the magnetic points anchored below the springline level did not move significantly throughout the tunnel construction whereas the

points located above the springline , detected uniform settlement after the tunnel passed by. The vertical straining detected by the magnetic points in ME9 was less than 0.1 per cent.

Figures 3.27 and 3.29 indicate that in ME10, the magnetic points installed close to the tunnel liner detected heave when they were within one tunnel diameter ahead of the mole. The measurements of lining deformation, Section 4.5.4.3, indicate that heave also occurred after the lining installation. No downward movement ahead of the mole was noticed in magnet points anchored above the tunnel crown which indicates that negligible loss of ground, defined in Section 3.4.4, occurs ahead of the tunnel face.

As discussed in Section 3.3.2.3, Multipoint Extensometer Installation, ME17 was installed approximately 80 metres from the Instrumented Section because, due to the damage of ME10, no ground movements were available above the tunnel crown after the mole passed a given section. The excavation of the tunnel through the section where ME17 was installed induced a roof failure. The upper portion of a sand pocket excavated by the mole caved in and left a void above the tunnel crown of approximately 1.5 cubic metre and 1.5 metre high. The magnetic point MP5 in ME17 was anchored in the sand pocket that caved into the tunnel.

The data recorded from ME17, presented in Tables B28 to B32 in Appendix B indicate that large vertical extension due to roof failure propagated up to 3.4 metres to 4.5 metres

above the tunnel crown. The last reading in ME17 was taken three days after the mole stopped digging, close to the east wall of 104th St Station. This occurred when the face of the mole was 24.9 metres from ME17. At this distance from the mole the magnetic point located 3.0 metres from surface, in ME17, had settled 11.4mm whereas SP11, in the Instrumented Section, at the same distance from the face of the mole, had settled 8.4mm. This difference in surface settlements measured at the tunnel centreline in SP11 and M17 is probably due to the roof failure that occurred at ME17 and did not occur in the Instrumented Section.

The data obtained from ME17 cannot be analysed together with the data gathered in the Instrumented Section because, due to the failure of the roof, ME17 did not reflect the standard behaviour of the ground surrounding the tunnel.

3.4.3 Deep Horizontal Displacements

The difficulty in analysing the data presented in Figures 3.36 to 3.38 led to the plots presented in Figures 3.39 and 3.40. No trend of horizontal movements can be noticed in Figures 3.36 to 3.38 because the measured movements were small compared to the accuracy of the inclinometer. Figures 3.39 and 3.40 depict the soil displacements in a horizontal plane located at 11.58 metres below surface, approximately at the tunnel springline level.

The plots of horizontal displacements perpendicular to the tunnel axis at the springline level, in Figure 3.39,

indicate that points located at 1.2 metre and 3.3 metres from the liner moved approximately 3.0mm and 2.0mm, respectively, towards the tunnel axis. These movements started to occur at 3.0 metres ahead of the face of the mole and stabilized at approximately 6.0 metres from it, where the primary lining was expanded against the ground.

The plots of horizontal displacements parallel to the tunnel axis, at the springline level, in Figure 3.40, indicate that a point located at the tunnel axis and at 4.3 metres from it moved 3.5mm towards the face of the mole before it passed by the inclinometers. This movement was only 1.0mm for a point at 6.4 metres from the tunnel axis. After the mole passed by the inclinometers, the points that were initially moving eastwards, against the tunnel advance direction, started to move westwards, in the tunnel advance direction, going back to their initial position. The soil movements in the direction parallel to the tunnel axis indicate that analytical studies of tunnel behaviour based on plane strain conditions do not reflect reality. The fact that the points in the ground move in the direction parallel to the tunnel axis during tunneling and go back to their initial position after the mole passes by enhances the fact that a study of the final displacements about the tunnel without taking into account the "strain history" of the soil is not acceptable.

3.4.4 Loss of Ground Around Tunnels

Hansmire (1975) defined loss of ground as the sum of the soil displacements normal to, and over a unit area of, the tunnel perimeter.

The loss of ground takes place at three different positions along the tunnel excavation:

a) Ahead of the face of excavation (face loss)

The face loss is the volume of soil excavated at the tunnel face in excess of the theoretical excavation volume.


b) Along the digging machine (shield loss)

The shield loss is the sum of soil displacements, perpendicular to the tunnel profile, immediately about the shield from the time the leading edge of the shield passes a section until the shield tail passes that section. Loss of ground due to the shield results from plowing and yawing of the shield and any displacement created by changes in the cross-sectional area of the shield.

c) Behind the tail of the shield (tail loss)

The tail loss happens because the tunnel lining insufficiently replaces the cross sectional area of the tail of the shield. The losses due to the flexibility of the lining are considered tail losses and are usually negligible.

A comprehensive study of ground movements around tunnels developed by Hansmire (opt.cit.) is based on the model presented in Figure 3.41. Hansmire (opt.cit.) proposed the following equation in his study:



DEFINITION OF SYMBOLS AND UNITS

V_s	VOLUME OF SURFACE SETTLEMENT (M^3/M OF TUNNEL)
V_b	VOLUME OF BOTTOM DISPLACEMENT (M^3/M OF TUNNEL)
$V_{lat}^{(1)}$	VOLUME OF LATERAL DISPLACEMENT (M^3/M OF TUNNEL)
V_l	VOLUME OF LOST GROUND (M^3/M OF TUNNEL)
$V_{long}^{(1)}$	VOLUME OF LONGITUDINAL DISPLACEMENT (M^3)

Figure 3.41 THREE DIMENSIONAL GROUND MOVEMENTS ABOUT TUNNELS
(HANSMIRE, 1975)

$$\Delta V = V_s + V_{lat} + V'_{lat} + V_{long} + V'_{long} + V_b - V_l$$

3.1

where

ΔV = soil volume change. ΔV is the sum of the volumetric change of the elements located outside the nominal limits of the tunnel excavation. It takes place due to stress-strain-volume changes in the presence of stress changes in the soil mass due to tunneling.

V_s , V_{lat} , V'_{lat} , V_{long} , V'_{long} , V_b and V_l are defined in Figure 3.41.

The model proposed by Hansmire (opt.cit.) enables an analysis of the development of ground volume changes at several stages of tunnel construction based on soil instrumentation data to be carried out.

For the north tunnel of the LRT South Extension, the detailed study of the ground volume changes at different stages of the tunnel construction was not possible because no ground movement data was available in the region between SI7 (1.2 metre from the springline) and the tunnel axis after the mole passed a section. However, the ground volume changes can be calculated for the final displacement situation if the following assumptions are considered:

a) The lateral and lower boundaries in Figure 3.41 are considered far from the tunnel. In this case, $V_{lat} = V'_{lat} =$

$V_b = 0.$

b) For the final displacement situation, the volume of longitudinal displacements, V_{long} and V'_{long} , are considered zero. Actually, there are volume changes in the longitudinal direction but they are expected to be small. In the tunnel excavated for the Washington D.C. Metro, the maximum longitudinal volume changes were less than 5% of the volume of lost ground.

With these assumptions, equation 3.1 becomes:

$$\Delta V = V_s - V_l \quad 3.2$$

For the north tunnel, LRT South Extension, the volume of the surface settlement (V_s) calculated at 37.6 metres away from the face of the mole is $0.14\text{m}^3/\text{m}$ or 0.46% of the nominal tunnel area.

The volume of lost ground (V_l) is assumed to be the difference between the volume defined by the cross-sectional area of the excavated face and the cross-sectional area of the expanded primary lining. It is assumed, then, that there is negligible loss of ground ahead of the mole, there is no shield loss due to plowing and yawing of the shield and the soil fills the voids around the lining. With these assumptions, V_l can be calculated: $V_l = 0.73\text{m}^3/\text{m}$ or 2.42% of the nominal tunnel area. The values of V_s and V_l are substituted in Equation 3.2 and $\Delta V = 0.59\text{m}^3/\text{m}$ or 1.96% of

the tunnel nominal area. This value of ΔV indicated that an average increase in ground volume occurred around the LRT South Extension tunnel. This increase in volume of ground is similar to those measured by Hansmire (1975), in dense cohesionless soil: $0.32\text{m}^3/\text{m}$ to $0.77\text{m}^3/\text{m}$. In shallow tunnels, once the zone of disturbance, or the zone where ground plasticity occurs, reaches the ground surface, no further significant volume change takes place and the further increase of volume of lost ground is directly related to the downward movement of the block of soil above the tunnel. The verification of whether or not the "zones of disturbance" reached the surface is not possible with the data presented in this chapter. However, the data from load cells and steel lagging presented in Chapter 4 of this thesis indicate that only a small fraction of the overburden was being supported by the lining. This might be an indication that the "zone of disturbance" did not propagate to the surface.

The change of volume that takes place in the soil mass beside the tunnel can be evaluated through the relationship between V_{lat} and V_s , indicated in Figure 3.42. V_{lat} can be computed from the soil displacements measured by an inclinometer (SI6 or SI7). For no volume change in the soil, the lateral volume of soil displaced along a vertical plane, as shown in Figure 3.42, would produce an equal settlement volume at the ground surface.

Figure 3.43 depicts the values of V_{lat} and V_s , indicated in Figure 3.42, calculated with the data obtained




Figure 3.42 RELATIONSHIP OF SURFACE SETTLEMENT VOLUME TO LATERAL DISPLACEMENT VOLUME (AFTER HANSMIRE, 1975)




Figure 3.43 COMPARISON OF SETTLEMENT AND LATERAL DISPLACEMENT VOLUMES

from SI6, SI7 and surface settlement points. The variation of V_{lat} between February 06 and February 26 and February 01 and February 23, 1981, were chosen for SI7 and SI6, respectively, based on the inclinometer data presented in Figure 3.39.

Figure 3.43 indicates that a small portion of the ground volume increase (1.7% of ΔV), evaluated earlier in this section takes place beside the tunnel liner. This indicates that the volume changes due to LRT South Extension tunnel construction are restricted to the area above the tunnel crown.

3.5 Summary and Conclusions on Ground Displacements

This chapter reviewed the techniques most commonly used in measuring ground displacements around tunnels.

Details of the design, installation and measurement procedure of the instruments used to monitor ground displacements around the north tunnel of the LRT South Extension were presented.

From the analysis of the field data, the following was observed:

1. The surface settlement trough is not symmetric about the tunnel axis and does not fit the Gaussian distribution of surface settlements.
2. The maximum surface settlement was 10mm and occurred above the tunnel axis.

3. A small portion of the final vertical and horizontal measured displacements took place ahead of the face of the mole.
4. The magnetic extensometer ME5 indicated that no measurable vertical movements occurred 10.4 metres from the tunnel axis.
5. ME9, 1.2 metre from the springline, detected negligible vertical movements at points located below the springline level.
6. ME10, at the tunnel centreline, detected heave ahead of the mole in the magnet points close to the liner.
7. The final horizontal displacement in the direction perpendicular to the tunnel axis at the springline level was 3mm and 2mm at 1.2 metre and 3.3 metres, respectively, from the tunnel lining, directed towards the tunnel axis.
8. A ground volume increase of 1.96% of the tunnel nominal area was obtained. The inclinometers and surface settlement data indicated that over 96% of this volume increase takes place above the tunnel crown.

4. LINING LOADS AND DISPLACEMENTS

4.1 Introduction

The tunneling activities in the City of Edmonton have increased in the last decade with the growth of the city. Tunnels have been constructed for rapid transit systems and for storm and sanitary sewers.

The increase in tunneling activities has resulted in the need for improved design methods because the available methods, discussed in Chapter 5 of this thesis, do not take into account some of the details of construction and the variability of natural deposits.

Full scale field measurements have been carried out in order to verify the design methods and to provide an empirical evaluation of the behaviour of tunnels constructed in the glacial till and the Upper Cretaceous clay-shale of the Edmonton area. Soil movements and loads and deformations of the lining have been measured.

In this chapter, only the behaviour of tunnel linings is discussed.

Einsenstein et al. (1977) and Einsenstein and Thomson (1978) studied the normal loads acting on the primary lining of the north tunnel of the LRT North-East line, Edmonton, based on electrical strain gauges bonded to the steel ribs. From this study it was concluded that the determination of loads from strains measured in the strain gauges is complex

and it proved difficult to separate stresses from the mole jacks from those from the soil mass.

El-Nahhas (1977) and Thomson and El-Nahhas (1980) reported lining distortion and results from pressure cells installed at the interface between the soil and the wood lagging of the temporary lining of two small diameter, deep tunnels constructed in Edmonton. They concluded that the results from the two pressure cells were of little value because the soil closing on the timber was unknown.

El-Nahhas (1980) compared the performance of two lining systems (rib and lagging and precast concrete segments) of a small diameter, deep tunnel, constructed in the glacial till of Edmonton. In this study, the precast segmented lining was extensively instrumented, with load cells and embedded strain gauges whereas the rib and lagging lining had loads evaluated from four vibrating-wire strain gauges welded to the steel ribs.

From the field instrumentation carried out in tunnels constructed in Edmonton, it can be concluded that the accurate magnitude and distribution of stresses acting on the rib and lagging lining system has not, as yet, been obtained. The lack of information concerning the behaviour of the rib and lagging lining systems led to the comprehensive instrumentation of the primary lining of the north tunnel of the LRT-South Extension.

In this chapter, the methods of determining the magnitude and distribution of stresses acting on tunnel

liners are discussed in Sections 4.2 and 4.3. The instruments used in the study of the behaviour of the LRT primary lining and the discussion on the results from this instrumentation are presented in Section 4.4.

The data presented in this chapter is used in the study of soil structure interaction presented in Chapter 5.

4.2 Direct Pressure Measurement

4.2.1 Pressure Cells

There are two basic types of earth pressure measurement possible with pressure cells. One is the measurement of total pressure at a point within a soil mass (often used in earth dams) and the other is the measurement of total pressure or contact pressure against the face of a structural element (termed a boundary cell). The latter has been used to measure radial soil pressures acting at the tunnel liner interface and has yielded unsatisfactory results (Cording et al., 1975).

One reason for the poor performance of boundary cells is the difficulty in designing a pressure cell that behaves in a manner similar to the soil structure interface where the cell is installed. This similarity must include stiffness, wall roughness and simultaneous activation of cell pressure and instrumented structures.

Even in cases where these requirements are met, the scale effects may adversely affect the resulting interpretation: the contact pressures may not be uniform over the areas of contact of the pressures cell (15 to 20cm diameter). Local variation of soil contact pressures on the tunnel lining (due to ground irregularity, construction method, etc.) can cause a large variation in measured pressures. Difficulties in obtaining reliable results from boundary cells are reported by Cording et al (1975); Thomson and El-Nahhas (1980) and Delory et al (1979).

4.3 Indirect Pressure Measurement

The pressure distribution on a lining, obtained from the measurement of thrusts, moments, shear forces and deformations can be used to evaluate the lining safety. These values can be obtained from:

- strain gauges: installed in or on the lining
- load cells: usually installed in joints of the lining
- lining deformation measurements

4.3.1 Strain Gauges

Strain Gauges are devices that measure displacements over a known length.

The commonest strain gauges in geotechnical engineering are:

- electrical resistance strain gauge

- vibrating wire gauge
- mechanical gauge
- photoelastic strain gauge

Descriptions of the principles of operation, construction details, advantages and disadvantages of each gauge are extensively discussed in the literature on instrumentation (e.g. Cording et al 1975). Table 4.1 summarizes the most important features of some strain gauges (Cording et al , opt.cit.)

By installing strain gauges across the thickness of the lining one can obtain the strain distribution, and (once the elastic properties of this lining are known) the stress distribution within the instrumented section. Normal forces and bending moments can be back calculated from this stress distribution and the safety of the structure can be evaluated.

Strain gauges can be installed within the lining (concrete liners) or attached to the surface of the structural element (steel ribs in the rib and lagging system on steel segments in the liner plate system).

Strain gauges embedded in a concrete lining will not be discussed in this report. The present study, concerns the behaviour of primary lining (rib and lagging) used in the LRT South Extension tunnel.

The strains and stresses in a rib and lagging lining can be measured in either or both of the two structural members composing the system.

Type	Strain Sensitivity, Microstrains	Gage Length, Inches	Typical Range, Microstrains	Advantages	Limitations and Precautions	Reliability
Bonded electrical resistance gage	2-4	.008-6	20,000 - 50,000	Small size, low cost. Temperature compensation available.	Errors due to lead wire and circuit resistance changes unless compensated. Long term stability may be poor due to cement creep. Meticulous installation procedure. Difficult to waterproof.	Poor - Fair
Encapsulated, unbonded, electrical resistance a) Alltech weldable gage b) Carlson gage	2-4	1 - 6	20,000	Factory waterproofing. Welded surface mount. Temperature compensation available.	Errors due to lead wire and circuit resistance changes unless compensated.	Fair - Good
	4	8 - 20	700 tension, 1400 compression	Factory waterproofing. easy to install. Long experience record.	Errors due to lead wire and circuit resistance changes unless compensated. Small range. Temperature correction required.	Good
Vibrating-wire gage	1-2	4 - 14	600 - 7,000	Not as affected by lead wire resistance changes. Easy to install. factory waterproofing. Long experience record. Robust, reusable.	Small range. Temperature correction required.	Good
Mechanical gage	5-10	2 - 80	10,000 - 50,000	Simple, low cost, waterproofing not required.	Requires skill in reading. Can not be read remotely.	Excellent
Scratch gage	30	Variable, up to 30 in. or more.	40 - 1000	Self-contained, automatic recording, simple.	Limited accuracy and range.	Fair
Laser gage	0.2	6	6000	Rugged and simple.	Can not be read remotely.	

Table 4.1 STRAIN GAUGES - TYPES AND FEATURES (AFTER CORDING ET AL, 1975)

The steel ribs are the most commonly instrumented components. The variation found in the mechanical and geometric properties of the ribs is much less than that found with the timber lagging elements.

In order to obtain stress distributions across the "H" sections, usually chosen for the steel ribs, strain gauges have to be attached to both, web and flanges. Figure 4.1 illustrates the location of strain gauges used in the rib instrumentation of the north tunnel of the north-eastern section of the LRT system in Edmonton. Stresses in steel ribs were also measured by El-Nahhas (1980 and 1977) from strain gauges on the two flanges. Experience with strain gauges bonded to steel ribs is quite discouraging. Many factors lead to the poor performance of strain gauges bonded to steel ribs:

- In tunnels where ribs are subjected to longitudinal loads from the TBM, the strains induced during jacking may exceed and hence mask those from ground loads
- Flanges are subjected to secondary bending distortion effects
- Steel ribs are likely to be subjected to eccentric or torsional loadings
- The protection cap covering the strain gauge may induce a local strain field distortion.

All these factors combine to create a complex analysis of strain distribution across the rib section. It is




Figure 4.1 LOCATION OF STRAIN GAUGES ON RIB CROSS-SECTION -
LRT NORTH-EAST LINE (AFTER EISENSTEIN ET AL, 1977)

difficult in such cases to separate the sources of deformation of the steel ribs. For geotechnical engineering research purposes, the loadings due to ground pressure are of major interest and can hardly be quantified given the preceding factors.

The wooden lagging of the primary lining is seldom instrumented due to the variation in mechanical and geometric properties of the timbers. To avoid this variability one can substitute for some pieces of wooden lagging, other pieces made of another material that present more uniform properties (e.g. steel). The piece of lagging that replaces the timber must have similar properties to the original timber lagging otherwise problems similar to those described for pressure cells will be created. The installation of strain gauges on these special pieces of lagging allows the evaluation of loads supported by these pieces.

4.3.2 Load Cells

Load cells are often used in the monitoring of loads in tunnel liners in order to minimize the difficulties in interpreting the data, as described in Section 4.3.1. Load cells also simplify the installation procedure since they are easily transported and installed.

Load cells are structural members of known mechanical properties, with strain gauges attached to measure the deformation of the element under load. The type of strain

gauge attached to the load cell defines the load cell type

- mechanical load cells
- photoelastic load cells
- electrical resistance load cells
- vibrating wire load cells

Load cells have been extensively used in segmented liners. The load cells are installed between segments, yielding no significant change in the original liner behaviour. Load cells can also be specially installed within a segment of the liner. This procedure facilitates the installation at the usually congested face of the tunnel as no deviation from the normal construction sequence occurs since this segment will have been previously prepared. However, the installation of the load cell within a segment complicates the load cell design, since its presence must not alter the mechanical behaviour of the segment. This is not easily achieved.

Usually Load cells are designed to carry only normal loads which can be achieved by providing spherical seats for the structural members (usually part of a steel sphere). The results from this type of load cell will reflect the behaviour of the lining only if the position, where the device is installed, originally carries only normal load.

Load cells designed to measure shear forces in addition to normal forces are also available. One type of these load cells is described by Kovari et al. (1977).

4.3.3 Lining Deformation

Another means of obtaining the ground stress acting on the lining is the measurement of the lining deformation.

The deformed shape of the lining can be used as a displacement boundary in any numerical analysis in which the soil-structure interaction is analysed (back analysis from known displacements)

Two of the commonest means of measuring lining deformation are described in the follow sections:

4.3.3.1 Rod or Tape Extensometer

This is an easy, accurate and relatively inexpensive way of measuring the distance between two points of the lining. Many types of extensometers have been designed and details concerning them are considered by Burke (1957), Obert and Duvall (1967), Cording et al (1975) and El-Nahhas (1977).

Tape extensometers consist of a micrometer or mechanical dial gauge connected to a rod or series of rods of known length, or to a spring loaded tape measure, kept under constant tension during readings. Measurements are taken by attaching the tape extensometer between the measurement bolts, fixed to the inside of the lining and adjusting the rods or the tension of the tapes to the required load.

The deformed shape of the tunnel can be determined by taking readings between several bolts spaced on the tunnel

lining in a plane normal to the tunnel axis. The larger the number of relative displacements measured between measurement bolts, the better the definition of the deformed lining shape.

4.3.3.2 Integrated Measuring Technique

Kovari et al. (1977) proposed a technique of measuring lining displacements in order to obtain the normal loads and bending moments acting in the lining and also to obtain the external loading (radial and tangential). This procedure is termed Integrated Measuring Technique and yields reasonable results despite some simplifications inherent in the method such as deformations occur only in the plane of the monitored ring and small deformation theory. Kovari et al. (opt.cit.) reported that the deformation of the Gotthard Road Tunnel liner were monitored with the aid of three displacement measuring devices (curvometer, deformer, distometer-ISETH), as proposed by their method. The loads predicted by the Integrated Measuring Technique were compared to those obtained from load cells installed in the same ring of the liner. This comparison showed the satisfactory performance of the method proposed by Kovari et al. (opt.cit.)

4.4 The L.R.T. South Extension Tunnel Liner Instrumentation

Loads and deformations in the primary lining were measured in the early stages of construction of the LRT tunnel in order to optimize the initial liner design and to study the soil-structure interaction.

The selection of instruments used in the monitoring of liner loads and displacements of the LRT tunnel was based mainly on previous experience in tunneling instrumentation at the University of Alberta.

The interaction between the steel ribs and wood lagging was investigated because little is known about this interaction and because it affects the construction costs and lining design to a significant extent. The study of the rib and lagging interaction was accomplished with the instrumentation of twelve steel pieces of lagging and eight load cells. Two load cells were installed on each of four steel rib rings. Convergence of other four ribs was measured with the tape extensometer and eyebolts described later in this chapter.

Pressure distribution acting on the lagging was obtained by measuring strains on the internal face of 12 pieces of hollow steel lagging that were designed to have the same bending stiffness of the wooden lagging in order to simulate its normal behaviour.

Details of each proposed instrument, including calibration tests, installation, measurement procedure, field data and data reduction is presented in the following

sections of this chapter.

4.4.1 Load Cells

The choice of which method should be used to measure loads in the steel ribs was based on an analysis of the lining installation procedure. As explained in the description of the construction method (2.3.1), the four segments, composing one ring of the steel rib, are initially erected within the mole shield and kept together by two loose sets of bolts and nuts at each joint. The steel rings are exposed to the soil as the mole advances and the expansion ring (jacks) are positioned and aligned. The bolts and nuts from the upper joints are removed to allow full expansion of the joints. The expansion spacers (15.24cm long) are then placed between the end plates of the expanded joints. The bolts and nuts are then properly placed and tightened with no particular predetermined torque. By leaving the bolts and nuts relatively loose (hand tightened) the joints become free to rotate and to move radially.

The substitution of a joint spacer by a load cell designed to have the same thickness as the rib spacers and designed with spherical load caps on each end of the load cell insuring that only axial loads are transferred between ribs, would not alter the normal behaviour of the lining.

4.4.1.1 Load Cell Design Details

The structural members of the load cells were a solid cylinder of cold rolled steel (type C1018). Both ends of these cylinders had a spherical shape in order to fit the concave seatings of same radius welded to the end plates according to Figure 4.2. This allows free rotation of the structural member of the load cell in the presence of any bending moment. The mechanical properties of the structural steel are:

- Compressive yield strength = 461965 KN/m²
- Tensile yield strength = 572285 KN/m²
- Elastic deformation modulus = 204092000 KN/m²

A diameter of 7.62cm was chosen for the solid steel cylinder and safety against yielding was checked as follows:

Assuming full overburden at the springline, uniformly acting around the lining, the maximum normal load in the load cell can be calculated:

$$w = 20 \text{ KN/m}^3$$

$$h = 11.9\text{m}$$

$$w.h.s.R = 885.36 \text{ KN}$$

$$s = 1.2\text{m}$$

$$R = 3.1\text{m}$$


where: w = soil unit weight

h = depth of springline

s = ribs spacing

R = lining radius.

Based on the load from full overburden pressure the load cells have a safety factor of 2.4 against yielding.



UNITS: MM
SCALE 1:30

Figure 4.2 LOAD CELL - DESIGN DETAILS

Two SINCO 52621 vibrating wire strain gauges were welded to the cylinder in diametrically opposite directions so strains could be averaged hence a more accurate normal load obtained. SINCO 52622 Pickup Sensors were placed over the vibrating wire gauges and fastened with steel belts welded to the cylinder. These sensors were connected to leads long enough to enable remote readings.

Details concerning the vibrating wire gauge, pickup sensor and strain indicator are given in the manual provided by SINCO.

Details of the load cells are depicted in Fig 4.2 and Plate 4.1.

4.4.1.2 Load Cell Calibration

Eisenstein et al. (1977) found that the maximum normal load in the ribs was approximately 630KN. Based on this information, load cells were calibrated to a load of 700KN. Each of the eight load cells was loaded and unloaded three times under a load controlled condition. Strains (from strain gauges) and loads were recorded for every increase or decrease of 100KN. Results from these calibration tests are presented in the Appendix C of this thesis. A relationship between loads and strains for each load cell was obtained by the linear regression of the data related to the loading portion of the three tests. These relationships are presented in Table C5 in Appendix C.




Plate 4.1 LOAD CELL DETAIL




Plate 4.2 LOAD CELL INSTALLATION

4.4.1.3 Load Cell Installation

The eight load cells were installed as shown on Figure 4.3. They were installed in such a way that loads in each of the four joints of the steel sets could be measured twice.

The instrumented rings should ideally be installed exactly within the area of the tunnel where "ground instruments" had been installed (between chainage Sta.200 + 43.4 and Sta.200 + 57.1). Unfortunately, it was only possible to place the four rings in the following positions:

ring 1 - Sta. 200 + 60.6

ring 2 - Sta. 200 + 61.8

ring 3 - Sta. 200 + 63.0

ring 4 - Sta. 200 + 64.2

After the joint expansion, the load cells were placed between end plates of the steel ribs (Plate 4.2) and the bolts and nuts placed in order to be tightened later.

The load cells were positioned so that one of the strain-gauges was facing the soil and the other facing the tunnel centreline.

An additional 2.54cm long spacer (W6x25 section) had to be placed between one end of the load cell and the steel rib plate in order to complete the 15.24cm of length of the original spacer (at the time the load cells were built, it was thought that spacers were to be 12.70cm long).

A departure from the normal construction procedure was necessary in the rings where load cells had to be installed in the lower joints as the expansion joints were usually




Figure 4.3 LOAD CELL LOCATION

placed in the upper joints. Expanding one or two of the lower joints instead of the upper ones, probably altered the behaviour of the lining in that region but not significantly.

After the pressure in the expansion jacks was released and the load cells activated, it was noticed that a large radial displacement of the end plates of adjoining ribs and relatively large rotation of the structural member of the load cells on the seats had taken place. The rotation of the load cells separated the sensor from the strain gauge due to a contact between sensors and end plates of load cells. The sensors were replaced and the strain gauges continued to function.

4.4.1.4 Measurement Procedure

Readings were taken with a SINCO Model 52601 strain indicator. Readings were directly displayed as microstrains, and recorded in a field sheet presented in Figure 4.4.

Zero readings for data reduction were taken for each cell immediately before installation. Subsequent readings were taken soon after the pressure in the expansion jacks was released and as often as possible in the proximity of the mole tail. The number of readings collected was restricted by other readings that had to be taken simultaneously and by the installation time required for other instruments.

4.4.1.5 Field Data

The data obtained from field measurements is presented in Tables C6 to C13 in Appendix C.

Measured loads were plotted versus time (Figure 4.5 and Figure 4.8), versus logarithm of time (Figure 4.6 and Figure 4.9) and versus distance from tail of mole (Figure 4.7 and Figure 4.10)

Figures 4.5 to 4.7 contain data from the load cells installed in the upper joints while Figures 4.8 to 4.10 contain data from the load cells installed in the lower joints.

4.4.1.6 Data Reduction

The loads measured at the joints of the steel ribs reflect the resultant of the stress distribution acting along the ribs and adjoining pieces of lagging.

There are many possible stress distributions acting in the perimeter of the ring that yield the same set of loads as those measured at this site.

The most often used stress distribution in the back calculation of field data is that presented in Figure 4.11. The use of this distribution is reasonable for deep tunnels where the weight of the excavated soil has a minor influence on the equilibrium of the tunnel liner (Mindlin 1940). The assumption of the stress distribution presented in Fig 4.11 in the calculation of stresses acting on the liner from the loads measured in the load cell is only reasonable when load




Figure 4.5 LOAD CELLS - UPPER JOINTS - LOAD VS TIME




Figure 4.6 LOAD CELLS - UPPER JOINTS - LOAD VS LOG.TIME




Figure 4.7 LOAD CELLS - UPPER JOINTS - LOAD VS DISTANCE FROM TAIL OF MOLE




Figure 4.8 LOAD CELLS - LOWER JOINTS - LOAD VS TIME




Figure 4.9 LOAD CELLS - LOWER JOINTS - LOAD VS LOG.TIME




Figure 4.10 LOAD CELLS - LOWER JOINTS - LOAD VS DISTANCE FROM TAIL OF MOLE




Figure 4.11 LOAD DISTRIBUTION AROUND TUNNEL LINERS:
SYMMETRIC TO VERTICAL AND HORIZONTAL AXIS

cells installed in both upper and lower joints measure similar loads.

In the present study where the loads in the lower joints are significantly higher than those in the upper joints, a stress distribution taking into account the side friction along the tunnel walls seems to better explain the results, and does not complicate the analysis (many other more complex stress distributions could be used).

Figure 4.12 depicts the proposed stress distribution and it should be noted that, in this figure, the ratio between vertical and horizontal effective stresses after the tunnel construction was assumed to be unity, in order to simplify the solution.

Figure 4.13 presents the calculations carried out in order to obtain the relationship between measured loads in the upper and lower load cells and the stresses acting on the lining. These relationships are given below:

$$R_{upper} = 2.91p_c + 0.19p_i$$

$$R_{lower} = 2.91p_i + 0.19p_c \quad 4.1$$

The meaning of each component of this equation is given in Figure 4.13.

Values of p_c and p_i (pressures at the crown and invert, respectively) can be found by substituting a pair of loads measured in the field (in the upper and lower joints) in equations 4.1.

A decision was made to study the stress distribution acting on the liner using load cell readings taken when the





Figure 4.12 GROUND STRESS DISTRIBUTION ON STEEL RIBS TAKING INTO ACCOUNT SHEAR ALONG THE SOIL-LINER INTERFACE

UPPER JOINT



ASSUMPTIONS:

- SYMMETRY WITH RESPECT TO THE VERTICAL AXIS ($V_a=0$)
- JOINTS DO NOT CARRY SHEAR FORCE AND BEND/MOMENTS ($V_{ju}=H_{ju}$; $M_{ju}=0$)

$$\vec{V}_{ju} + \vec{H}_{ju} = \vec{R}_{ju}$$

R_{ju} = load in upper joint

VERTICAL EQUILIBRIUM:


$$P_c \cdot 2.19 + \frac{0.29 (P_i - P_c) \cdot 0.91}{2} = V_{ju}$$

$$2.06 P_c + 0.13 P_i = V_{ju}$$

$$R_{ju} = \sqrt{2} \cdot V_{ju}$$

$$R_{ju} = 2.91 P_c + 0.19 P_i$$


LOWER JOINT



ASSUMPTIONS:

- $V_b = 0$
- $V_{jl} = H_{jl}$
- $M_{jl} = 0$

$$\vec{V}_{jl} + \vec{H}_{jl} = \vec{R}_{jl}$$



R_{jl} = load in lower joint

VERTICAL EQUILIBRIUM:

$$P_i \cdot 2.19 - \frac{0.29 (P_i - P_c) \cdot 0.91}{2} = V_{jl}$$

$$2.06 P_i + 0.13 P_c = V_{jl}$$

$$R_{jl} = \sqrt{2} \cdot V_{jl}$$

$$R_{jl} = 2.91 P_i + 0.19 P_c$$

Figure 4.13 EQUILIBRIUM EQUATIONS FOR THE LOAD DISTRIBUTION OF FIG 4.12

shield tail was 36.4 metres away. This distance was found to be convenient because, at this distance from the shield, the sections studied were considered to be far enough to avoid mole jacking effects and close enough to minimize the time dependent soil behavior effects on the lining pressure. Readings of load cells taken at approximately 36.4m away from the mole took place within 14 days of their installation.

Due to the fact that the use of Equations 4.1 requires load measurements in the upper and lower joints at the same ring and that not all instrumented rings had load measured in both upper and lower joints, it was proposed that the study of pressure distribution on the lining be carried out by combining the data obtained from two adjoining instrumented rings. By doing so, stress distributions can be obtained by combining loads measured in the upper and lower joints of rings 1 and 2, rings 2 and 3 and rings 3 and 4 (figure 4.3).

The values of load cell readings at 36.4m away from the mole and values of p_c and p_i obtained from the solution of Equations 4.1 are presented in Table 4.2.

4.4.2 Steel Lagging

The instrumentation and study of the lagging in the LRT tunnel primary lining was not only important from the research point of view, but also from an economic point of view since an increase in the originally specified timber

Load cell no.	Load* (kN) at 36.4 from shield
1	172.00
2	194.41
3	304.71
4	239.41
5	210.00
6	145.00
7	70.23
8	100.23

* Values linearly interpolated from readings
(see Tables C6 to C13 in Appendix C)

STUDIED RINGS	COMBINED LOAD CELLS	** P _{crow} (kN/m ²)	** P _{invert} (kN/m ²)
RING 1	#1 & #2	45.83	52.49
AND	#1 & #3	43.76	84.21
RING 2	#1 & #4	44.98	65.43
RING 2	#6 & #3	35.99	84.75
AND	#6 & #4	37.22	65.97
RING 3	#6 & #5	37.77	57.51
RING 3	#6 & #5	37.77	57.51
AND	#7 & #5	16.26	59.00
RING 4	#8 & #5	24.89	58.40

** 1.2m rib spacing already considered

Table 4.2 LOADS ACTING ON THE STEEL RIBS AT 36.4M FROM THE SHIELD TAIL

lagging length would yield an increase in the tunnel advance rate and a decrease in the number of steel ribs required, thus resulting in an overall cost decrease.

The pressure acting on the timber lagging could be obtained by installing pressure cells at the contact between the ground and lagging but this procedure was promptly disregarded due to reasons discussed in Section 4.2

It was then decided to obtain ground load distributions by monitoring lagging strains and converting them to pressures by back calculation.

Three problems had to be faced at this stage:

- the difficulty of obtaining accurate and reproducible strain measurements in wood;
- the variability of timber properties;
- how to separate the deformations caused by the mole advance from those caused by the action of the ground.

The first two problems can be avoided by measuring strains in steel pieces of lagging, constructed to have the same bending stiffness as timber, and the third by making these special instrumented pieces of lagging slightly shorter than the standard 121.92cm length.

4.4.2.1 Steel Lagging Design Details

According to the specifications for the primary lining, the wooden lagging should consist of spruce or equivalent material having an allowable bending fibre stress of not

less than 6895 KN/M^2 . Its dimensions should be

- section $100 \times 150 \text{ (mm)}$
- length 121.92 cm

The 150 mm cross-sectional dimension should be placed against the soil.

Three pieces of timber lagging were brought to the University laboratory and loaded in bending by applying equal concentrated loads at the one-third points of the 152.4 cm span (it was decided to test longer timbers than the ones that were being used in the early stages of the construction) and the central deflection versus load was recorded in order to obtain the average flexural rigidity. The flexural rigidity (EI) was found to be 105.61 KN.m^2 and the modulus of elasticity (E) 7929.25 MN/m^2 .

It can be concluded that steel pieces of lagging with a flexural rigidity of 105.61 KN.m^2 should be built in order to replace the original timber lagging.

Twelve pieces of lagging were made according to Figure 4.14 and the steel section HSS $5 \times 2 \times 0.188$ was the best available, at that time, that would satisfy the requirements. The relevant mechanical properties of the beam section chosen are presented in Figure 4.14.

Weldable Ailtech electric strain gauges, Model SG129, were attached to the face of the steel lagging, facing the tunnel axis, in three locations in order to enable the evaluation of the ground stress distribution along the length of the beam. A piece of steel lagging is shown on




Figure 4.14 STEEL LAGGING DESIGN DETAILS

Plate 4.3.

4.4.2.2 Steel Lagging Calibration Tests

Calibration tests were carried out on each of the twelve pieces of steel lagging. Tests were carried out on a Baldwin Universal Testing Machine where the HSS 5x2x0.188 test beams were loaded in bending by applying equal concentrated loads at the one-third points of the 110.48cm free span.

Due to time constraints, strain readings during the calibration tests were taken from all three gauges only for piece SL10 while for the other beams readings were taken only at the centre strain gauge. Strains were measured with the strain indicator produced by Automation Industries Inc. The calibration test results are presented in Tables C14 to C19 in Appendix C.

As expected, the strain readings along the length of test beam SL10 were proportional to bending moment. The strains can also be expected to be proportional to bending moments for the other beams.

The inclination of the loading portion of the calibration curves were practically the same for all beams with a mean value of 6410KN.m (Fig 4.15). From this mean calibration curve, the empirical flexural rigidity of the 12 test beams can be evaluated.

For a beam under bending:




Figure 4.15 STEEL LAGGING - MEAN CALIBRATION CURVE




Plate 4.3 STEEL LAGGING DETAIL




Plate 4.4 STEEL LAGGING INSTALLATION

$$\varepsilon = M.y/E.I$$

where ε = strain
 M = bending moment
 EI = flexural rigidity
 $y = 0.0254\text{m}$

thus: $EI = \frac{M}{\varepsilon} 0.0254$

For $M/\varepsilon = 6410\text{KN.m}$, $EI = 162.81 \text{ KN.m}^2$

which is different from the tabulated one: 132.81KN.m^2 .

It can be concluded that the test beams have a flexural rigidity 54% higher than anticipated.

Corrections have been made to the field data in order to analyse them.

4.4.2.3 Steel lagging Installation

The pieces of steel lagging were placed in position 1, position 2 and position 3 as shown on Figure 4.16.

Position 1 was located between rings 1 and 2 where load cells #1, #2, #3 and #4 were installed (see Figure 4.17), position 2, between rings 2 and 3 and position 3 between rings 3 and 4. In each of these positions, four pieces of lagging were installed. They were placed in positions that would enable the monitoring loads in most significant




Figure 4.16 STEEL LAGGING LOCATION




Figure 4.17 SL AND LC RELATIVE POSITION

portions of the circumference. No steel lagging was placed at the invert because this region was being used as the base for the tracks for the muck cars.

The pieces of lagging were installed soon after the erection of the steel ribs within the shield (Plate 4.4). The ribs were erected at a distance, from the previous installed ribs, slightly larger than the standard 121.92cm spacing, in order to facilitate the lagging installation.

During the steel lagging installation, a space was left between adjacent timbers by using four pieces of wood (1cm thick and 3cm wide), two at each side of the contact, to minimize side friction and to allow the measurement of overcore closure.

4.4.2.4 Measurement Procedure

Strains in the steel lagging strain gauges were measured with the read-out unit produced by Automation Industries Inc.

Zero readings from the steel lagging were taken immediately after installation, when the pieces of lagging were within the shield. The first reading following the zero reading, after installation, was taken when the steel lagging was between 1 and 3 metres from the shield tail. It was not possible to record the strains more frequently at this stage because other readings had to be taken and other instruments had to be installed simultaneously.

Strains were read for the three strain gauges of each piece of steel lagging and recorded in the field sheet presented in Figure 4.18. As the tunnel had its axis in the EAST-WEST direction, strain gauges from each piece of lagging were given the letters E (east), C (centre) and W (west).

At least four sets of readings were taken for all pieces of steel lagging, when they were within one diameter of distance from the shield tail.

4.4.2.5 Field Data

The data recorded in the field is tabulated in Tables C20 to C25 presented in Appendix C.

The strains were plotted versus time and versus distance from shield tail and are presented in figures 4.19 to 4.30.

In all figures and tables referring to the steel lagging data, the term "DISTANCE FROM TAIL OF MOLE" means the distance from the end of the steel lagging, that first leaves the shield, to the tail of the mole (shield).

In some cases, strains could not be properly recorded due to the mal-functioning of the connectors attached to the strain gauges.

Data from the steel lagging occupying the same relative position along the perimeter of the tunnel wall, were plotted in the same graph.

PIECE OF LAGGING #

DATE	DIST. TAIL	ΔE		ΔC		ΔW		ΔE		ΔC		ΔW		COMMENTS
		E		C		W		E		C		W		

PIECE OF LAGGING #

DATE	DIST TAIL	ΔE		ΔC		ΔW		ΔE		ΔC		ΔW		COMMENTS
		E		C		W		E		C		W		

Figure 4.18 STEEL LAGGING FIELD SHEET




Figure 4.19 STEEL LAGGING - #1 AND #8 - STRAIN VS TIME




Figure 4.20 STEEL LAGGING - #1 AND #8 - STRAIN VS DIST. FROM TAIL OF MOLE




Figure 4.21 STEEL LAGGING - #10 AND #11 - STRAIN VS TIME




Figure 4.22 STEEL LAGGING - #10 AND #11 - STRAIN VS DIST. FROM TAIL OF MOLE




Figure 4.23 STEEL LAGGING - #9 AND #12 - STRAIN VS TIME




Figure 4.24 STEEL LAGGING - #9 AND #12 - STRAIN VS DIST. FROM TAIL OF MOLE




Figure 4.25 STEEL LAGGING - #2 AND #7 - STRAIN VS TIME




Figure 4.26 STEEL LAGGING - #2 AND #7 - STRAIN VS DIST. FROM TAIL OF MOLE




Figure 4.27 STEEL LAGGING - #3 AND #6 - STRAIN VS TIME




Figure 4.28 STEEL LAGGING - #3 AND #6 - STRAIN VS DIST. FROM TAIL OF MOLE




Figure 4.29 STEEL LAGGING - #4 AND #5 - STRAIN VS TIME




Figure 4.30 STEEL LAGGING - #4 AND #5 - STRAIN VS DIST. FROM TAIL OF MOLE

4.4.2.6 Data Reduction

The measurement of strains at three different points along the length of the pieces of steel lagging was taken to obtain the magnitude and distribution of the soil load on the lagging.

Bending moments are directly related to measured strains through the calibration curve, Figure 4.15, and are tabulated in Tables C20 to C25 in Appendix C.

Load distribution can be evaluated from bending moments through the structural concept:

$$p = \frac{\partial V}{\partial x} = \frac{\partial^2 M}{\partial x^2}$$

where p = load distribution

V = shear force

M = bending moment

As bending moments are only available at three positions along the pieces of steel lagging, the evaluation of the bending moment distribution is only approximate. The load distribution calculated from the analysis is strongly affected by the assumed initial moment distribution.

For the field data reduction, it was initially assumed that the bending moments varied linearly between strain gauges and between the outer strain gauges and the ends of the steel lagging. Shear forces could be calculated from this variation of bending moments and the same procedure is applicable to shear forces in order to calculate external load distributions.

This procedure is illustrated in Figure 4.31.

The results obtained from this analysis were clearly not reflecting the actual load distribution carried by the lining. In some cases, loads were found to be acting in the opposite of the expected direction (i.e. acting outwards).

It was then decided to submit the data to a simpler analysis that would assume:

- the ground load was uniformly distributed along the length of the steel lagging.
- no moments were carried by the ends of the steel pieces of lagging.
- no axial load was transmitted to the steel lagging.

Since, for all pieces of lagging, it was impossible to find a unique uniform load distribution that would yield values of strains identical to those obtained from the strain gauges, the uniform load distribution obtained from the data was assumed to be the average of two different uniform load distributions, calculated from the three strain gauges as follows:

$P_{u,c}$ = obtained from the strains measured by the central strain gauge.

$P_{u,o}$ = obtained from the average of the strains measured by the two outer strain gauges.

Figure 4.32 depicts these assumptions.

The load distribution along the steel lagging was calculated using the data obtained when the pieces of




Figure 4.31 STEEL LAGGING STRESS DISTRIBUTION CALCULATED FROM STRAIN GAUGES




Figure 4.32 SIMPLIFIED STEEL LAGGING STRESS DISTRIBUTION ASSUMED ON THE DATA REDUCTION

lagging were at 36.4m of distance from the tail of the mole.

This distance was chosen for the same reasons discussed earlier for the load cells:

- readings taken close to the tail would be affected by the mole advance forces
- readings taken remote from the tail would be affected by the ground time dependent behavior.

The reading taken at 36.4m from the mole tail took place less than 14 days after the tail passed any instrumented ring. In most cases readings exactly at the distance of 36.4m from the tail were not taken and, in these cases, bending moments were obtained by linear interpolation of available field data. The uniform load distribution, calculated based on the assumptions described in this section, is presented in Table 4.3.

During the calibration tests, the flexural rigidity of the steel lagging was found to be 54% larger than that of the timber lagging (162.81KN.m^2 and 105.61KNm^2 respectively). This means that the load picked up by the steel lagging is probably larger than that carried by the timber. Hence, a correction is necessary since the main interest is the ground load acting on the wooden lagging. For the sake of simplicity, it was assumed that there is a linear relation between load carried and the bending stiffness. The loads originally calculated can be corrected easily and are presented in the last column of table 4.3. More complex corrections are not justified since many

MOMENTS AT 36.4m AWAY FROM TAIL (kN.m)

LAG/NO	M _e	M _C	M _W	$\frac{M_e + M_W}{2}$	P _C (kN/m)	P _O (kN/m)	P _{av} (kN/m)	P _f nal (kN/m ²)	P _f nal corr.
1	1.47	1.92	1.35	1.41	11.50	10.95	11.23	88.43	57.36
8	0.67	0.98	0.53	0.60	5.87	4.66	5.27	41.50	26.92
10	0.76	1.22	0.89	0.83	7.31	6.41	6.86	54.02	35.04
11	0.16*		0.21	0.19	0.96	1.44	1.20	9.45	6.15
9	0.31	0.08	0.09	0.20	0.48	1.55	1.02	8.00	5.19
12	0.57	0.61	0.22	0.40	3.65	3.07	3.36	26.46	17.16
3	0.33	0.49	0.17	0.25	2.94	1.94	2.44	19.21	12.46
6	1.07	0.94	0.76	0.92	5.63	7.10	6.37	50.37	32.67
2	0.34	0.43	0.38	0.36	2.58	2.80	2.69	21.18	13.74
7	0.18	0.32	0.18	0.18	1.92	1.40	1.66	13.07	8.48
4	0.80	1.21	1.11	0.96	7.25	7.41	7.33	57.72	37.44
5	ZERO	ZERO	ZERO	ZERO	ZERO	ZERO	ZERO	ZERO	ZERO
	**	**	**						

* Value not linearly interpolated -See table C25.

** These values were actually negative and, here, they were considered zero.

*** P_fnal = Pav/0.127 (m) (width correction)

**** Pcorrected = P_fnal x 105.61/162.81 (stiffness correction)

TABLE 4.3 - LOADS ACTING ON THE LAGGING AT 36.4m FROM THE SHIELD TAIL.

simplifying assumptions have been already made. The corrected values of table 4.3 are plotted in their respective locations in Figure 4.33.

4.4.3 Overcoring Measurement

The knowledge of the rate of closure of the void left between the ground and the lagging would be of great interest, with respect to loss of ground studies and helpful in interpreting the steel lagging and load cell results.

The distance between the pieces of steel lagging and the ground will be referred as overcoring. The overcoring was measured in six different locations along the length of each steel lagging installed in positions 1 and 2, soon after they left the shield.

Shortly before the second set of readings was taken (a couple of hours later) it was noticed that the ground was being squeezed through the space left between the steel and timber lagging. The soil that was coming towards the tunnel was a very wet soft clay mixed with medium sand which was probably coming from a inter-till water bearing sand pocket mixed with cuttings from the mole. The presence of this material around the lining determined the end of overcoring rate closure measurements which was not measured later.




Figure 4.33 STRESS DISTRIBUTION ON THE LAGGING AT 36.4m FROM THE SHIELD TAIL

4.4.4 Lining Deformation

The monitoring of lining deformation can be very helpful in the interpretation of the steel lagging and load cell results and provides valuable input for the computer numerical analysis.


For the LRT primary lining, the distortion was recorded by measuring the change in chords of the lining with a tape extensometer and monitoring the level change of some points welded to the lining.

The quality of the distortion readings would be undoubtedly improved if use had been made of the curvometer and deformer proposed by Kovari (1977) but these instruments were not available at the moment they were needed.

4.4.4.1 Details of Instrumentation

The tape extensometer used in the distance readings was produced by Slope Indicator Co. Model P/N 518115. This tape extensometer consists of a spring loaded steel tape connected to a dial gauge. Accurate measurements of distances between two points are accomplished by hooking one end of the tape and the hook connected to the dial gauge to the eye-bolts, previously fixed to these two points.

In the primary lining, four steel ribs were chosen for deformation observation. Each of these steel rings had five eye-bolts welded according to Figure 4.34. In this figure, seven chords are indicated, which together with the level



NOT TO SCALE

LEVEL CHANGE WAS MONITORED IN 'A' AND 'B'

I TO VII - MEASURED CHORDS

Figure 4.34 LINING DEFORMATION MEASUREMENT - POSITION OF THE EYE-BOLTS AND MEASURED CHORDS

change of the two lower eye-bolts, made possible the location of the absolute position of the five points in the plane of that ring.

4.4.4.2 Eye-Bolts Installation

The ribs that had deformations monitored were named ring 5, ring 6, ring 7 and ring 8 located at Sta. 200 + 73.0, Sta. 200 + 74.2, Sta. 200 + 75.4 and Sta. 200 + 76.6 respectively.

The eye-bolt installations were very simple and consisted simply of welding them to the rib. The welding was only possible after the joint expansion and the spacer placement because, during expansion, the rib expansion ring was kept in contact with the ribs being expanded. The premature eye-bolt installation would inevitably have resulted in their complete destruction.

In order to improve the accuracy of the level measurements, the two lower eye-bolts of each of the four rings were welded to the lining together with a specially designed steel cylinder, with a cone-shaped depression that fits the lower end of the surveying rod.

All level measurements were referenced to a steel pin anchored to the concrete structure of the Central Station, at the tunnel entrance (approximately at 70 metres from ring 5).

A turning point was welded to the lining between the Central Station and ring 5 in order to decrease the sight

distance from surveying rod to the level.

4.4.4.3 Measurement Procedure

For ring 5, the first set of readings was taken soon after the eye-bolts were installed at a distance of 0.4m from the tail. At that moment, the mole was advancing and the jacking forces on the lining, together with the vibration from the muck cars, made the readings significantly difficult to observe. This set of readings comprises the measurement of the length of seven chords and level of the two lower eye-bolts. Another difficulty that was encountered while readings were being taken was the interference of these readings with the construction procedure.

Based on these experiences it was decided to take readings only when neither the mole nor the muck cars were working. This situation happened at a distance of 1.6m away from the shield tail (1 push of the mole after the eye-bolt installation).

The second complete set of readings could not be taken within the next 15 metres of mole advance because the conveyor belt structure and the power generator (pulled by the mole) directly interfered with the chord measurements. The subsequent set of readings was taken for all rings (5 to 8) when they were at distances between three and four diameters from the shield tail. The third, and last set of readings, was taken one day after the second set.

Measurements were recorded in the field data sheet presented in Figure 4.35.

4.4.4.4 Field Data

The field data related to the lining deformation measurements is presented in Table C26, in Appendix C, and the reduced displacements are plotted in Figure 4.36.

The results shown on Figure 4.36 assume that the central point of the chord I did not move laterally.

4.5 Discussion of the LRT South Extension Tunnel Liner Instrumentation

In this section, data will be analysed independently for each set of data obtained from each instrument and, finally, a general discussion will consider all the data.

4.5.1 Discussion of Loads and Displacements of the Steel Ribs

A significant difference in normal loads obtained from load cells installed in the same relative position of the liner is noticeable (Figures 4.5 and 4.6). This variability of results happens due to the uneven application of jacking forces around the perimeter of the lining during the mole advance. This uneven force application is necessary for the steering and alignment of the mole. It can be concluded, then, that the load distribution acting on the lining is strongly affected by the construction method.

RING NO.	DATE	TIME	IN. W. BY	HOLE FUNCTION	STATIONING						
					I	II	III	IV	V	VI	VII.


FACE	POINT	READINGS		$\sum (error)$
		FORWARD	BACKWARD	
1	BH1			
	BH2			

FACE	POINT	READINGS		$\sum (error)$	$\sum (error) + \sum (adj)$	$\sum adj$
		FORWARD	BACKWARD			
2	BH2					
	5A					
	5B					

POINT	READING	$\sum (error)$	$\sum error$ *
5A			
5B			
6A			
6B			
7A			
7B			
8A			
8B			

* $\sum (error) + \sum (error - adj)$

SKETCH:



NOTE → VIEW FROM EACH POINT

Figure 4.35 LINING DEFORMATION MEASUREMENT - FIELD DATA SHEET




Figure 4.36 LINING DEFORMATION RESULTS

The variability of readings for each load cell was evident when these readings were taken when the mole propulsion jacks were within a distance of approximately 20 metres from the load cells (or 14 days after installation).

All figures depicting the load cell data also clearly show that the load cells installed in the upper joints picked up lower normal loads than those installed in the lower joints. This was the main justification for the analysis of Section 4.4.1.6 (Load Cell Data Reduction). Higher loads in the lower joints are probably due to the development of shear forces between the ground and tunnel liner. The installation of load cells in the lower joints undoubtedly induced this side friction because the joint expansion was done with an upward movement of the steel rib located above this joint. The tunnel construction was shut down for five days (from 18 to 23-feb-81), when ring number 4 was four metres away from the shield tail. During this period, the loads in the lower joints (numbers 2,3,4,5) increased while loads in the upper joints (numbers 6,7 and 8) decreased (see Tables in Appendix C). This enhances the interpretation that the development of shear forces along the tunnel walls is not solely due to the expansion of the lower joints.

The shear force at the soil-liner interface has a greater effect on the lining behaviour in shallow tunnels than in deep tunnels. For the latter, the shear forces are small when compared to the ring stresses induced by the

stress field.

There are many methods of defining whether a tunnel is shallow or deep. These definitions can be based on the modes of failure of the opening; the similarity of ground displacements above and below the tunnel; whether the surface displacements are measurable or not; and the theory of elasticity. The knowledge of whether a tunnel will behave as a shallow or as a deep tunnel seems to be of enormous consequence in the liner design. This importance is discussed in Chapter 5 of this thesis.

The study of stress distribution around the tunnel, presented in Section 4.4.1.6 (Load Cell Data Reduction) aided in interpreting the lining behaviour. By comparing the values of load distribution acting on the crown and the invert presented in Table 4.2 with the stress at these locations before the tunnel was excavated, it can be concluded that the average stress relief at the invert (233KN/m^2) is higher than that at the crown (138KN/m^2). This difference in stress relief might reflect the behaviour of a shallow tunnel, since for a deep tunnel this relief should be approximately the same for crown and invert. The general upward movement of the tunnel liner presented in Figure 4.36 might also be related to the difference in stress relief in the crown and invert.

The plots of load versus time and logarithm of time show that loads continually increase after the mole passes a section. This behaviour is attributed to the time dependent

transfer of loads from the soil to the tunnel liner.

The observation by Peck (1969-b) seems to be valid in this case: "For many tunnels the ring load appears to increase roughly proportionally to the logarithm of time".

It should be finally mentioned that load cells located at 36.4m away from the shield tail indicated a load distribution on the lining varying from 9 to 26 per cent of the overburden at the crown. Further comments on this variation will be offered in Section 4.5.4.

4.5.2 Discussion on Steel Lagging Results

Figures 4.19 to 4.29, which present strains measured versus time and versus distance from the tail of the mole, show some points of the lagging behaviour that are worth mentioning.

It should be noted that there is no direct relationship between the load carried and the position of the pieces of lagging as compared to the load cells that consistently measured higher loads in the lower joints of the steel ribs.

The figures also show that the strains measured in the three strain gauges attached to each of the instrumented pieces of lagging reflect the non-uniform nature of the load acting along each of these pieces. In some cases (SL2, SL5 and SL9) negative strains were measured indicating that normal load was present, probably transmitted through the four contact points of the steel lagging with the adjoining timbers and through the contact between these pieces and

steel ribs. It is believed that these normal loads are very small and should not significantly alter the analysis.

In most cases, activation of the lagging occurred at a distance between 1.3 and 5.2 metres from the shield tail thus giving some indication of where the arching between the excavated soil ahead of the mole and the lining is taking place. After the lagging activation, the strains varied within a relatively narrow range except for SL9, SL2 and SL7.

It should be noted that most strain gauges reflected a decrease in the magnitude of loads supported by the steel lagging after the mole stopped with the tail at 85.6 metres from ring 5. This occurrence was probably due to the decrease in the "negative ground arching" induced by the presence of a stiffer element in the lagging and not to the increase in arching of ground between steel ribs, which probably decreases with time.

The reduced data, presented in Section 4.4.2.6 (steel lagging data reduction) involved many simplifications and assumptions but still are very useful in interpreting the lagging behaviour. Figure 4.33 depicts the reduced uniform loads and confirms the statement made at the beginning of this section: there is no direct relationship between the load carried and the position of pieces of lagging. The superimposed values presented in Figure 4.33 must be analysed with care since values of loads measured in different planes (different positions) bear no

interrelationship.

The maximum measured load acting on the lagging 36.4m away from the mole is only 33% of the overburden (51% if no stiffness correction is made) which justified the increase in the rib spacing from 121.92cm to 152.40cm. This increase in rib spacing for the construction of the remainder of the tunnel was enhanced by the loads acting on the lagging measured by Thomson and El-Nahhas (1980) from 3% to 63% of overburden (tunnel in clay shale and TBM excavated). The increase in the rib spacing promoted significant economy by not only decreasing the number of steel ribs required but also increasing the rate of mole advance.

More accurate load distributions would be possible if the steel lagging comprised the entire ring rather than just a part.

4.5.3 Discussion of the Convergence / Divergence Measurements

Results from closure measurements in Figure 4.36 indicate the upward movement of the liner as a "solid body" since all these vertical displacements vary within a narrow range (from 1.58 to 3.60mm) and most of the nodes (A to E) had horizontal movements of less than 1mm.

The author is sceptical about the results of the liner movements basically due to two reasons. First, the zero readings were taken within the region where the lining movements are basically governed by the mole, and second, the

number of readings was small. It seems, then, very difficult to be sure whether the displacements shown in Fig 4.36 are caused by ground action or by the mole action.

The valuable item of information arising from the monitoring of the liner deformation is its symmetrical behaviour with respect to the vertical line passing through the center of the tunnel and the small magnitude of displacements which is in agreement with the low normal loads measured in the load cells.

The small amount of distortion that occurred in the lining might be an indication that the ratio between vertical and horizontal ground stresses by the time the lining was installed was very close to one ($K = 1$).

Further discussions will be offered in the next Section, 4.5.4.

4.5.4 General Discussion of the Lining Behaviour

The data presented in Tables 4.2 and 4.3 were assembled in Table 4.4 to enable the study of the interaction between steel ribs and lagging to be made. In this table, loads obtained from the pieces of lagging located between the two lower joints were considered as acting on the invert and those located between the upper and lower joints were considered as acting on the springline.

The average values of P_{crown} (stress at the crown) $P_{\text{springline}}$ and P_{invert} were plotted for each of these three positions for both the steel lagging and load cell data, in

DATA FROM	Pcrown (kN/m²)		Pspringline (kN/m²)		Pinvert (kN/m²)		AVERAGE RING STRESSES (kN/m²)	
	LC	SL	LC*	SL	LC	SL	LC	SL
POSITION 1 BETWEEN RING 1 & 2	From 43.76 to 45.83	From 13.74 to 57.36	From 49.16 to 63.99	From 12.46 to 12.46	From 52.49 to 84.21	From 37.44 to 37.44	56.12	30.25
	Average: 44.86	Average: 35.55	Average: 56.12	Average: 12.46	Average: 67.38	Average: 37.44		
POSITION 2 BETWEEN RING 2 & 3	From 35.99 to 37.77	From 8.48 to 26.92	From 47.64 to 60.37	From 32.67 to 32.67	From 57.51 to 84.75	From 0.00 to 0.00	53.20	17.02
	Average: 36.99	Average: 17.70	Average: 53.20	Average: 32.67	Average: 69.41	Average: 0.00		
POSITION 3 BETWEEN RING 3 & 4	From 16.26 to 37.77	From 6.15 to 35.04	From 37.63 to 47.64	From 5.19 to 17.16	From 57.51 to 59.00	From --- to ---	42.31	15.89
	Average: 26.31	Average: 20.61	Average: 42.31	Average: 11.18	Average: 58.30	Average: ---		

* Average of Pcrown and Pinvert.

TABLE 4.4 - LOADS ACTING ON STEEL RIBS AND LAGGING AT 36.4m FROM THE SHIELD TAIL.

Figure 4.37. In this figure, the numbers are only approximate and were plotted simply to elucidate an understanding of the lining behaviour.

The decision to plot *average* values of load distribution was made because these, when evaluated from load cell reflect the average of all loads acting along the steel ribs and the lagging, while the load distribution obtained from the steel lagging do not reflect the lining behaviour as a whole. The results plotted on this figure consistently show that loads carried by the steel ribs are higher than those carried by the neighbouring timber lagging. The opposite could be only possible if the lagging had a self supporting capacity, acting as a perfectly flexible lining. This does not happen due to the existence of the end plates welded to the steel ribs; all the radial loads carried by the lagging is transmitted to the ribs through the end plates.

Another factor affecting the load distribution along the tunnel liner is the construction method. One of the steps of the lining installation procedure is the rib expansion where the jacks, through the rib expansion ring, push the rib towards the soil, in order to minimize the ground loss around the lining. Since the expansion happens on the ribs, and these are projected 1.3cm outwards with respect to the lagging, the difference in the load carried is clearly understandable.




Figure 4.37 STRESS DISTRIBUTION ON RIB AND LAGGING AT 36.4M FROM THE SHIELD TAIL

The magnitude of the difference in load supported by the components of the primary lining can be roughly expressed by the average ring load values presented in the last two columns of Table 4.4. They show that ribs carry loads from 85 to 213% higher than those carried by the lagging. It is of major interest to compare the pressure on lining obtained in this study with those presented by El-Nahhas(1980) (Table 4.5). For the LRT Extension tunnel currently being studied, the height of soil carried by the steel ribs varies from 2.12m to 2.81m (obtained from average "ring loads" in Table 4.4) as compared to the 4.71m obtained from the north-eastern tunnel of the LRT. The difference in load supported by the two LRT tunnels might be due to a greater self support capacity of the ground surrounding the tunnel of the LRT South-Extension. Another reason for this difference might be due to the different methods utilized to measure normal loads in both tunnels. In the north-eastern tunnel, loads were measured with strain gauges attached to the ribs and these seem to have been affected by the advance of the mole.

The ratio (n) of height of soil carried by the lining to the tunnel diameter varies from 0.34 to 0.45 as opposed to the values presented in Table 4.5 where n varies from 0.8 to 1.09.

The great disadvantages of the comparison based on ratios such as n are that it does not take into account the construction effects that certainly have a major role in the

	Depth metre (Z)	Diam. metre (D)	Z/D	Pv (kPa)	PL (kPa)	PL/Pv x 100	h metre	n=h/D	References
LRT-NORTH EAST TUNNEL	10.2	6.1	1.7	125	100	80	4.71	0.8	Eisenstein et al. (1977) Eisenstein and Thomson (1978)
LRT-SOUTH EXTENSION	11.8	6.2	1.9	174	42.3-56.1(c) 15.9-30.3(d)	24-32 9-17	2.12-2.81 0.80-1.52	0.34-0.45 0.13-0.25	Present study
Whitemud Creek Tunnel	47.2	6.05	7.8	575	114.7	20	5.41	0.9	E1-Nahhas (1977) Thomson and E1-Nahhas (1980)
107th Street Tunnel	20	2.56	7.81	380	6.1-12.6(a) 112-240(b)	1.6-3.3(a) 29.5-63(b)	0.29-0.59(a) 5.28-11.31(b)	- -	E1-Nahhas (1977) Thomson and E1-Nahhas (1980)
Experim. Tunnel	27	2.56	10.54	550	63	12	2.79	1.09	E1-Nahhas (1980)

Notes: Pv : Overburden pressure.
PL : Pressure on lining.
h : Height of soil carried by lining = PL/soil unit weight

(a) = From pressure cells.
(b) = From lagging deflection.
(c) = From load cells - average ring stresses.
(d) = From steel lagging - average ring stresses

TABLE 4.5 - Soil pressure on the primary lining in Edmonton tunnels (After E1-Nahhas 1980)

lining and ground behaviour, nor does it take into account local changes in stratigraphy.

4.6 Summary and Conclusions

In this chapter, the techniques most commonly used in the measurement of lining loads and displacements have been reviewed. Details concerning the installation, measurement procedures and design of the instruments used to monitor loads and displacements in the LRT South-Extension tunnel liner have been presented.

From the analysis of the field data, the following have been concluded:

- Load cells yielded the best results;
- Loads at the crown varied from 9 to 26% of the overburden;
- Load cell measurements indicated that the shear developed along the ribs, acting downwards, are of comparable magnitude to the ring stresses which indicates that the tunnel behaves as a shallow tunnel;
- Steel lagging picked up loads lower than those carried by the ribs, indicating arching between ribs. These loads were always less than 33% of overburden which made possible an increase of rib spacing in the continuation of the tunnel construction;

- Loads measured in the load cells increased roughly with the logarithm of time;
- Lining displacements measurements indicated a general upward movement of the liner with very small distortion of the steel ribs;
- The ratio of the height of soil carried by the lining to the tunnel diameter was found to vary from 0.34 to 0.45 which is lower than the values measured for other tunnels.
- The load distribution acting on the lining is strongly affected by the construction method.

5. SOIL-STRUCTURE INTERACTION AT TUNNELS

5.1 Introduction

The transfer of loads from the excavated ground to the tunnel lining (Soil-Structure Interaction) depends on the construction method and ground and lining deformation and strength properties. The tunnel design methods endeavour to predict the Soil-Structure Interaction. The many existing lining design methods may be divided in three classes:

- Analytical Methods:
 - Finite Element Method
 - Closed Form Solutions
 - Subgrade Reaction Theory
 - Convergence-Confinement Method
- Empirical Methods:
 - Hewett and Johannesson (1922)
 - Peck et al (1972)
 - Design Specifications
- Observational Methods

El-Nahhas (1980) provided a complete summary of some of the currently used design methods. Sophisticated methods, such as the finite element methods, require appropriate input information in order to reproduce properly the ground support interaction. In most cases appropriate information concerning construction details is not available and cannot be easily predicted.

Empirical Methods, on the other hand, do not require accurate input information rather they are based on easily measured ground properties, qualitative geological description and local experience. Usually, the lack of more accurate input information in Empirical Methods results in substantial and indeterminable amount of overdesign. The drawbacks associated with Analytical and Empirical Methods are avoided in the Observational Method. In the Observational Method, the information obtained in the early stages of the tunnel construction is the input for the modifications of the design of sections constructed subsequently. This "learn-as-you-go" method is discussed in the Ninth Rankine Lecture presented by Peck (1969-a).

The interaction between the liner and the surrounding ground has been the subject of several recent studies because its understanding certainly leads to improved tunnel designs.

The finite element methods, closed form solutions and the convergence-confinement curves have played an important role in enlightening the complex soil-structure interaction in tunnels. Closed Form Solutions and Characteristic Lines Method (Convergence Confinement Method) are referred to in this chapter as "Simple Solutions".

The simple solutions are not only helpful in understanding the interaction problems related to tunneling but also permit the designer to rapidly investigate a range of possible support alternatives. According to Muir Wood

(1975):

"A special virtue of the simple method is that it serves quickly to indicate sensitivity of the solution across the range of the possible ground parameters."

The use of the available simple solutions in the soil-structure analysis of shallow tunnels is questionable and is the main purpose of the discussion of this chapter. Closed Form Solutions and the Convergence-Confinement Method (C.C. Method) are also discussed comprehensively in this chapter.

The applicability of Simple Solutions to shallow tunnels is discussed on the basis of the data obtained from three tunnels constructed in Edmonton. The detailed description of the three tunnels is given in Section 5.4.

5.2 Closed Form Solutions

5.2.1 Deep Tunnels

The analysis of stresses and strains around ground openings based on continuum mechanics have improved significantly in the last decade. The elastic solutions were limited to unlined openings prior to the work of Burns and Richard (1964).

Burns and Richard (opt. cit.) introduced the lining in the conventional analysis and through the extensional shell

theory and derivations of the Airy's stress function, derived the stresses and displacements in both the soil and lining. The assumptions made to develop Burns and Richard (opt. cit) equations were:

1. Two dimensional problem
2. Both the lining and soil behave elastically
3. Gravity forces are ignored and soil is loaded symmetrically, with respect to both the horizontal and vertical axes, at surfaces considered as infinite (deep tunnel with external loading)
4. The lining is placed before the excavation takes place and before the medium is unstressed
5. The lining is a cylinder with constant thickness and constant elastic properties.

Burns and Richard defined two new coefficients: the compressibility and the flexibility ratios. The compressibility ratio is defined as the extensional stiffness of the medium relative to that of the liner, whereas the flexibility ratio is a measure of the flexural stiffness of the medium relative to that of the liner.

The extensional stiffness is the uniform all around pressure, applied to a circular portion of the soil with the same diameter as the tunnel liner, or the uniform pressure applied to the lining, necessary to cause a unit diametral strain.

The flexural stiffness is the pressure applied to a circular portion of the soil with the same diameter as the

tunnel liner or the pressure applied to the tunnel liner, under a state of pure shear, necessary to cause a unit diametral strain.

The coefficients defined above are extremely useful in the study of deep tunnels because every in-situ stress symmetric to the horizontal and vertical axis of the tunnel can be divided into uniform all around pressure and a state of pure shear pressure distribution (Fig. 5.1).

A detailed derivation of the two ratios described above is given in Peck et al. (1972) who examined the effects of the lining flexibility and compressibility on forces and deformation in tunnel liners erected in soft ground. As the closed form solutions were limited to deep buried cylinders, the effects of the depth of cover above the tunnel crown were studied on the basis of elastic finite element solutions.

Peck et al (opt. cit.) found that the closed form solutions proposed by Burns and Richard, developed for deep tunnels, could be applied to the study of tunnels with a depth of cover (distance between the crown and the surface) greater than 1.5 times the tunnel diameter.

Mohraz et al (1975) with a series of elastic finite element solutions, investigated the effects of different lining loading conditions on the lining thrusts and deformations evaluated by the closed form solutions derived by Burns and Richard. This study was necessary since Burns and Richard's solutions assumed an external loading of the




Figure 5.1 FIELD STRESSES IN BURNS AND RICHARD'S CLOSED FORM SOLUTION

lining which did not simulate the actual lining loading condition during the tunnel construction.

Mohraz et al concluded that the loading condition affects the thrust and lining deformation to a significant degree whereas transverse shear (along the soil-structure interface) and the bending moments are less affected.

Also in 1975, Muir Wood published another closed form solution for deep lined tunnels in which the unloading due to excavation was taken into account and the ground water seepage towards the tunnel was analysed.

In the report by Muir Wood, the previous closed form solution proposed by Morgan (1961) was corrected. Morgan's derivation assumed the sum of the tangential and radial stresses (σ_θ and σ_r) constant throughout the soil mass. This assumption does not reflect the plane strain condition where the strains in the direction parallel to the tunnel axis are considered equal to zero. For the plane strain case the sum of the radial and tangential stresses is given by the equation

$$\sigma_\theta + \sigma_r = \frac{\sigma_2}{\nu} \quad 5.1$$

where σ_2 is the principal stress acting in the direction parallel to the tunnel axis and ν is the Poisson's Ratio of the medium.

Muir Wood's solution ignored the effect of the in-situ shear stresses at the ground-support interface. These shear stresses were taken into account in Curtis' derivation

(1976). Curtis extended the closed form solutions for deep lined tunnels to include the parameter of time in the context of visco-elastic behaviour of the ground.

In 1979 Einstein and Schwartz proposed another derivation for the ground-liner interaction problem. They stated that despite the fact that Curtis' solution took into account the in-situ shear stresses at the ground-support interface, neglected by Muir Wood, it still was not completely correct. Curtis' derivation assumed that the liner was inextensible for the state of pure shear loading (the loads on the lining were assumed to be the sum of two components: uniform compression and state of pure shear loading). The final equations derived by Einstein and Schwartz are presented in Figures 5.2 and 5.3 for the full-slip and no-slip cases, respectively.

Einstein and Schwartz (1980), based on parametric studies, drew the following conclusions concerning the sensitivity of the thrusts and moments relative to the variation in the lining and soil properties (the terms are defined in Figure 5.2):

1. T/PR is strongly dependent on C^* only within the range $0.05 < C^* < 50.0$ and is relatively insensitive to variations of F^* .
2. M/PR^2 is near zero for $F^* > 100$ and is insensitive to variations of C^* .
3. For excavation unloading conditions, both T/PR and M/PR^2 are insensitive to variations in Poisson's Ratio

$$C^* = \frac{ER(1-\nu_s^2)}{E_s A_s (1-\nu^2)} \quad \text{COMPRESSIBILITY RATIO}$$

$$F^* = \frac{ER^3(1-\nu_s^2)}{E_s I_s (1-\nu^2)} \quad \text{FLEXIBILITY RATIO}$$

$$\frac{T}{PR} = 0.5(1+K)(1-a_0^*) + 0.5(1-K)(1-2a_2^*) \cos 2\theta$$

$$\frac{M}{PR^2} = 0.5(1-K)(1-2a_2^*) \cos 2\theta$$

$$\frac{u_s E}{PR(1+\nu)} = 0.5(1+K)a_0^* - (1-K)[(5-6\nu)a_2^* - (1-\nu)] \cos 2\theta$$

$$\frac{v_s E}{PR(1+\nu)} = 0.5(1-K)[(5-6\nu)a_2^* - (1-\nu)] \sin 2\theta$$

WHERE : θ = ANGULAR COORDINATE MEASURED FROM THE SPRINGLINE

$$a_0^* = \frac{C^* F^* (1-\nu)}{C^* + F^* + C^* F^* (1-\nu)}$$

$$a_2^* = \frac{(F^* + 6)(1-\nu)}{2F^*(1-\nu) + 6(5-6\nu)}$$

T, M = SUPPORT THRUST AND BENDING MOMENT

P, K = IN SITU FIELD STRESS, LATERAL STRESS RATIO

E, ν = GROUND YOUNG'S MODULUS, POISSON'S RATIO

E_s, ν_s = SUPPORT YOUNG'S MODULUS, POISSON'S RATIO

A_s, I_s = SUPPORT CROSS SECTIONAL AREA AND

MOMENT OF INERTIA PER UNIT LENGTH OF TUNNEL

R, u_s, v_s = SUPPORT RADIUS, RADIAL AND TANGENTIAL DISPLACEMENT

Figure 5.2 FULL SLIP CASE - EINSTEIN AND SCHWARTZ, 1979-1980

$$\frac{T}{PR} = 0.5(1+K)(1-a_0^*) + 0.5(1-K)(1+2a_2^*) \cos 2\theta$$

$$\frac{M}{PR^2} = 0.25(1-K)(1-2a_2^*+2b_2^*) \cos 2\theta$$

$$\frac{u_s E}{PR(1+\nu)} = 0.5(1+K)a_0^* + 0.5(1-K)[4(1-\nu)b_2^* - 2a_2^*] \cos 2\theta$$

$$\frac{v_s E}{PR(1+\nu)} = -(1-K)[a_2^* + (1-2\nu)b_2^*] \sin 2\theta$$

$$\text{WHERE: } b_2^* = \frac{C^*(1-\nu)}{2[C^*(1-\nu) + 4\nu - 6\underline{b} - 3\underline{b}C^*(1-\nu)]}$$

$$\underline{b} = \frac{(6+F^*)C^*(1-\nu) + 2F^*\nu}{3F^* + 3C^* + 2C^*F^*(1-\nu)}$$

$C^*, F^*, a_0^*, a_2^*, \theta, T, M, P, K, E, \nu, E_s, \nu_s, R, u_s, v_s$: DEFINED IN
FIG. 5.2

Figure 5.3 NO-SLIP CASE - EINSTEIN AND SCHWARTZ, 1979-1980

of the ground.

4. T/PR and M/PR^2 vary linearly with K .
5. the difference between the support forces calculated from the full-slip and no-slip solution are small.

Einstein and Schwartz (opt. cit.), with the aid of the finite element method, introduced correction factors to the lining thrusts and moments calculated by the proposed closed form solutions. Correction factors were introduced in order to take into account the spatial lag, or delay of support and the yielding in the ground mass surrounding the tunnel.

The correction factors are

λ_d = support delay factor

λ_y = ground yielding factor

The final lining thrusts and moments are:

$$T_f = T \cdot \lambda_d \cdot \lambda_y \quad 5.2$$

$$M_f = M \cdot \lambda_d \cdot \lambda_y \quad 5.3$$

$$\text{where } \lambda_d = 0.98 - 0.57(L_d/R) \quad 5.4$$

L_d = distance between the support and the face of the tunnel (unsupported span)

R = tunnel radius

λ_y is presented in the form of graphs and tables in Einstein and Schwartz (1980) as a function of the in-situ stress level, in situ stress ratio

(K), the soil strength properties and .

5.2.2 Shallow Tunnels

The existing definitions of shallow tunnels are presented in Chapter 4, Section 4.5.1.

The available closed form solutions for shallow tunnels are restricted to unlined tunnels. Mindlin (1940) presented a solution in which Gravity Loading, as opposed to External Loading, was taken into account. In the Gravity Loading case the soil mass has self weight whereas in the External Loading case the soils mass is weightless. Mindlin calculated strains and stresses around openings in an elastic medium under plane strain conditions with the help of bi-polar coordinates which simplified the solution.

In Mindlin's derivation, the effects of the proximity of the tunnel to the surface on the stress distribution in the surrounding ground mass is expressed by the difference between the weight of the excavated soil and the in-situ stresses at level of the tunnel centreline. In Mindlin's derivation, the following equation is presented:

$$[\sigma_{\theta}]_{\alpha,\alpha} = -2cw - R_2 w \frac{3-4\nu}{2-1\nu} \cos\psi \quad . \quad 5.5$$

where $[\sigma_{\theta}]_{\alpha,\alpha}$ = tangential stresses at the tunnel wall
(unlined tunnel)

c = the depth of the centre of the tunnel

w = the unit weight of the soil (elastic)

R_2 = the tunnel radius

ν = Poisson's Ratio

ψ = the angle between the radius from the center of tunnel and the normal to the straight boundary (surface).

The second term from this equation arises from the weight of the material removed from the opening and the first term is the stress concentration effect.

Before excavation, the tangential stresses at the tunnel wall at a distance c below surface is $-cw$, so that the term $-2cw$ reveals a predicted stress concentration factor of 2.

The second term of the equation is small in comparison with the first if R_2 is small in comparison to c .

The conclusion mentioned above can be verified in Figure 5.4 where values of normalized tangential stresses in the crown and invert are plotted versus the normalized depth of the tunnel. In this figure, when values of tangential stresses tend to be twice the field stress ($w.c$) the tunnel is said to be deep. To illustrate, the depth ratio $c/R_2 = 3.8$ ($11.3/3.1$) of the LRT tunnel, in Edmonton, is indicated in Fig 5.4. It might be concluded that, according to Mindlin's derivation, the tunnel is at the boundary between a deep and shallow opening.

It is interesting to note that, according to Peck et al (1972), the closed form solutions developed for deep lined tunnels are applicable to depth ratios (c/R_2) greater than 4 which is approximately the same value found by Mindlin's




Figure 5.4 MINDLIN'S CLOSED FORM SOLUTION FOR UNLINED TUNNELS

solution for unlined tunnels (Fig 5.4).

The role of Simple Solutions in tunnel design is discussed in the introduction of this chapter. However, the lack of simple solutions for shallow lined tunnels leaves a gap in the available tools that help in the rapid investigation of alternative solutions.

5.3 The Convergence Confinement Method (Characteristic Lines Method)

The Convergence-Confinement Method is a method in which the ground structure interaction is analysed by an independent study of the behaviour of the ground and the structure.

The Convergence-Confinement Method, therefore, requires an understanding of the behaviour of the ground surrounding the opening in order to find the soil convergence in terms of the applied confining pressure and an understanding of the lining behaviour to find the confining pressure acting on the lining, in terms of deformation.

The idealization of the ground-support interaction by the two Characteristic Curves mentioned above is valid only for the symmetrical cylindrical model in which, irrespective of the lining and ground mechanical properties (E, ν), the soil and support present the same radial mode of deformation.

5.3.1 The Convergence Curve for the Ground Surrounding the Opening (Ground Reaction Curve)

The determination of the convergence curve (or Ground Reaction Curve) requires an understanding of the ground behaviour. For a homogeneous, isotropic and continuous ground mass, the parameters that reflect the ground behaviour can be separated into three categories:

- a) elastic characteristics (E, ν)
- b) shear strength characteristics (c, φ)
- c) parameters representing the soil behaviour after maximum strength is fully mobilized (sensitivity and dilation)

A knowledge of the soil properties mentioned above allows the development of closed form solutions for unlined openings. The closed form solutions developed for the hydrostatic stress field and for the case where the loaded boundaries can be considered at infinity are of major interest in the study of Ground Reaction Curves. In the case of the hydrostatic stress field, the problem can be modelled by a thick walled hollow cylinder. Kaiser (1980) and Panet (1976) presented the derivation of a closed form solution that yields the Ground Reaction Curve of an opening excavated in a material that is assumed to be linear elastic, brittle-perfectly plastic, with yield surfaces described by the Coulomb failure criterion:

$$\sigma_1 = m\sigma_3 + s\sigma_c \quad \text{or}$$

$$\sigma_{\theta} = m\sigma_r + s\sigma_c \quad 5.6$$

where

σ_1, σ_3 = principal stresses

σ_c = unconfined compressive strength

s = strength ratio: σ_c ultimate / σ_c peak

$m = \tan^2(45^\circ + \varphi/2)$

φ = soil friction angle

$\sigma_{\theta}, \sigma_r$ = tangential and radial stresses (also principal stresses for $k=1$)

By imposing the continuity of radial stresses at the boundary between the elastic and plastic zone, the radius of the plastic zone can be evaluated as:

$$\frac{R}{a} = \left[\frac{(m-1)(1-\lambda_c)\sigma_o + s\sigma_c}{(m-1)(1-\lambda_s)\sigma_o + s\sigma_c} \right]^{\frac{1}{m-1}} \quad 5.7$$

where: R, a = radius of the plastic zone and opening, respectively

$\sigma_o(1-\lambda_s)$ = support pressure

λ_s = support pressure coefficient

$$\lambda_e = \frac{1}{1+m} \left[m-1 + \frac{\sigma_c}{\sigma_o} \right] \quad 5.8$$

$\lambda_s = \lambda_e$ if σ_{θ} at $r = a$ is equal to σ_c

σ_o = in situ field stress.

The normalized radial tunnel wall displacement is given by the equation:

$$\frac{u_r^{e+p}}{u_r^e} = \frac{\lambda_e}{1+\alpha} \left[2\left(\frac{R}{r}\right)^{1+\alpha} + \alpha - 1 \right] \quad 5.9$$

where $u_r^e = \frac{\bar{\sigma}_s \cdot r}{2 \cdot G}$ is the tunnel wall displacement under condition of elastic material behaviour

u_r^{e+p} : is the tunnel wall displacement under condition of elastic-plastic material behaviour

α : is a parameter that measures soil dilation during plastic flow ($\epsilon_r^p + \alpha \epsilon_\theta^p$)

$\alpha = 1$ when no dilation takes place

$\alpha = m$ for flow associated with the Coulomb failure criterion


$1 < \alpha < m$ for non-associated flow.

The combination of equations 5.6 to 5.9 enables the determination of the pressure applied to the walls of the opening as a function of the wall displacement.

The influence of friction angle, cohesion, sensitivity, time dependent behaviour and stress history on the Ground Reaction Curve have been reported by Lombardi (1970), Daemen and Fairhurst (1970 and 1972), Ladanyi (1974) and Kaiser (1980).

5.3.2 The Confinement Curve for the Support (Support Reaction Curve)


The Confinement Curve of a cylindrical support loaded by a uniform radial pressure (p_s) is defined by the relationship between and the corresponding radial displacement (u_r) given in Fig 5.5. The support parameters such as elastic properties, load capacity, behaviour after



SUPPORT REACTION CURVE (SRC)

COMBINED SUPPORT STIFFNESS :

"SERIES" COMBINED ELEMENTS



"PARALLEL" COMBINED ELEMENTS




Figure 5.5 SUPPORT REACTION CURVE - COMBINED SUPPORT STIFFNESS

failure and the displacements that occurred before the lining erection are necessary for the determination of the Support Reaction Curve.

The support stiffness (K_s) is defined as the uniform all around pressure required to cause unit diametral strain on the lining. Support stiffnesses for different liners such as concrete or shotcrete, block steel sets, rock bolts or cables are presented by Kaiser (1981). Lombardi (1970) also presents a variety of Support Reaction Curves. Hoek and Brown (1981) present the calculated maximum support pressures for various support systems. The study of combined support systems can be carried out with the models presented in Fig 5.5.

5.3.3 Determination of the Support Pressure and Ground Displacement at the Soil-Structure Interface

The solution for the soil-structure interaction is given by the intersection of the two curves GRC and SRC (Fig 5.6). The simple solution of the complex ground-support interaction provided by the Characteristic Lines Method has several limitations associated with it.

The limitations of the Characteristic Lines Method were comprehensively discussed by Kerisel, J.; Duddeck, H.; Lombardi, G.; Fairhurst, C. and Daemen, J. J. K. during the Conference on "Analysis of Tunnel Stability by the Convergence-Confinement Method" held in Paris, 1978. The most significant limitations of this method are briefly




Figure 5.6 SOLUTION FOR THE SOIL-STRUCTURE INTERACTION BY THE CONVERGENCE-CONFINEMENT METHOD

discussed here. The Convergence-Confinement Method is limited to:

- a) Cylindrical, or nearly cylindrical, opening and support
- b) Support with constant mechanical and geometric properties (E , A , ν , I)
- c) Homogeneous, isotropic and continuous ground
- d) Uniform state of stresses ($\sigma_H = \sigma_V$): closed form solutions for studies of non-elastic ground masses are restricted to stress field ratio equal to one ($K=1$)
- e) Uniform radial mode of deformation: as already noted in this chapter, the independent study of the ground and support is not possible for stress field ratios different than unity. This restriction limits the use of the Characteristic Lines Method to deep tunnels because shallow tunnels are often subjected to bending. This factor is not taken into account in the uniform radial mode of deformation
- f) Time dependent soil behaviour: Fairhurst and Daemen (1972) present a qualitative discussion of the influence of the time dependent behaviour of rocks on the Ground Reaction Curve.
- g) Gravity: the closed form solutions developed for the "hollow cylinder case" ignore the

effects of gravity around the tunnel. The effects of gravity limit the Characteristic Lines Method to a greater degree when a "decompressed zone" develops to a significant extent around the opening and forms an unstable area in the crown.

The weight of the decompressed zone above the crown is an additional load not taken into account in the Convergence-Confinement Method. Kerisel in the Conference on Convergence-Confinement Method held in Paris proposed a method that takes the gravity loads into account. It is a method based on experiments on mini-tunnels and on the formulas for plastic equilibrium around a tunnel. The method enables a designer to calculate the gravity loads or "dead loads" as a function of the tunnel diameter, the soil unit weight and the distance between the support and face of the tunnel

- h) Two dimensional behaviour of the system: Characteristic Curves are limited to plane strain/plane stress conditions. This is a significant limitation of the C.-C. Method since the face effects on the ground and lining behaviour are of utmost importance.

Egger (1978) proposed a simple method to take

into account the face effects on excavation: the face is analytically modelled by a spherical face.

Lombardi (1970) proposed the simulation of the face by the sequential excavation of a core that has the tunnel diameter and length of one tunnel diameter. As the core is excavated, its load carrying capacity decreases and its wall displacements can be evaluated. The accuracy of the evaluation of the displacements that take place before the lining installation directly affects the accuracy of the prediction of loads and displacements by the Convergence-Confinement Method. Extensive finite element analyses have been carried out in order to study the three dimensional effects on tunnel design (Ranken and Ghaboussi (1975), Einstein and Schwartz (1980)).

5.3.4 Advantages of the Convergence-Confinement Method

The simplicity of the Convergence-Confinement Method is its major advantage. With the aid of only two curves, G.R.C. and S.R.C., the C.-C. Method provides a clear understanding and explanation of the process of tunnel construction.

The transfer of stresses from the ground to the lining, the effects of the delayed lining placement and concepts such as stand up time and many others are represented with

ease by the C.-C. Method whereas other simple solutions, such as Closed Form Solutions, are limited to yield a "frozen picture" of strains and stresses within the ground and lining at the equilibrium condition.

The C.-C. Method is of enormous utility in complementing the tunnel design but may, however, not be suitable for direct design procedures due to the reasons discussed in this section.

5.4 Application of Simple Solutions to Tunnels Driven in Edmonton Till

In this section, the lining loads and displacements obtained from three tunnels driven in Edmonton till are compared to the loads and displacements calculated by the Simple Solutions described in the last two sections.

The three tunnels discussed in this section are:

LRT- North-East line, north tunnel (LRT-NE tunnel)

LRT- South Extension, north tunnel (LRT-SE tunnel)

Experimental tunnel (EXP tunnel)

The studies related to the LRT-NE tunnel are reported by Eisenstein et al (1977), and Eisentein and Thomson (1978). In the LRT-NE tunnel, surface settlements and stresses in the lining were measured. The LRT-SE tunnel is described in Chapters 2 to 4 in this thesis. The two tunnels mentioned above were constructed under very similar conditions. The only difference between the two LRT tunnels,

despite minor local soil heterogeneities, is the size of the spacers installed in the two upper joints of the primary lining. The LRT-NE tunnel had spacers 10.2 cm long whereas in the LRT-SE the spacers were 15.2 cm long. The EXP-tunnel was comprehensively analysed by El-Nahhas (1980). It is a small diameter tunnel ($D=2.56\text{m}$) driven at a depth of 27 meters in the lower Edmonton till. Although the behaviour of two different types of lining (rib and lagging and precast concrete segments) were monitored in the EXP tunnel, only measurements from the rib and lagging system were related to the present study.

The lining and ground parameters, related to the three tunnels, used throughout the calculations carried out in this section are presented in Table 5.1.

The three tunnels studied in this section were constructed under very similar conditions. The construction method and lining system is the same for the three tunnels.

The differences in strength and stiffness between the lower till, where the EXP tunnel was excavated, and the upper till, where the LRT tunnels were excavated are considered not to significantly alter the analysis carried out throughout this section.

The difference in the depth ratio (depth of the center of the tunnel / tunnel diameter) of the LRT tunnels and the EXP tunnel is important in the analysis of the validity of the application of "Simple Solutions" in the analysis of shallow tunnels. The EXP tunnel has a depth ratio of 10.56,

TUNNEL	SOIL ELAS. PARAMETERS E (MPa)	SOIL DISPLACEMENTS TOWARDS THE TUNNEL (mm) (AT THE SPRINGLINE)			
		BEFORE		AFTER	
		FACE	EXPANSION	EXPANSION	EXPANSION
LRT SE & NE EXPERIMENTAL	150	0*	2.5*	0.5*	
	150	4	19	2.5+	

* ONLY MEASURED AT THE LRT-SE TUNNEL

+ Obtained from El-Nahas (1980) Fig 4.14

STEEL RIBS

TUNNEL	E (MPa)	I_s (m ⁴) MOMENT OF INERTIA	AS (m ²) AREA CROSS SECTION	SPACING (m)	DIAM. (m)	LOADS AT THE SPRINGLINE (p_i/p_o)
LRT	0.25	22.2*10 ⁻⁶	47.3*10 ⁻⁴	1.2	6.1	0.18 TO 0.24 (SE)
EXPERIMENTAL	0.25	4.76*10 ⁻⁶	24.7*10 ⁻⁴	1.5	2.56	0.62 TO 0.80 (NE) 0.02 to 0.12

TABLE 5.1 LINING AND GROUND PARAMETERS FOR THE LRT AND EXPERIMENTAL TUNNELS

and will be dealt with as a deep tunnel, whereas the LRT tunnels have a depth ratio of 1.90, and will be dealt with as shallow tunnels.

5.4.1 Analysis of the Results Obtained from Closed Form Solutions

The discussion presented in section 5.2 of this chapter showed the limitations of the available closed form solutions for deep lined tunnels. The solution proposed by Einstein and Schwartz (1979 and 1980) was chosen for this section. The assumptions involved in the derivation of this solution are summarized as:

- Plane strain condition
- Elastic behaviour of the ground and support
- Lining with constant cross section and constant mechanical properties
- Soil is isotropic and homogeneous
- The support and ground are simultaneously activated: no delayed installation of the support
- The unloading due to excavation is considered rather than external loading.

The required input for Closed Form Solutions related to ground and elastic support constants and the geometry of the support (diameter, cross sectional area, moment of inertia) is presented in Table 5.1.

The in-situ stress field is considered to be symmetric to both the vertical and horizontal tunnel axis ($k=1$). The magnitude of the field stress used in the calculations is calculated at the depth of the tunnel centreline.

The assumption that the in-situ stress ratio is equal to unity implies that in both cases, the full slip and no-slip between soil and structure yield identical results. The two cases yield the same results because when $K=1$, the shear stresses at the soil-liner interface is zero.

The equations presented in Fig 5.2 and the data presented in Table 5.1 make possible the calculation of the thrusts and deformations of the lining presented in Table 5.2. For the calculations of values presented in Table 5.2, the steel rib cross section area was divided by the rib spacing in order to obtain the effective cross section area, as recommended by Mohraz et al (1975).

The wooden lagging, installed between ribs, is assumed to have no self support capacity and does not enter into the calculations of the loads and displacements of the lining. A discussion of the self support capacity of the lagging is presented in Section 4.5.5.4.

The correction factors due to the delayed support installation and yielding ground, described in Section 5.2 are discussed in the next section.

TUNNEL	RATIOS		RIBS NORMAL LOAD (KN)		RADIAL DISPLACEMENT (mm)	
	C*	F*	CALCULATED	MEASURED	CALCULATED	MEASURED
LRT-NE	0.64	1302		461-585		-
LRT-SE			529	100-300	2.0	3.0+
EXP	0.42	534	552	14-83	1.3	24.0++

+ MEASURED AT 1.2m FROM THE LINING SPRINGLINE

++ MEASURED AT .6m FROM THE LINING SPRINGLINE

TABLE 5.2- LINING THRUSTS AND DISPLACEMENTS CALCULATED BY THE CLOSED FORM SOLUTION PROPOSED BY EINSTEIN AND SCHWARTZ (1979,1980) FOR THE LRT AND THE EXPERIMENTAL TUNNELS.

5.4.2 Comments on the Evaluation of Ground Support Interaction by the Closed Form Solution by Einstein and Schwartz (1979,1980)

For the calculation of the flexibility ratios (F^*) presented in Table 5.2, the existence of the four joints of the LRT tunnel primary lining and the three joints of the EXP tunnel primary lining was neglected. Even neglecting the "hinges" in the steel ribs, the values of F^* are found to be high. As discussed in section 5.2.1, for values of F^* greater than 100, the bending moments on the lining are near zero and the thrust calculations are insensitive to F^* which means that neglecting the lining joints does not affect the values of loads and displacements presented in Table 5.2.

The loads and lining displacements presented in Table 5.2 indicate that for the LRT-SE tunnel and the EXP tunnel, the thrusts on the lining are overestimated and the displacements underestimated when no corrections due to delay in the lining installation is applied to the linear elastic, closed form solution.

Table 5.2 also indicates that the loads measured in the LRT-NE tunnel were very close to that estimated, and that no correction factor due to delayed lining installation should be applied.

The correction due to the delayed lining installation, proposed by Einstein and Schwartz (1980), λ_d , presented in Section 5.2 is extremely difficult to estimate for the three tunnels studied in this section. The correction factor, λ_d ,

is a function of the distance between the face of excavation and the point where the lining first touches the ground (L_d). However, for tunnels excavated with a shielded mole, the span of unsupported ground is somewhat difficult to estimate.

In their study of some case histories on tunnel construction, Einstein and Schwartz proposed that, for tunnels excavated by a shielded mole, L_d should be the distance measured from the shield tail to the position where the lining touches the ground. This proposal assumes full contact between the shield and soil which is unreasonable for the stiff ground that surrounds the LRT and the EXP tunnels. Measurements taken from inside the LRT-SE indicate that there is a gap between the soil and the shield tail, hence, supporting the assumption that full contact between the soil and shield is unreasonable.

Values of λ_d varying from 0 to 0.8 for the LRT and EXP tunnels can be obtained from the calculations proposed by Einstein and Schwartz, which make the analysis of the results of Table 5.2 difficult. The yield factor (λ_y) based on finite element analyses carried out by Einstein and Schwartz indicate that yielding in the ground would result in an increase of up to 50% in the loads calculated from the elastic ground behaviour (Table 5.2).

If λ_y is equal to 1.5, λ_d would have to be 0.3 for the LRT-SE tunnel and 0.1 for the Experimental tunnel in order to obtain estimated loads similar to those measured at the

site.

Einstein and Schwartz (1980) stated that the loads calculated by their method are overestimated up to 75%. They also verified the difficulty in the evaluation of λ_d , which is responsible for most of the inaccuracy of the method.

From the discussion presented in this chapter, it can be concluded that the prediction of lining thrusts by the Closed Form Solution is inaccurate for both deep and shallow tunnels.

It is believed that the construction details and the heterogeneity of the soil mask the inaccuracy of the application of Closed Form Solution for shallow tunnels.

The influence of the construction details and local heterogeneities on the lining thrusts can be verified by comparing the lining thrusts measured in the two LRT tunnels: the measured lining thrusts are very different despite of the fact that the two tunnels were built under identical conditions.

5.4.3 Analysis of the results obtained from the Convergence-Confinement Method

The normalized Ground Reaction Curve (GRC) for openings in the Edmonton till is plotted in Figure 5.7. The assumptions and equations involved in the plot of Ground Reaction Curves are shown in Figure 5.7 and described in Section 5.3 of this chapter. It is interesting to note that the Ground Reaction Curve, in the normalized form




Figure 5.7 CHARACTERISTIC CURVES FOR THE LRT AND EXPERIMENTAL TUNNELS

$(P_i/P_o U_i/U_o^e)$ is a function only of " λ_e " and " m " (defined in section 5.3). In the case where the soil cohesion is assumed to be zero, the normalized G.R.C. is a function only of the soil friction angle and the coefficient of dilation (α), irrespective of the soil elastic parameters in-situ stress field and size of the opening. The parameters E , ν , σ_o , D , are used when a specific displacement or pressure is to be plotted on the normalized G.R.C. plot.

The coordinates " λ_e ", for the displacement ratio, and " $1-\lambda_e$ " for the pressure ratio, indicated in Fig 5.7, define the point where the onset of plasticity takes place around the opening.

Three different kinds of points of equilibrium ¹ of the soil-structure interface, for the LRT and EXP tunnels, are shown in Fig 5.7 as E_a , E_b , and E_c .

1) E_a :

This is the point of equilibrium defined by the intersection of two curves, viz., the theoretical ground reaction and the support reaction curves.

The plot of the support reaction curves shown in Figure 5.7 requires a knowledge of the compressive stiffness of the support, calculated in Appendix D, and a knowledge of the ground displacement close to the ground support interface, that takes place before the lining expansion (U_{b1}).

¹ The point of equilibrium is defined by the coordinates P_i/P_o , pressure ratio, and U_i/U_o^e , displacement ratio, plotted in the characteristic lines graph (Fig 5.7).

The amount of ground displacement that takes place at the soil-structure interface before the lining expansion, is defined as being the sum of two ground displacements:

- a) Ground displacements that take place ahead of the face of the tunnel: assumed to be one third of the final elastic wall displacement of the unlined tunnel ($U_0^e/3$) (Ranken and Ghaboussi, 1975).
- b) Ground displacements that take place along the length of the excavating machine are assumed to be one half of the difference between the excavated diameter and the diameter of the expanded primary lining.

The estimation of " U_{b1} " is presented in Table 5.3.

2) E_b :

This is the point of equilibrium defined by the intersection of two curves, viz., the theoretical ground reaction and the support reaction curves.

The difference between E_b and E_a is associated with the ground displacement that takes place before the lining expansion (U_{b1}):

In order to find E_a , " U_{b1} " is simply estimated based on a calculation, presented in Table 5.3, without taking into account any information from the tunnel instrumentation. On the other hand, the plot of the support reaction curve that defines the point of equilibrium, E_b , is based on the measured ground displacements that take place before the

TUNNEL	$P_o \text{ (kN/m}^2\text{)}$	$u_o^e = \frac{P_o(1+\nu)D}{2E}$	$\frac{D_{\text{excav.}} - D_{\text{lin}}}{2}$	$u_{bl} = \frac{\Delta D}{2} + \frac{u_o^e}{3}$	$\frac{u_{bl}}{u_o^e}$
LRT TUNNELS	236	6.8mm	37mm	39.3mm	5.8
EXPERIMENTAL TUNNEL	540	6.5mm	20mm	22.2mm	3.4

where: u_{bl} = Ground displacement that takes place at the soil-structure interface, before the lining expansion.
 u_o^e = Elastic wall displacements of the unlined tunnel.
 P_o = In situ stress at the tunnel springline.

TABLE 5.3 - ESTIMATION OF THE GROUND DISPLACEMENTS AT THE SOIL-STRUCTURE INTERFACE THAT OCCUR BEFORE THE LINING EXPANSION.

lining expansion ($U_{bl-meas}$) obtained from field instrumentation

The values of $U_{bl-meas}/U_0^e$ are presented in Table 5.4.

3) E_c :

This is the range of points of equilibrium obtained from the lining and ground instrumentation.

Table 5.5 indicates the pressure and displacement ratios (P_i/P_o and $U_{final-meas}/U_0^e$) calculated for three tunnels:

- LRT - South Extension - North tunnel
- LRT - North-East line - North tunnel
- Experimental tunnel

The range of points of equilibrium (E_c) related to the LRT-NE tunnel was plotted on Figure 5.7 based on certain assumptions because no ground displacements at the springline were available for this tunnel. It was assumed that the ground displacements at the springline of the LRT-NE tunnel are equal to the ones measured in the LRT-SE tunnel. The assumption of equal lining displacement in the two LRT tunnels is based on the fact that these two tunnels were built with very similar geometry, constructions method and ground conditions, and caused similar surface settlements.

The load and displacement ratios defining " E_c " are related to the springline of the tunnels studied in this section because at the springline, more complete information was available.

TUNNEL	$P_o \text{ (kN/m}^2\text{)}$	$u_o^e = \frac{P_o(1+\nu)D}{2E}$	$u_{bl-meas}$	$\frac{u_{bl-meas}}{u_o^e}$
LRT	236	6.8mm	2.5mm	0.37
EXPERIMENTAL	540	6.5mm	19mm	2.92

where: $u_{bl-meas}$ = Measured ground displacements at the soil-structure interface that take place before the lining expansion.

u_o^e = Elastic wall displacements of the unlined tunnel.

P_o = In situ stress at the tunnel springline.

Table 5.4 CALCULATION OF THE RATIO $U_{bl-meas}/U_o$

TUNNEL	$P_o \text{ (kN/m}^2\text{)}$	P_i/P_o	$u_o^e = \frac{P_o(1+\nu)D}{2E}$	$u_{\text{final-meas}}$	$\frac{u_{\text{final-meas}}}{u_o^e}$
LRT-SOUTH EXT	236	0.18 to 0.24	6.8mm	3mm	0.44
LRT-NORTH EAST	236	0.63 to 0.80	6.8mm	3mm	0.44
EXPERIMENTAL	540	0.02 to 0.12	6.5mm	24mm	3.75

where: $u_{\text{final-meas}}$ = Final ground displacement at the soil-structure interface.
 u_o^e = Elastic wall displacements of the unlined tunnel.
 P_o = In situ stress at the tunnel springline.

Table 5.5 CALCULATION OF THE RATIO $u_{\text{final-meas}}/u_o$

The value of the modulus of elasticity, E , chosen for the Edmonton till, 150 MN/m^2 , is based on the pressuremeter tests reported by Morrison (1972).

5.4.4 Comments on the Evaluation of the Ground Support Interaction by the Convergence-Confinement Method

The analysis of the "points of equilibrium" plotted for the soil-structure interface of the EXP tunnel, in Fig 5.7, indicates that thrusts and lining displacements can be reasonably well predicted using the Convergence-Confinement Method.

The measured loads and displacements, in the EXP tunnel are greater than those estimated but not to a significant extent. The reason for higher measured values may be ascribed to a higher degree of soil disturbance during tunnel construction. An increase in the soil disturbance would probably result in a decrease in the soil elasticity modulus and shear strength that would yield greater loads and lining displacements.

As opposed to the EXP tunnel, the predictions of loads on the lining and ground displacements for the LRT tunnels based on the characteristic lines method yielded loads and displacements completely different than those measured.

The comparison between E_c , measured loads and displacements, and E_a , estimated loads and displacements, obtained for the LRT tunnels, indicates that the convergence confinement method predicts much higher displacements and

much lower thrusts in the lining than those measured.

The comparison between E_c and E_b , related to the LRT tunnels, indicate that the discrepancy between measured and expected loads and lining displacements is basically due to the inaccurate estimation of ground displacements ahead of the lining expansion. The estimated loads and lining displacements compare better to those measured when the point of equilibrium of the soil-structure interface is estimated on the basis of the ground movements obtained from the field instrumentation (E_b).

The inaccurate assessment of ground displacements that take place before the lining expansion is believed to be the result of the non-axisymmetric mode of deformation and development of plasticity around shallow tunnels, even in the case where K (stress field ratio) is approximately 1. The fact that the mode of deformation is responsible for the inaccuracy of the soil structure interactions predicted for the LRT is supported by the fact that after the non-axisymmetric mode of deformation ceases, i.e. when the lining is expanded against the ground, the loads and displacements predicted by the C.-C. Method become close to the measured ones.

It is believed that the soil disturbance due to tunnel construction strongly affects the boundary condition and consequently the mode of deformation of the soils around shallow tunnels.

As already mentioned in section 5.2, elastic finite element studies indicate that the LRT tunnels are at the boundary of being defined as a deep or shallow tunnel. The study of the LRT and the EXP tunnels indicated that this definition, based on finite element analyses, is not necessarily valid.

The definition of difference between deep and shallow tunnels based on stress and strain distribution around openings should take into account the construction technique used and particularly the sequence of lining installation in order to evaluate more effectively the effect of the opening excavation on the boundaries.

The study of the prediction of the soil-structure interaction for deep and shallow tunnels, constructed in a similar manner, indicated that, for the Convergence-Confinement Method (Section 5.3.3), the limitations related to the mode of deformation on the ground and of the lining are of major importance.

The discrepancy between measured and estimated ground displacements at the springline of the LRT-SE tunnel before the lining is expanded might also be due to the distance between the inclinometers and the lining. The distance between the inclinometer at the springline level and the LRT-SE lining is 1.2 metre. If soil expansion takes place within this 1.2 metre space, the measured displacements would be smaller than those at the soil-liner interface.

The comparative study of the LRT tunnels and the EXP tunnel is not invalidated by the distance between the inclinometer and LRT lining because in the EXP tunnel, the inclinometer that yielded the results reported in this section was installed at 0.6 metre from the liner which is considered large compared to the tunnel diameter.

5.5 Summary and Conclusions of the Evaluation of Soil-Structure Interaction by "Simple Solutions"

In this chapter, the applicability of Closed Form Solutions and the Convergence-Confinement Method for the evaluation of the soil-structure interaction in shallow tunnels was analysed. This analysis was based on the data collected from two types of tunnels constructed under very similar conditions, viz., the shallow LRT tunnels and the deep EXP tunnel.

It was concluded that the thrusts and lining displacements predicted by the closed form solution proposed by Einstein and Schwartz (1979,1980) were only comparable to those measured in the LRT-NE tunnel.

For the LRT-SE and EXP tunnels, the measured thrusts were much smaller than those predicted.

The correction to the lining thrusts and moments calculated by the Closed Form Solution due to delayed lining installation and yielding ground was discussed in this chapter. It was concluded that the delayed lining

installation correction factor (λ_d) is difficult to predict for tunnels excavated in stiff ground by shielded tunnel boring machines.

The difficulty in predicting λ_d masks the effects of the proximity of the surface on the thrusts and lining displacements calculated by the Closed Form Solutions.

The evaluation of the soil-structure interaction by the Characteristic Lines Method was found to be good for the deep tunnel, i.e. the EXP tunnel. The boundary conditions and mode of deformation in the Experimental tunnel are probably closer to those assumed by the Characteristic Lines Method.

The lining loads and ground deformations predicted by the Characteristic Lines Method for the LRT tunnels, were different than those observed. The predicted displacements at the tunnel springline were much greater than those measured. The reasons for the discrepancy between predicted and measured displacements were ascribed to the fact that the mode of deformation of the soil surrounding the LRT tunnels was not equal to that assumed in the derivation of the characteristic lines in the Convergence-Confinement Method.

A departure from the uniform radial mode of behaviour (axisymmetric) assumed by the C.-C. Method might be due to:

- A lower value of the in-situ stress ratio ($K < 1$)
- The heterogeneous nature of the upper till, with the presence of the inter-till sand in the

proximity of the tunnel.

- the proximity of the tunnel to the surface

The fact that an in-situ stress ratio close to unity has been verified in the upper Edmonton till and that only small sand pockets were detected close to the tunnel instrumentation might be an indication of the importance of proximity of the tunnel to the surface on the departure from the axisymmetric behaviour in the LRT-SE tunnel.

The use of the Convergence-Confinement Method in the study of the soil-structure interaction of the tunnels presented in this section was extremely useful. The plot of estimated and measured loads and displacements on the ground and lining on Figure 5.7 gave an indication of the importance of the proper assumptions concerning the mode of behaviour around shallow openings.

There is a great need for the development of simple solutions for shallow tunnels. The existence of Simple Solutions would help the tunnel design but its limitations can be foreseen because the discrepancy between the loads measured in the two LRT tunnels can only be explained by the complete knowledge of minor construction details and local heterogeneity. These can hardly be incorporated in a Simple Solution.

6. CONCLUSIONS

6.1 Introduction

The research herein examined the behaviour of a large diameter, shallow tunnel, built in stiff ground for the extension of the Light Rail Transit System of the City of Edmonton, Alberta.

The analysis of the factors affecting the behaviour of the tunnel lining and surrounding ground was based on the data collected from a comprehensive monitoring program. The comparison of the results from a deeper, small diameter tunnel, with a different depth ratio (depth of the centre of the tunnel/tunnel diameter) allowed the analysis of the influence of the depth ratio on the mode of deformation and plastic behaviour of the soil and how these affect the lining behaviour.

The following sections summarize the major findings of this research.

6.2 Soil Response to Tunneling

6.2.1 Surface Vertical Displacements

The surface settlement points indicated that the surface settlement trough was not symmetric to the tunnel axis. This asymmetry might be due to the presence of inter-till sand pockets, non-symmetric to the tunnel axis

or/and due to the presence of buildings at only one side of the tunnel axis. The shallow foundations of these buildings might locally increase the soil stiffness, resulting in smaller settlements.

The asymmetry observed in the transverse sections of the surface settlements troughs indicates that they do not fit the Gaussian distribution of surface settlements proposed by Litviniszyn (1956) and Peck (1969).

The steeper portions of the transverse section of the settlement troughs occur in a narrow region above the tunnel and do not affect the buildings located 10 metres from the tunnel axis, where the differential settlements are approximately 1:17000.

Negligible surface vertical displacements were measured ahead of the face of the mole. These displacements stabilized 15 metres behind the face of the mole.

6.2.2 Deep Vertical Displacements

Before the mole reached a section, points close to the soil to be excavated along a vertical line passing through the tunnel axis experienced heave of up to 3mm. Negligible downward movements were detected ahead of the face of the mole.

During the tunnel excavation, the extensometers located beside the tunnel liner did not measure significant soil straining in the vertical direction ($\epsilon_{\text{vert}} < 0.1\%$)

The stabilization of vertical displacements of the soil occurred approximately 15 metres from the face of the mole.

The monitoring of vertical movements above a roof failure indicated that large vertical displacements (larger than 50mm) propagated up to 3.4 metres to 4.5 metres above the tunnel crown. The settlements at the surface, above this roof failure, were small and should not affect the nearby building foundations.

6.2.3 Deep Horizontal Displacements

The inclinometers located at 1.2 metre and 3.3 metres from the tunnel liner, at the springline, measured horizontal displacements of 3.0mm and 2.0mm, respectively, towards the tunnel axis. The development of horizontal movements towards the tunnel axis started 3.0 metres ahead of the face of the mole and stabilized approximately 6.0 metres from the tail of the mole, where the primary lining was expanded against the ground. It can be concluded that the horizontal displacements in the soil stabilized faster than the vertical ones.

The development of soil movements in the direction parallel to the tunnel axis indicated that analytical studies of tunnel behaviour based on plane strain analyses do not reflect reality. The fact that the points in the ground move in a direction parallel to the tunnel axis during tunneling and return to their initial position, after the mole passes, enhances the fact that studies of the final

displacements about tunnels that do not take into account the soil "strain history" are not acceptable.

6.2.4 Loss of Ground

The coupled analysis of vertical and horizontal displacements around the LRT tunnel yielded the conclusion that the ground experienced an average volume increase of $0.59 \text{ m}^3/\text{lineal metre}$ (1.96% of the tunnel nominal volume) due to tunnel construction. Similar ground volume increases were measured by Hansmire (1975) in a tunnel dug in dense sand.

More than 96% of the ground volume increase due to the LRT tunnel construction occurred in the region above the tunnel crown.

6.3 Lining Loads and Displacements

The loads carried by the steel lagging and load cells were affected by the action of the longitudinal propulsion jacks of the mole on the primary lining.

The load cells installed in the lower rib joints consistently picked up higher loads than those installed in the upper joints. This reflects the development of shear at the soil-liner interface, probably due to the upward movement of the liner detected in the lining displacement measurements. The load cells also indicated higher soil stress relief at the invert than at the crown. This

difference in soil stress relief might also be due to the upward movement of the liner.

The coupled study of the steel lagging and load cell data indicated that the steel ribs carried average loads 85% to 213% higher than those carried by the lagging. This might be an indication that soil arching occurred between ribs.

The steel ribs at the crown carried loads from 9% to 26% of the overburden. These loads are smaller than those measured in the LRT North East tunnel (71% of overburden).

The lining displacements measurements indicated that after rib expansion, there is very little liner distortion.

6.4 Soil-Structure Interaction

The study of the soil displacements associated with the loads on the primary lining in tunnels constructed in Edmonton with different depth ratios (depth of center of the tunnel/tunnel diameter) enabled the analysis of the applicability of Closed Form Solutions and the Convergence-Confinement Method, termed Simple Solutions, to shallow tunnels. This analysis showed that the prediction of lining loads and displacements with Closed Form Solutions is inaccurate for both deep and shallow tunnels, basically due to the difficulty of taking into account the delayed installation of the lining. It was concluded that the prediction of tunnel behaviour based on the Confinement-Convergence Method yielded good results for deep

tunnels but not for shallow tunnels.

The discrepancy between predicted and measured displacements is ascribed to the fact that the mode of deformation and development of plasticity of the soil surrounding the LRT tunnels was not axisymmetric, as assumed by the Convergence-Confinement Method. The departure from the uniform radial mode of behaviour (axisymmetric) was ascribed to the proximity of the LRT tunnels to the surface.

6.5 Recommendations for Further Studies

The conclusions presented in this Chapter indicate that there is no simple method that permits the engineer to rapidly investigate alternatives to problems related to shallow tunnels. It is suggested that further studies to develop Closed Form Solutions for shallow lined tunnels should be carried out. These Closed Form Solutions would probably lead to simple design methods applicable to shallow tunnels.

REFERENCES

- Attewell, P.B., and Farmer, I.W. 1974a. Ground deformation resulting from shield tunnelling in London clay, Canadian Geotechnical Journal, Vol. 11, pp. 380-395.
- Attewell, P.B., and Farmer, I.W. 1974b. Ground disturbance caused by shield tunnelling in stiff overconsolidated clay. Engineering Geology, Vol. 8, pp.361-381.
- Attewell, P.B., and Farmer, I.W. 1975. Ground settlement above shield driven tunnels in clay. Tunnels and Tunnelling, Vol. 7, No. 1, pp.58-62.
- Burke, H. 1957. Garrison Dam tunnel test section investigation. Journal of Soil Mechanics and Foundations Division, ASCE, Vol. 83, paper no. 1438.
- Burland, J.B., and Moore, J.F.A. 1973. The measurement of ground displacement around deep excavations. Field Instrumentation in Geotechnical Engineering, Butterworth and Co., London, pp.70-84.
- Burns, J.Q. and Richard, R.M. 1964. Attenuation of stresses for buried cylinders. Proceedings on Symposium on Soil-Structure Interaction, Tucson, pp. 378-392
- Chatterji, P.K., Smith, L.B., Insley, A.E., and Sharma, L. 1979. Construction of Saline Creek Tunnel in Athabasca Oil Sand. Canadian Geotechnical Journal, Vol. 16, pp. 90-107.
- Cording, E.J., Hendron, A.J., PacPherson, H.H. Hansmire, W.H., Jones, R.A., Mahar, J.W. and O'Rourke, T.D. 1975. Methods for geotechnical observations and instrumentation in tunneling. Report prepared for U.S.
- Curtis, D.J. 1976. The circular tunnel in elastic ground. Discussion. Geotechnique, Vol. 26, pp.231-237.

Daemen, J.J.K. and Fairhurst, C. 1970. Influence of failed rock properties in tunnel stability. 12th Symposium on Rock Mechanics. Rolla, Missouri, pp. 855-875.

Daemen, J.J.K. and Fairhurst, C. 1972. Rock failure and tunnel support loading. Proceedings of the International Symposium on Underground Openings. Luzern, Switzerland

Delory, F.A., Crawford, A.M., and Gibson, M.E.M. 1979. Measurements on a tunnel lining in very dense till. Canadian Geotechnical Journal, Vol. 16, pp. 190-199.

Eisenstein, Z., Kulak, G.I., MacGregor, J.G., and Thomson, S. , 1977. Report on Geotechnical and Construction Performance of the Twin Tunnels. Unpublished report prepared for the City of Edmonton Engineering Dpt., Edmonton, Alberta, 77 pp.

Eisenstein, Z., and Thomson, S. 1978. Geotechnical performance of a tunnel in till. Canadian Geotechnical Journal, Vol. 15, pp. 332-345.

Einstein, H.H. and Schwartz, C.W. 1979. Simplified analysis for tunnel supports. ASCE Journal of Geotechnical Engineering Division, July 1979, pp. 499-518.

Einstein, H.H. and Schwartz, C.W. 1980. Improved design of tunnel supports volumes 1 and 2. Report prepared for the U.S. Dept of Transportations. Report numbers: UMTA-MA-06-0100-80-4 and 5.

El-Nahhas, F. 1977. Field measurements in two tunnels in the City of Edmonton. M.Sc. Thesis, Departement of Civil Engineering, University of Alberta, Edmonton, Alberta, 85p.

El-Nahhas, F. 1980. The behaviour of tunnels in stiff soils. Ph.D. Thesis, Dpt. of Civil Engineering, University of Alberta. Edmonton, Alberta, 305 pp.

Figueiredo, A.F. and Negro, A. 1981. A new sensing system for boreholes extensometers. Unpublished technical note.

- Gould, J.D. and Dunnicliff, C.J. 1971. Accuracy of field deformation measurements. Proceedings of the 4th Pan American Conference on Soil Mechanics and Foundation Engineering, Puerto Rico, Vol. 1, pp.313-366.
- Hanna, T.H. 1973. Foundation instrumentation. Trans. Tech. Publications, Cleveland.
- Hansmire, W. 1975. Field measurements of ground displacements about a tunnel in soil. Ph.D. Thesis, University of Illinois at Urbana-Champaign.
- Hedley, D.G.F. 1969. Design criteria for multi-wire borehole extensometer systems. First Canadian Symposium on Mining Surveying and Rock Deformation Measurements.
- Hoek, E. and Brown, E.T. 1981. Underground excavations in rock. Inst. Min. and Met., London
- Kaiser, P.K. 1980. Effect of stress history on the deformation behaviour of underground openings. 13th Canadian Rock Mechanics Symposium, pp. 133-140.
- Kaiser, P.K. 1981. University of Alberta CIVE 699 Unpublished class notes.
- Kanji, M.A. 1979. Surface displacement as a consequence of excavation activities (General Report, Theme IV). Proc. 4th Rock Mech. Congress, Int. Soc. Rock Mech., Montreux, Vol 3, pp 345-368.
- Kathol, C.P. and McPherson, R.A. 1975. Urban geology of Edmonton. Alberta Research Council, Bulletin 32, 61p.
- Kerisel, J.; Duddeck, H.; Lombardi, G.; Fairhurst, C. and Daemen, J.J.K; Egger, P. 1978. Proceedings of the Conference on Analysis of Tunnel Stability by the Convergence-Confinement Method, Underground Space, 1980, Vol. 4, No. 4, 5 and 6, pp.221-258, 297-318 and 361-402.
- Kovari, K., Amstad, C.H., Fritz, P. 1977. Integrated measuring technique for rock pressure. Int. Symposium on Field measurements in Rock Mechanics, Zurich, pp.

289-316.

- Ladanyi, B. 1974. Use of long-term strength concept in the determination of ground pressure on tunnel linings. Proc. of the 3rd Inter. Cong. on Rock Mechanics, Vol. 2B, pp. 1150-1156.
- Litviniszyn, J. 1956. Application of the equation of stochastic processes to mechanics of loose bodies. Arch. Mech. Stosow, Vol.8, pp.393-411.
- Lombardi, G. 1970. The influence of rock characteristics on the stability of rock cavities. Tunnels and Tunnelling, Vol. 2, pp. 104-109.
- Lombardi, G. 1973. Dimensioning of tunnel linings with regards to constructional procedure. Tunnels and Tunnelling, Vol. 5, pp. 340-351.
- May, R.W. and Thomson, S. 1978. The geology and geotechnical properties of till and related deposits in the Edmonton, Alberta, area. Canadian Geotechnical Journal, Vol. 15, pp. 362-370.
- Medeiros, L. 1979. Deep excavations in stiff soils. Ph.D. Thesis, Departement of Civil Engineering, University of Alberta.
- Mello, V.F.B. 1981. Proposed bases for collating experiences for urban tunneling design. Proceedings of the Symposium on Tunneling and Deep Excavations in Soils, Sao Paulo, Brazil, pp. 197-235.
- Mendes, R.H., Brown, E.L., Moreau, R. and Boyer, B. 1970. Supervision of the behaviour of Daniel Johnson Dam (Manicouagan 5). Trans. 10th Intl. Cong. on Large Dams, Montreal, Vol III, pp. 1183-1205.
- Mindlin, R.D. 1940. Stress distribution around a tunnel. Trans. American Society of Civil Engineering, Vol 105, pp. 1117-1140.
- Mohraz, B., Hendron, A.J., Ranken, R.E. and Salem, M.H. 1975. Liner medium interaction in tunnels ASCE

Journal of the Construction Division, March 1975, pp. 127-141.

- Morgan, H.D. 1961. A contribution to the analysis of stress in a circular tunnel, *Geotechnique*, Vol. 11, pp. 37-46.
- Muir Wood, A.M. 1975. The circular tunnel in elastic ground. *Geotechnique*, Vol. 25, pp. 115-127.
- Obert, L. and Duvall, W.I. 1967. *Rock mechanics and the design of structures in rock*. New-York, John Wiley and Sons.
- Panet, M. 1976. *Stabilite et Soutenement des tunnels. La mecanique des roches appliquee aux ouvrages du Genie Civil*, Chapitre IX, pp 143-168. L'Ecole Nationale des Ponts et Chausses.
- Peck, R.B. 1969-a. Advantages and limitations of the Observational method in applied soil mechanics. 9th Rankine Lecture, *Geotechnique*, Vol. 19, pp 171-187.
- Peck, R.B. 1969-b. Deep excavations and tunnelling in soft ground. State of the Art Report. Proc. 7th Int. Conf. on Soil Mech. and Found. Eng., Vol. 3, Mexico City, Mexico, pp. 225-290.
- Peck, R.B., Hendron, A.J. and Mohraz, B. 1972. State of the art of soft-ground tunneling. Proceedings of the 1st North American Rapid Excavation and Tunneling Conference, Vol. 1, pp.259-286.
- Ranken, R.E. and Ghaboussi, J. 1975. Tunnel design considerations: Analysis of stresses and deformations around advancing tunnels. Report prepared for U.S. Department of transportation, UILU-ENG75-2016.
- Ryzuk, C.N. 1977. Details of multipoint extensometers used to monitor deformation in a tunnel in oil sands. Memorandum to Dr. N.R. Morgenstern, unpublished.
- Savigny, K.W. 1980. In situ analysis of naturally occurring creep in ice-rich permafrost soil. Ph.D. Thesis, Dpt.

of Civil Engineering, University of Alberta,
Edmonton, Alberta. pp 439.

Schmidt, B. 1969. Settlement and ground movement associated with tunnelling in soil. Ph.D. Thesis, Department of Civil Engineering, University of Illinois, Urbana.

Thomson, S. and El-Nahhas, F. 1980. Field measurements in two tunnels in Edmonton, Alberta. Canadian Geotechnical Journal, Vol. 17, pp. 20-33.

Terzaghi, K. 1938. Settlement of structures in Europe and methods of measurement. Transactions, ASCE, Vol. 103, 1432.

Thurber Consultants Ltd. 1980. Subsurface conditions, Central Station to Government Centre Station. Unpublished report prepared for the City of Edmonton, LRT, Edmonton, Alberta.

U.S.B.R. 1963. Earth manual, U.S. Bureau of Reclamation, Denver Colorado.

Ward, W.H., Burland, J.B. and Gallois, R.W. 1968. Geotechnical assessment of site at Mundford, Norfolk for a large proton accelerator. Geotechnique, Vol. 18, No.4, pp. 399-431.

Westgate, J.A. 1969. The Quaternary geology of the Edmonton area, Alberta. In Pedology and Quaternary research. Edited by S. Pawluk. University of Alberta Printing Department, Edmonton, Alberta, pp.129-151.

Wilson, S.D. 1962. The use of slope measuring devices to determine movements in earth masses. ASTM STP 322, Field Testing of Soils, pp.187-197.

A. APPENDIX - LABORATORY TEST RESULTS

TEST HOLE	DEPTH (m)	w _l (%)	w _p (%)	w _l (%)	I _p (%)	% SAND	% SILT	% CLAY	BULK DENSITY (Mg/m ³)	UNDRAINED SHEAR STRENGTH (kPa)
A. CLAYS										
79-1	3.8-4.3	26.4	29.4	65.0	35.6	9.0	47.0	44.0	2.01	63
79-2	3.8-4.3	33.2	19.1	61.9	42.8	6.0	54.0	40.0	1.98	101
79-3	3.8-4.3	32.3	23.8	70.9	47.8	7.0	38.0	55.0	1.95	141
79-6	5.3-5.6	38.2	20.9	46.5	25.6	-	70.0	30.0	1.95	60
79-10	3.8-4.3	33.7	22.9	59.1	36.2	-	64.5	35.5	1.94	81
79-15	3.8-4.3	31.5	18.2	32.9	14.7	5.0	85.0	10.0		
79-18	2.4-2.9	32.3	27.2	64.6	37.4	5.0	51.0	44.0		
79-20	5.8-6.2	39.4	27.7	49.9	22.2	1.5	69.5	29.0	1.81	44
79-21	4.1-4.6	34.6	27.7	57.5	29.8	12.5	50.0	37.5	1.91	96
79-23	3.7-4.1	28.0	32.6	78.7	46.1	2.0	36.0	62.0	1.84	86
79-23	5.2-5.6	34.3							1.86	137
B. SILTS										
79-13	6.9-7.3	33.3	27.8	35.3	7.5	5.0	82.0	13.0	-	-
79-14	6.9-7.3	35.7	26.2	34.2	8.0	10.0	81.0	9.0	-	-
79-16	5.3-5.8	21.1	27.7	30.4	2.7	1.0	89.0	10.0	-	-

Table A.1 SUMMARY OF LABORATORY TEST RESULTS - LAKE EDMONTON SEDIMENTS

TEST HOLE	DEPTH (m)	Wi (%)	Wp (%)	Wl (%)	Ip (%)	% SAND	% SILT	% CLAY	BULK DENSITY (Mg/m ³)	UNDRAINED SHEAR STRENGTH (kPa)
79-1	8.4- 8.7	14.4	18.1	34.9	16.8	40.0	40.0	20.0	2.15	344
79-2	9.9-10.2	14.1	16.4	26.8	10.4	45.0	47.5	7.5	2.16	54*
79-3	8.4- 8.7	12.7	16.8	27.8	11.0	41.0	43.0	16.0	2.24	339
79-3	13.1-13.5	12.1	14.9	31.9	17.0	42.0	37.0	21.0	2.23	342
79-4	5.3- 5.8	28.7	18.2	43.2	25.0	24.0	49.0	27.0	2.01	54*
79-5	8.4- 8.7	16.3	16.9	38.4	21.05	37.5	39.0	23.5	2.25	175
79-8	8.4- 8.7	13.6	15.9	30.5	14.6	45.0	40.0	15.0	2.30	198
79-11	8.4- 8.7	14.5	15.8	34.3	18.5	37.0	45.0	17.5	2.27	365
79-19	11.6-11.9		16.7	34.2	17.5	40.0	41.0	19.0		
79-22	7.3- 7.8	24.2	16.2	29.9	13.7	47.5	36.5	16.0	2.12	325

*Sheared along vertical crack.

LEGEND: Wi in situ water content
Wp plastic limit
Wl liquid limit
Ip plasticity index

Table A.2 SUMMARY OF LABORATORY TEST RESULTS - BROWN TILL

TEST HOLE	DEPTH (m)	wl (%)	Wp (%)	Wl (%)	Ip (%)	% SAND	% SILT	% CLAY	BULK DENSITY (Mg/m ³)	UNDRAINED SHEAR STRENGTH (kPa)
79-1	13.0-13.4	11.3	19.3	34.8	15.4	40.0	40.0	20.0	2.33	363
79-1	16.0-16.5	12.0	15.6	38.0	22.4	36.0	40.0	24.0	2.24	540
79-2	14.8-15.2	13.2	16.4	29.1	12.7	45.0	40.0	15.0	2.24	315
79-2	17.8-18.3	14.9	15.5	39.6	24.1	36.0	40.0	24.0	2.19	259
79-2	20.6-21.0	24.6	20.8	66.8	46.0	9.0	36.0	55.0	2.03	176
79-2	22.1-22.6	24.5	21.5	49.5	28.0	20.0	53.0	27.0	2.00	192
79-2	23.6-24.1	18.0	20.6	51.8	31.2	16.0	42.5	41.5	2.17	240
79-3	17.5-17.8	15.5	14.2	38.0	23.8	36.0	39.0	25.0	2.17	218
79-3	19.0-19.5	15.7	18.3	40.6	22.3	32.0	40.5	27.5	2.12	254
79-3	20.6-21.0	15.9	14.8	38.1	23.3	36.0	39.0	25.0	2.19	187
79-3	22.1-22.6	14.2	18.8	40.2	21.4	32.0	41.0	27.0	2.17	383
79-5	16.0-16.3	15.0	14.9	36.6	21.7	35.0	42.0	23.0	2.31	225
79-5	19.1-19.4	16.3	15.6	35.4	19.8	39.0	39.5	21.5	-	-
79-5	22.1-22.6	12.7	16.6	34.9	18.3	42.5	35.5	22.0	2.21	380
79-6	22.1-22.6	12.6	18.7	42.5	23.8	35.0	36.5	28.5	2.21	680

Table A.3 SUMMARY OF LABORATORY TEST RESULTS - GREY TILL

TEST HOLE	DEPTH (m)	wl (%)	Wp (%)	Wl (%)	Ip (%)	% SAND	% SILT	% CLAY	BULK DENSITY (Mg/m ³)	UNDRAINED SHEAR STRENGTH (kPa)
79-10	16.0-16.5	14.6	14.2	36.2	22.0	35.5	43.5	21.0	2.25	250*
79-18	14.8-15.2	18.7	18.7	29.4	10.7	13.0	77.0	10.0	2.06	180
79-18	20.7-21.2	16.6	16.8	35.0	18.2	42.0	35.5	22.5	1.97	163
79-20	13.0-13.4	19.8	17.2	30.9	13.7	41.0	42.0	17.0	2.32	220
79-21	22.1-22.6	15.9	16.8	37.4	20.6	41.0	36.0	23.0	2.13	245
79-22	7.3- 7.8	17.4	16.2	29.9	13.7	47.5	36.5	16.0	2.12	225
79-22	10.4-10.8	15.5	16.3	32.7	16.4	41.5	41.0	17.5	2.21	183
79-22	16.2-16.6	16.3	17.4	33.6	16.2	38.0	41.0	21.0	2.20	243
79-24	14.8-15.3	10.1	15.7	32.9	17.2	44.5	35.0	20.5	2.24	662
79-25	16.3-16.8	11.1	17.2	31.5	14.3	41.0	42.0	17.0	2.22	486
79-26	14.8-15.3	14.5	16.3	36.9	20.6	40.5	37.0	22.5	2.10	155
79-26	17.5-18.0	14.2	16.1	34.7	18.6	42.0	38.0	20.0	2.03	139
79-26	22.1-22.6	18.6	22.7	50.6	27.9	27.5	42.5	30.0	2.06	94

* Modulus of Elasticity as measured in Cyclic Compressive Test was 110 MPa.

Table A.4 SUMMARY OF LABORATORY TEST RESULTS - GREY TILL
(cont)

Table A.5 SUMMARY OF LABORATORY TEST RESULTS - INTER-TILL SANDS

<u>Test Hole</u>	<u>Depth (m)</u>	<u>Wi</u>	<u>% Sand</u>	<u>% Silt</u>	<u>% Clay</u>
79-6	8.4 - 8.7	15.5	66.0	24.0	5.0
79-6	11.7 - 12.0	19.9	65.0	31.0	4.0
79-6	14.5 - 14.7	22.9	38.0	62.0	0.0
79-19	14.7 - 15.0	22.0	60.0	35.5	4.5
79-19	17.7 - 18.0	18.3	78.5	17.0	4.5

Table A.6 SUMMARY OF LABORATORY TEST RESULTS - SASKATCHEWAN SANDS AND GRAVELS

<u>Test Hole</u>	<u>Depth (m)</u>	<u>Wi</u>	<u>% Sand</u>	<u>% Silt</u>	<u>%Clay</u>
79-28			97.5	2.5	0.0

B. APPENDIX - GROUND INSTRUMENTS - FIELD DATA

POINTS POSITION 1981

INSTR.	SP2	SP3	SP4	ME5	SI6	SI7	SP8	ME9	ME10	SP11	SI12	SP13	SP14	SP15	SP16
ST.	55.2	46.5	46.6	44.6	43.4	48.7	46.6	43.4	48.7	46.6	43.6	46.5	55.5	56.9	57.1
DATE	TIME				DIST	FROM	THE	FACE	OF	THE	MOLE				
JAN18	15:00	-41.5	-46.6	-39.6	-38.4	-43.7	-41.6	-38.4	-43.7	-41.6	-38.6	-41.5	-50.5	-51.9	-52.1
JAN30	15:00	-30.9	-22.3	-20.3	-19.1	-24.4	-22.3	-19.1	-24.4	-22.3	-19.3	-22.2	-31.2	-32.6	-32.8
FEB 2	15:45	-27.5	-18.9	-16.9	-15.7	-21.0	-18.9	-15.7	-21.0	-18.9	-15.9	-18.8	-27.8	-29.2	-29.4
FEB 3	7--15	-27.5	-18.9	-16.9	-15.7	-21.0	-18.9	-15.7	-21.0	-18.9	-15.9	-18.8	-27.8	-29.2	-29.4
FEB 4	15:00	-26.3	-17.7	-15.7	-14.5	-19.8	-17.7	-14.5	-19.8	-17.7	-14.7	-17.6	-26.6	-28.0	-28.2
FEB 5	11:10	-23.9	-15.2	-13.3	-12.1	-17.4	-15.3	-12.1	-17.4	-15.3	-12.3	-15.2	-24.2	-25.6	-25.8
FEB 5	15:00	-21.5	-12.8	-10.9	-9.7	-15.0	-12.9	-9.7	-15.0	-12.9	-9.9	-12.8	-21.8	-23.2	-23.4
FEB 6	13:00	-9.1	-9.2	-7.2	-6.0	-11.3	-9.2	-6.0	-11.3	-9.2	-6.2	-9.1	-18.1	-19.5	-19.7
FEB7/8	all	-17.8	-9.2	-7.2	-6.0	-11.3	-9.2	-6.0	-11.3	-9.2	-6.2	-9.1	-18.1	-19.5	-19.7
FEB 9	12:45	-14.8	-6.1	-4.2	-3.4	-8.3	-6.2	-3.4	-8.3	-6.2	-3.6	-6.1	-15.1	-16.5	-16.7
FEB10	7:35	-13.4	-4.7	-2.8	-1.6	-6.9	-4.8	-1.6	-6.9	-4.8	-1.8	-4.7	-13.7	-15.1	-15.3
FEB10	8:30	-13.1	-4.4	-2.5	-1.3	-6.6	-4.5	-1.3	-6.6	-4.5	-1.5	-4.4	-13.4	-14.8	-15.0
FEB10	9:20	-12.8	-4.1	-2.2	-1.0	-6.3	-4.2	-1.0	-6.3	-4.2	-1.2	-4.1	-13.1	-14.5	-14.7
FEB10	10:10	-12.5	-3.8	-1.9	-0.7	-6.0	-3.9	-0.7	-6.0	-3.9	-0.9	-3.9	-12.8	-14.2	-14.4
FEB10	11:30	-12.3	-3.6	-1.7	-0.5	-5.8	-3.7	-0.5	-5.8	-3.7	-0.7	-3.7	-12.6	-14.0	-14.2
FEB10	13:45	-10.0	-1.3	-0.4	+1.8	-3.5	-1.4	+1.8	-3.5	-1.4	+1.6	-1.3	-10.3	-11.7	-11.9
FEB10	15:00	-8.7	+0.0	+1.9	+3.1	-2.2	-0.1	+3.1	-2.2	-0.1	+2.9	+0.0	-9.0	-10.4	-10.6
FEB11	9:05	-7.7	+1.0	+2.9	+4.1	-1.2	+0.9	+4.1	-1.2	+0.9	+3.9	+1.0	-8.0	-9.4	-9.6
FEB11	11:05	-6.4	+2.3	+4.2	+5.4	+0.1	+2.2	+5.4	+0.1	+2.2	+5.2	+2.3	-6.7	-8.1	-8.3
FEB 0	13:10	-5.2	+3.5	+5.4	+6.6	+1.3	+3.4	+6.6	+1.3	+3.4	+6.4	+3.5	-5.5	-6.9	-7.1
FEB 0	15:00	-3.9	+4.8	+6.7	+7.9	+2.6	+4.7	+7.9	+2.6	+4.7	+7.7	+4.8	-4.2	-5.6	-5.8
FEB12	9:45	-1.6	+7.1	+9.0	+10.2	+4.9	+7.0	+10.2	+4.9	+7.0	+10.0	+7.1	-1.9	-3.3	-3.5
FEB12	12:20	-0.3	+8.4	+10.3	+11.5	+6.2	+8.3	+11.5	+6.2	+8.3	+11.3	+8.4	-0.6	-2.0	-2.2
FEB12	13-15	+1.0	+9.7	+11.6	+12.8	+7.5	+9.6	+12.8	+7.5	+9.6	+12.6	+9.7	+0.7	-0.7	-0.9
FEB13	7:30	+2.3	+11.0	+12.9	+14.1	+8.8	+10.9	+14.1	+8.8	+10.9	+13.9	+11.0	+2.0	+0.6	+0.4
FEB13	8-15	+3.6	+12.3	+14.2	+15.4	+10.1	+12.2	+15.4	+10.1	+12.2	+15.2	+12.3	+3.3	+1.9	+1.7
FEB16	7:50	+4.8	+13.5	+15.4	+16.6	+11.3	+13.4	+16.6	+11.3	+13.4	+16.4	+13.5	+4.5	+3.1	+2.9
FEB16	9:45	+6.0	+14.7	+16.6	+17.8	+12.5	+14.6	+17.8	+12.5	+14.6	+17.6	+14.7	+5.7	+4.3	+4.1
FEB16	12:20	+7.1	+15.8	+17.7	+18.9	+13.6	+15.7	+18.9	+13.6	+15.7	+18.7	+15.8	+6.8	+5.4	+5.2

TABLE B1 - DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE

POINTS POSITION 1981															
INST.	SP2	SP3	SP4	ME5	SI6	SI7	SP8	ME9	ME10	SP11	SI12	SP13	SP14	SP15	SP16
ST.	55.2	46.5	46.6	44.6	43.4	48.7	46.6	43.4	48.7	46.6	43.6	46.5	55.5	56.9	57.1
DATE	TIME	FROM		THE		FACE		OF		THE		MOLE			
FEB16	13:40	17.0	16.9	18.9	20.1	14.8	16.8	20.1	14.8	16.9	19.9	17.0	8.0	6.6	6.4
FEB17	07:45	18.2	18.1	20.1	21.3	16.0	18.1	21.3	16.0	18.1	21.1	18.2	9.2	7.8	7.6
FEB17	08:50	19.4	19.3	21.3	22.5	17.2	19.3	22.5	17.2	19.3	22.3	19.4	10.4	9.0	8.8
FEB17	12:50	20.7	20.6	22.6	23.8	18.5	20.6	23.8	18.5	20.6	23.6	20.7	11.7	10.3	10.1
FEB17	13:55	22.0	21.9	23.9	25.1	19.8	21.9	25.1	19.8	21.9	24.9	22.0	13.0	11.6	11.4
FEB18	08:20	23.2	23.1	25.1	26.3	21.0	23.1	26.3	21.0	23.1	26.1	23.2	14.2	12.8	12.6
FEB18	09:45	24.3	24.2	26.2	27.4	22.1	24.2	27.4	22.1	24.2	27.2	24.3	15.3	13.9	13.7
FEB18	12:00	25.5	25.4	27.4	28.6	23.3	25.4	28.6	23.3	25.4	28.4	25.5	16.5	15.1	14.9
FEB18	13:30	26.7	26.6	28.6	29.8	24.5	26.6	29.8	24.5	26.6	29.6	26.7	17.7	16.3	16.1
FEB19	13:30	26.7	26.6	28.6	29.8	24.5	26.6	29.8	24.5	26.6	29.6	26.7	17.7	16.3	16.1
FEB20	13:30	26.7	26.6	28.6	29.8	24.5	26.6	29.8	24.5	26.6	29.6	26.7	17.7	16.3	16.1
FEB21	13:30	26.7	26.6	28.6	29.8	24.5	26.6	29.8	24.5	26.6	29.6	26.7	17.7	16.3	16.1
FEB22	13:30	26.7	26.6	28.6	29.8	24.5	26.6	29.8	24.5	26.6	29.6	26.7	17.7	16.3	16.1
FEB23	07:35	28.2	28.1	30.1	31.3	26.0	28.1	31.3	26.0	28.1	25.8	28.2	19.2	17.8	17.6
FEB23	12:10	29.3	29.2	31.2	32.4	27.1	29.2	32.4	27.1	29.2	32.2	29.3	20.3	18.9	18.7
FEB24	09:15	30.5	30.4	32.4	33.6	28.3	30.4	33.6	28.3	30.4	33.4	30.5	21.5	20.1	19.9
FEB24	10:35	31.8	31.7	33.7	34.9	29.6	31.7	34.9	29.6	31.7	34.7	31.8	22.8	21.4	21.2
FEB24	13:45	33.1	33.0	35.0	36.2	30.9	33.0	36.2	30.9	33.0	36.0	33.1	24.1	22.7	22.5
FEB25	10:20	34.3	34.2	36.2	37.4	32.1	34.2	37.4	32.1	34.2	37.2	34.3	25.3	23.9	23.7
FEB25	12:10	35.6	35.5	37.5	38.5	33.4	35.5	38.5	33.4	35.5	38.5	35.6	26.6	25.2	25.0
FEB25	13:30	36.8	36.7	38.7	39.9	34.6	36.7	39.9	34.6	36.7	39.7	36.8	27.8	26.4	26.2
FEB25	14:50	38.0	37.9	39.9	41.1	35.8	37.9	41.1	35.8	37.9	40.9	38.0	29.0	27.6	27.4
FEB26	07:00	38.0	37.9	39.9	41.1	35.8	37.9	41.1	35.8	37.9	40.9	38.0	29.0	27.6	27.4
FEB26	08-30	39.2	39.1	41.1	42.3	37.0	39.1	42.3	37.0	39.1	42.1	39.2	30.2	28.2	28.6
FEB26	12:50	40.4	40.3	42.3	43.5	38.2	40.3	43.5	38.2	40.3	43.3	40.4	31.4	30.0	29.8
FEB26	13:55	41.6	41.5	43.5	44.7	39.4	41.5	44.7	39.4	41.5	44.5	41.6	32.6	31.2	31.0
FEB26	15:00	42.8	42.7	44.7	45.9	40.6	42.7	45.9	40.6	42.7	45.7	42.9	33.8	32.4	32.2
FEB27	07:00	42.8	42.7	44.7	45.9	40.6	42.7	45.9	40.6	42.7	45.7	42.9	33.8	32.4	32.2
FEB27	07:45	44.0	43.9	45.9	47.1	41.8	43.9	47.1	41.8	43.9	46.9	44.0	35.0	33.6	33.4
FEB27	09:05	45.2	45.1	47.1	48.3	43.0	45.1	48.3	43.0	45.1	48.1	45.2	36.2	34.8	34.6

TABLE B2 - DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE (cont)

POINTS POSITION 1981

INSTR.	SP2	SP3	SP4	ME5	SI6	SI7	SP8	ME9	ME10	SP11	SI12	SP13	SP14	SP15	SP16
ST.	55.2	46.5	46.6	44.6	43.4	48.7	46.6	43.4	48.7	46.6	43.6	46.5	55.5	56.9	57.1
DATE	TIME				DIST	FROM	THE	FACE	OF	THE	MOLE				
FEB27	10:40	37.7	46.4	46.3	48.3	44.2	46.3	49.5	44.2	46.3	49.3	46.4	37.4	36.0	35.8
FEB27	13:00	38.9	47.6	47.5	49.5	45.4	47.5	50.7	45.4	47.5	50.5	47.6	38.6	37.2	37.0
FEB27	14:00	40.1	48.8	48.7	50.7	46.6	48.7	51.9	46.6	48.7	50.7	48.8	39.8	38.4	38.2
FEB27	14:45	41.3	50.0	49.9	51.9	47.8	49.9	53.1	47.8	49.9	52.9	50.0	41.0	39.6	39.4
MAR02	07:00	41.3	50.0	49.9	51.9	47.8	49.9	53.1	47.8	49.9	52.9	50.0	41.0	39.6	39.4
MAR02	09:30	42.5	51.2	51.1	53.1	49.0	51.1	54.3	49.0	51.1	54.1	51.2	42.2	40.8	40.6
MAR02	11:00	43.7	52.4	52.3	54.3	50.2	52.3	55.5	50.2	52.3	55.3	52.4	43.4	42.0	41.8
MAR02	13:50	44.9	53.6	53.5	55.5	51.5	53.5	56.7	51.5	53.7	56.7	53.8	44.6	43.2	43.0
MAR02	15:00	46.1	54.8	54.7	56.7	52.6	54.7	57.9	52.6	54.7	57.7	54.8	45.8	44.4	44.2
MAR03	07:00	46.1	54.8	54.7	56.7	52.6	54.7	57.9	52.6	54.7	57.7	54.8	45.8	44.4	44.2
MAR03	08:15	47.3	56.0	55.9	57.9	53.8	55.9	59.1	53.8	55.9	58.9	56.0	47.0	45.6	45.4
MAR03	09:30	48.5	57.2	57.1	59.1	55.0	57.1	60.3	55.0	57.1	60.1	57.2	48.2	46.8	46.8
MAR03	12:55	49.7	58.4	58.3	60.3	56.2	58.3	61.5	56.2	58.3	61.3	58.4	49.4	48.0	47.8
MAR03	14:10	50.9	59.6	59.5	61.5	57.4	59.5	62.7	57.4	59.5	62.5	59.6	50.6	49.2	49.0
MAR04	07:00	50.9	59.6	59.5	61.5	57.4	59.5	62.7	57.4	59.5	62.5	59.6	50.6	49.2	49.0
MAR04	07:30	52.1	60.8	60.7	62.7	58.6	60.7	63.9	58.6	60.7	63.7	60.8	51.8	50.4	50.2
MAR04	09:15	53.5	62.0	61.9	63.9	59.8	61.9	65.1	59.8	61.9	64.9	62.0	53.0	51.6	51.4
MAR04	10:30	54.5	63.2	63.1	65.1	61.0	63.1	66.2	61.0	63.1	66.0	63.2	54.2	52.8	52.6
MAR04	12:15	55.7	64.4	64.3	66.3	62.2	64.3	67.5	62.2	64.3	67.3	64.4	55.4	54.0	53.8
MAR04	14:00	56.9	65.5	65.6	67.5	63.4	65.5	68.7	63.4	65.5	68.5	65.6	56.6	55.2	55.0
MAR05	07:00	56.9	65.5	65.6	67.5	63.4	65.5	68.7	63.4	65.5	68.5	65.6	56.6	55.2	55.0
MAR05	07:25	58.5	67.2	67.1	69.1	65.0	67.1	70.3	65.0	67.1	70.1	67.2	58.2	56.8	56.6
MAR05	09:30	59.7	68.4	68.3	70.3	66.2	68.3	71.5	66.2	68.3	71.3	68.4	59.4	58.0	57.8
MAR05	10:35	60.9	69.6	69.5	71.5	67.4	69.5	72.7	67.4	69.5	72.5	69.6	60.6	59.2	59.0
MAR05	12:30	62.1	70.8	70.7	72.7	68.6	70.7	73.9	68.6	70.7	73.7	70.8	61.8	60.4	60.2
MAR05	14:00	63.4	72.1	72.0	74.0	69.9	72.0	75.2	69.9	72.0	75.0	72.1	63.1	61.8	61.6
MAR06	07:00	63.4	72.1	72.0	74.0	69.9	72.0	75.2	69.9	72.0	75.0	72.1	63.1	61.8	61.6
MAR06	07:45	64.9	73.6	73.5	75.5	71.4	73.5	76.7	71.4	73.5	76.5	73.6	64.6	63.2	63.0
MAR06	08:50	66.1	74.8	74.7	76.7	72.6	74.7	77.9	72.6	74.7	77.7	74.8	65.8	64.4	64.2
MAR06	10:00	67.3	76.0	75.9	77.9	73.8	75.9	79.1	73.8	75.9	78.9	76.0	67.0	66.6	66.4
MAR06	11:15	68.8	77.5	77.4	79.4	75.3	77.4	80.6	75.3	77.4	80.4	77.5	68.5	67.1	66.9
MAR06	13:15	70.0	78.7	78.6	80.6	76.5	78.6	81.8	76.5	78.6	81.6	78.7	69.7	68.3	68.1
MAR06	14:40	71.2	79.9	79.8	81.8	77.7	79.8	83.0	77.7	79.8	82.9	79.9	69.9	68.5	68.3

TABLE B3 - DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE (cont)

INSTR.	POINTS POSITION 1981														
	SP2	SP3	SP4	ME5	SI6	SI7	SP8	ME9	ME10	SP11	SI12	SP13	SP14	SP15	SP16
ST.	55.2	46.5	46.6	44.6	43.4	48.7	46.6	43.4	48.7	46.6	43.6	46.5	55.5	56.9	57.1
DATE	TIME				DIST	FROM	THE	FACE	OF	THE	MOLE				
MAR09	07:00	71.2	79.9	79.8	81.8	83.0	79.8	83.0	77.7	79.8	82.8	79.9	70.9	69.5	69.3
MAR09	08:30	72.4	81.1	81.0	83.0	84.2	81.0	84.2	78.9	81.0	84.0	81.1	72.1	70.7	70.5
MAR09	09:30	73.6	82.3	82.2	84.2	85.4	82.2	85.4	80.1	82.2	85.2	82.3	73.3	71.9	71.7
MAR09	10:40	74.9	83.6	83.5	85.5	86.7	83.5	86.7	81.7	83.5	86.5	83.6	74.6	73.2	73.0
MAR09	15:00	74.9	83.6	83.5	85.5	86.7	83.5	86.7	81.7	83.5	86.5	83.6	74.6	73.2	73.0
MAR10	07:00	74.9	83.6	83.5	85.5	86.7	83.5	86.7	81.7	83.5	86.5	83.6	74.6	73.2	73.0
MAR10	08:15	76.1	84.8	84.7	86.7	87.9	84.7	87.9	82.6	84.7	87.7	84.8	75.8	74.8	74.6
MAR10	09:30	78.3	87.0	86.9	88.9	90.1	86.9	90.1	84.8	86.9	89.9	87.0	78.0	76.6	76.4
MAR10	10:30	79.5	88.2	88.1	90.1	91.3	88.1	91.3	86.0	88.1	91.1	88.2	79.2	77.8	77.6
MAR10	12:00	80.0	89.5	89.4	91.4	92.6	89.4	92.6	87.3	89.4	92.4	89.5	80.5	79.1	78.9
MAR10	13:15	82.1	90.8	90.7	92.7	93.9	90.7	93.9	88.6	90.7	93.7	90.8	81.8	80.4	80.2
MAR10	14:20	83.4	92.1	92.0	94.0	95.2	92.0	95.2	89.9	92.0	95.0	92.1	83.3	81.9	81.7
MAR11	07:00	83.4	92.1	92.0	94.0	95.2	92.0	95.2	89.9	92.0	95.0	92.1	83.3	81.9	81.7
MAR11	09:30	84.6	93.3	93.2	95.2	96.4	93.2	96.4	91.1	93.2	96.2	93.3	84.3	82.9	82.7
MAR11	10:35	86.0	94.7	94.6	96.6	97.8	94.6	97.8	92.5	94.6	97.6	94.7	85.7	84.3	84.1
MAR11	12:29	87.3	96.0	95.9	97.9	99.1	95.9	99.1	93.8	95.9	98.9	96.0	87.0	85.6	85.4
MAR11	13:35	88.5	97.2	97.1	99.1	100.3	97.1	100.3	95.0	97.1	100.1	97.2	88.2	86.8	86.6
MAR11	14:30	89.7	98.4	98.3	100.3	101.5	98.3	101.5	96.2	98.3	101.3	98.4	89.4	88.0	87.8
MAR12	07:00	89.7	98.4	98.3	100.3	101.5	98.3	101.5	96.2	98.3	101.3	98.4	89.4	88.0	87.8
MAR12	09:10	91.2	99.9	99.8	101.8	103.0	99.8	103.0	97.7	99.8	102.8	99.9	89.9	87.5	87.2
MAR12	12:30	92.7	100.4	100.3	102.3	104.5	100.3	104.5	98.2	100.3	104.3	100.4	92.4	91.0	90.8
MAR12	14:00	94.2	101.9	101.8	103.8	106.0	100.8	106.0	99.7	100.8	105.8	100.9	93.9	92.5	92.3
MAR12	15:00	95.5	102.2	102.1	104.1	107.3	102.1	107.3	101.0	102.1	107.1	102.2	95.2	93.8	93.6
MAR13	07:00	95.5	102.2	102.1	104.1	107.3	102.1	107.3	101.0	102.1	107.1	102.2	95.2	93.8	93.6
MAR13	09:10	96.7	103.4	103.3	105.3	108.5	103.3	108.5	102.3	103.3	108.3	103.4	96.4	95.0	95.8
MAR13	10:45	97.9	104.6	104.5	106.5	109.7	104.5	109.7	103.5	104.5	109.5	104.6	97.6	96.2	96.0
MAR13	13:50	99.1	105.8	105.7	107.7	110.9	105.7	110.9	104.7	105.7	110.7	105.8	98.8	97.4	97.2
MAR13	14:45	100.3	107.0	106.9	108.9	112.1	106.9	112.1	105.9	106.9	111.9	107.0	100.0	98.6	98.4
MAR16	07:00	100.3	107.0	106.9	108.9	112.1	106.9	112.1	105.9	106.9	111.9	107.0	100.0	98.6	98.4
MAR16	07:30	100.8	107.5	107.4	109.4	112.6	107.3	112.6	106.4	107.3	112.4	107.4	100.5	99.1	98.9
MAR16	09:00	102.0	108.7	108.6	110.6	113.8	108.5	113.8	107.6	108.5	113.6	108.6	101.7	100.3	100.1
MAR16	10:45	103.2	109.9	109.8	111.8	115.0	109.7	115.0	108.8	109.7	114.8	108.9	102.9	101.5	101.3

TABLE B4 - DISTANCE FROM GROUND INSTRUMENTS TO THE NOSE OF MOLE (cont)

HA222T PE12T M2.							1
		TIME DAY	INIT. READ.	22A01002	DISPL CME	LOCATION	
26CUMBER 23	1220	22.0	2.3227	2.3227	0.0	-22.20	0.0
FEBRUARY 1	1201	77.0	2.3027	2.3022	0.0005	-20.20	0.0100
FEBRUARY 2	1221	72.0	2.3227	2.3222	2.0200	-12.02	0.0220
FEBRUARY 6	1021	21.0	2.3227	2.3226	0.0200	-10.20	0.0020
FEBRUARY 8	1221	22.0	2.3227	2.3222	0.1100	-7.20	0.0000
FEBRUARY 2	1221	24.0	2.3027	2.3212	0.0400	-7.20	-0.1000
FEBRUARY 2	1201	22.0	2.3227	2.3020	0.1200	-4.20	-0.1000
FEBRUARY 10	1221	22.0	2.3227	2.3022	0.0400	-1.70	-0.2020
FEBRUARY 10	1021	22.0	2.3027			1.20	-0.2000
FEBRUARY 11	1221	27.0	2.3227	2.3020	0.1220	2.00	-0.2000
FEBRUARY 11	1221	27.0	2.3227	2.3022	-0.0200	0.70	-0.2000
FEBRUARY 12	1201	22.0	2.3227	2.2402	-0.0221	2.20	-0.4100
FEBRUARY 12	1021	20.0	2.3227	2.3022	-0.0000	10.20	-0.2100
FEBRUARY 10	1021	22.0	2.3027	2.3210	0.0200	17.70	-0.1200
FEBRUARY 17	1021	22.0	2.3027	2.3212	-0.0220	22.20	-0.1200
FEBRUARY 12	1201	24.0	2.3227	2.3210	0.0200	20.20	-0.1200
FEBRUARY 12	1221	22.0	2.3027	2.3220	-0.0200	20.20	-0.1220
FEBRUARY 22	1221	20.0	2.3227	2.3022	-0.0000	21.20	-0.1100
FEBRUARY 22	1021	102.0	2.3227	2.3022	-0.1200	02.20	-0.1000
MARCH 7	1221	111.0	2.3227	2.3220	-0.1101	21.00	-0.1020




Figure B.1 ME5 MP#1 D=2.35m

MADIST POINT NO.		3					
		TIME DAYS	IRIT. ROAD.	RESURF	DISPL. CMS	LOCATION	
DECEMBER 22	1980	24.0	4.8788	4.8788	0.0	-38.30	0.0
FEBRUARY 1	1981	77.0	4.8788	4.8788	-0.0280	-29.30	0.0100
FEBRUARY 3	1981	79.0	4.8788	4.8788	0.0280	-18.30	0.0280
FEBRUARY 5	1981	81.0	4.8788	4.8788	0.0780	-14.30	0.0780
FEBRUARY 8	1981	82.0	4.8788	4.8788	0.0480	-7.30	0.0480
FEBRUARY 8	1981	84.0	4.8788	4.8778	-0.0040	-7.30	-0.1080
FEBRUARY 8	1981	84.0	4.8788	4.8784	0.1280	-4.30	-0.1880
FEBRUARY 14	1981	88.0	4.8788	4.8784	0.0180	-1.70	-0.2480
FEBRUARY 16	1981	88.4	4.8788	4.8788	0.0100	1.40	-0.2880
FEBRUARY 11	1981	87.0	4.8788	4.8744	0.0400	8.40	-0.2400
FEBRUARY 11	1981	87.0	4.8788	4.8788	-0.0480	8.70	-0.2480
FEBRUARY 13	1981	84.0	4.8788	4.8788	-0.0100	8.80	-0.4100
FEBRUARY 12	1981	88.0	4.8788	4.4728	-0.0480	14.30	-0.5140
FEBRUARY 18	1981	82.0	4.8788	4.8773	-0.0240	17.70	-0.1840
FEBRUARY 17	1981	82.0	4.8788	4.4778	-0.0800	23.40	-0.1400
FEBRUARY 18	1981	84.0	4.8788	4.8773	-0.0080	28.30	-0.1280
FEBRUARY 18	1981	88.0	4.8788	4.8773	-0.0180	28.40	-0.1280
FEBRUARY 22	1981	88.0	4.8788	4.8788	-0.1100	21.30	-0.1100
FEBRUARY 28	1981	102.0	4.8788	4.8788	-0.1200	42.30	-0.1400
MARCH 7	1981	111.0	4.8788	4.8788	-0.1280	51.80	-0.1080




Figure B.2 ME5 MP#2 D=4.88m

MARSET POINT SE.		3					
		TIME DAYS	LAT. DEGR.	SEADISSE	DISPL CMS	LOCATION	
DECEMBER 23	1980	26.0	8.8803	8.8802	0.0	-35.80	0.0
FEBRUARY 1	1981	77.0	8.8803	8.8806	-0.0448	-29.30	0.0100
FEBRUARY 3	1981	78.0	8.8803	8.8813	-0.0500	-18.80	0.0350
FEBRUARY 5	1981	81.0	8.8803	8.8803	0.0500	-10.80	0.0550
FEBRUARY 6	1981	83.0	8.8803	8.8858	0.1100	-7.30	0.0550
FEBRUARY 8	1981	84.0	8.8803	8.8853	-0.0058	-7.30	-0.1050
FEBRUARY 8	1981	85.0	8.8803	8.8873	0.1301	-4.20	-0.1550
FEBRUARY 10	1981	86.0	8.8803	8.8876	-0.0100	-1.70	-0.3550
FEBRUARY 10	1981	86.0	8.8803	8.8885	0.0250	1.80	-0.3550
FEBRUARY 11	1981	87.0	8.8803	8.8888	0.0050	5.40	-0.3400
FEBRUARY 11	1981	87.0	8.8803	8.8885	0.0301	8.70	-0.3450
FEBRUARY 13	1981	88.0	8.8803	8.8883	-0.0150	8.80	-0.4100
FEBRUARY 13	1981	88.0	8.8803	8.8883	-0.0158	14.30	-0.5150
FEBRUARY 15	1981	89.0	8.8803	8.8883	0.0400	17.70	-0.1550
FEBRUARY 17	1981	92.0	8.8803	8.8883	0.0150	22.80	-0.1550
FEBRUARY 18	1981	94.0	8.8803	8.8890	0.0000	26.30	-0.1350
FEBRUARY 18	1981	95.0	8.8803	8.8898	0.0101	28.80	-0.1350
FEBRUARY 22	1981	98.0	8.8803	8.8893	-0.1150	31.30	-0.1100
FEBRUARY 25	1981	103.0	8.8803	8.8888	-0.1350	43.30	-0.1500
MARCH 7	1981	111.0	8.8803	8.8893	-0.1100	51.80	-0.1050




Figure B.3 ME5 MP#3 D=6.85m

MA3R2T P01R7 00.		S					
		TIME DAYS	IRIT. R200.	R2A01R00	DISPL CMS	LOCATION	
02C2MB2R 22	1020	20.0	0.1220	0.1220	0.0	-20.00	0.0
F200UARY 1	1001	77.0	0.1220	0.1220	-0.0000	-20.20	0.0100
F220U00Y 3	1001	70.0	0.1220	0.1220	-0.0000	-10.00	0.0200
F20RUARY 0	1001	01.0	0.1220	0.1220	0.0000	-10.00	0.0000
F20RUARY 0	1001	02.0	0.1220	0.1220	0.0400	-7.20	0.0000
F20RUARY 2	1001	00.0	0.1222	0.1210	0.0200	-7.20	-0.1000
F20RUARY 0	1001	00.0	0.1220	0.1202	0.0000	-0.20	-0.1000
F20RUARY 10	1001	00.0	0.1220	0.1210	-0.1000	-1.70	-0.2000
F200UARY 10	1001	00.0	0.1220	0.1100	0.0000	1.00	-0.2000
F20RUARY 11	1001	07.0	0.1220	0.1100	0.0000	0.00	-0.2400
F20RUARY 11	1001	07.0	0.1220	0.1200	-0.0700	0.70	-0.2000
F20RUARY 12	1001	00.0	0.1220	0.1100	0.0101	0.00	-0.0100
F20RUARY 12	1001	00.0	0.1220	0.1170	-0.0100	10.20	-0.0100
F20RUARY 10	1001	02.0	0.1220	0.1202	0.0000	17.70	-0.1000
F200UARY 17	1001	02.0	0.1220	0.1200	0.0001	22.00	-0.1000
F20RUARY 10	1001	04.0	0.1220	0.1210	0.0000	20.20	-0.1200
F20RUARY 10	1001	02.0	0.1220	0.1210	-0.0100	20.00	-0.1200
F20RUARY 22	1001	00.0	0.1220	0.1220	-0.0000	21.20	-0.1100
F20RUARY 20	1001	102.0	0.1220	0.1220	-0.1000	42.20	-0.1000
MARCH 7	1001	111.0	0.1220	0.1220	-0.1100	01.00	-0.1000




Figure B.4 ME5 MP#4 D=8.13m

MAGNET FB107 05.		5					
		TIME DRY5	LOIT. NORD	SSAD1085	DIPL CHS	LCRTIR	
DECEMBER 05	1980	25.0	10.5555	10.5555	0.0	-55.50	0.0
FEBRUARY 1	1981	77.0	10.5555	10.5555	-0.0200	-50.50	0.0100
FEBRUARY 2	1981	76.0	10.5555	10.5555	-0.0552	-15.50	0.0550
FEBRUARY 3	1981	91.0	10.5555	10.5555	0.0048	-10.50	0.0550
FEBRUARY 5	1981	85.0	10.5555	10.5555	0.0048	-7.50	0.0550
FEBRUARY 5	1981	84.2	10.5555	10.5570	0.0445	-7.50	-0.1050
FEBRUARY 8	1981	88.0	10.5555	10.5550	0.0550	-4.50	-0.1550
FEBRUARY 10	1981	90.0	10.5555	10.5555	0.0148	-1.70	-0.5550
FEBRUARY 10	1981	88.2	10.5555	10.5555	0.0028	1.50	-0.5550
FEBRUARY 11	1981	87.2	10.5555	10.5545	0.0000	5.40	-0.3400
FEBRUARY 11	1981	87.0	10.5555	10.5555	-0.0451	5.70	-0.5450
FEBRUARY 15	1981	85.0	10.5555	10.5545	0.0100	8.50	-0.4100
FEBRUARY 12	1981	85.0	10.5555	10.5555	-0.0450	14.50	-0.5150
FEBRUARY 15	1981	85.0	10.5555	10.5555	0.0450	17.70	-0.1550
FEBRUARY 17	1981	85.0	10.5555	10.5555	0.0552	22.50	-0.1550
FEBRUARY 18	1981	84.0	10.5555	10.5555	0.0448	25.50	-0.1250
FEBRUARY 18	1981	85.0	10.5555	10.5555	0.0245	35.50	-0.1250
FEBRUARY 25	1981	88.0	10.5555	10.5552	-0.0001	51.20	-0.1100
FEBRUARY 28	1981	102.0	10.5555	10.5575	-0.0501	45.50	-0.1800
MARCH 7	1981	111.0	10.5555	10.5575	-0.0001	51.50	-0.1050




Figure B.5 ME5 MP#5 D=10.86m

HARBOY POINT RD. 6							
		TIME DAYS	INIT. ROAD.	ROADINGS	SIGPL CHS	LOCATION	
DECEMBER 22 1990		20.0	12.9099	12.9099	0.0	-29.90	0.0
FEBRUARY 1 1991		77.0	12.9099	12.9102	-0.1701	-20.20	0.0100
FEBRUARY 2 1991		78.0	12.9099	12.9100	-0.1200	-19.80	0.0200
FEBRUARY 9 1991		91.0	12.9099	12.9095	-0.0400	-10.90	0.0099
FEBRUARY 9 1991		92.0	12.9099	12.9099	0.0140	-7.20	0.0099
FEBRUARY 9 1991		94.0	12.9099	12.9075	0.0190	-7.20	-0.1099
FEBRUARY 9 1991		99.0	12.9099	12.9088	0.0200	-6.20	-0.1099
FEBRUARY 10 1991		99.0	12.9099	12.9080	-0.0200	-1.70	-0.2099
FEBRUARY 10 1991		99.0	12.9099	12.9088	0.0099	1.80	-0.2099
FEBRUARY 11 1991		97.0	12.9099	12.9048	0.0099	9.40	-0.2499
FEBRUARY 11 1991		97.0	12.9099	12.9092	-0.0200	9.70	-0.2499
FEBRUARY 12 1991		98.0	12.9099	12.9049	-0.0100	9.40	-0.4100
FEBRUARY 12 1991		99.0	12.9099	12.9029	0.0099	14.20	-0.8199
FEBRUARY 19 1991		92.0	12.9099	12.9092	0.0099	17.70	-0.1099
FEBRUARY 17 1991		92.0	12.9099	12.9092	0.0400	22.80	-0.1099
FEBRUARY 19 1991		94.0	12.9099	12.9070	0.0200	29.20	-0.1299
FEBRUARY 19 1991		98.0	12.9099	12.9089	0.0248	29.90	-0.1299
FEBRUARY 22 1991		98.0	12.9099	12.9088	-0.1100	21.20	-0.1100
FEBRUARY 29 1991		102.0	12.9099	12.9078	-0.0001	42.20	-0.1099
MARCH 7 1991		111.0	12.9099	12.9072	0.0100	51.80	-0.1099




Figure B.6 ME5 MP#6 D=12.91m

MAGNET PILOT 00. 7							
		TIME DAYS	1017. ROAD.	ROAD1000	DISPL CMB	LOCATION	
DECEMBER 22	1990	20.0	14.0020	14.0020	0.0	-28.50	0.0
FEBRUARY 1	1991	77.0	14.0520	14.0000	-12.7000	-20.20	0.0100
FEBRUARY 2	1991	78.0	14.0525	14.0020	-12.9700	-19.50	0.0200
FEBRUARY 5	1991	81.8	14.0025	14.0025	-14.0450	-19.50	0.0050
FEBRUARY 5	1991	82.0	14.0020	14.0040	-14.1250	-7.20	0.0050
FEBRUARY 5	1991	84.0	14.0020	14.0050	-14.2050	-7.20	-0.1050
FEBRUARY 8	1991	85.0	14.0020	14.0050	-14.4000	-4.20	-0.1500
FEBRUARY 10	1991	89.0	14.0520	14.0050	-14.0050	-1.70	-0.2000
FEBRUARY 10	1991	95.0	14.0025	14.0050	-14.5400	1.00	-0.2500
FEBRUARY 11	1991	97.0	14.0020	14.0050	-14.5400	0.40	-0.2400
FEBRUARY 11	1991	97.0	14.0020	14.0050	-14.5400	0.70	-0.2450
FEBRUARY 12	1991	98.0	14.0020	14.0040	-14.5100	0.50	-0.4100
FEBRUARY 12	1991	98.0	14.0020	14.0042	-14.5550	14.20	-0.5150
FEBRUARY 15	1991	92.0	14.0020	14.0072	-14.5200	17.70	-0.1000
FEBRUARY 17	1991	92.0	14.0020	14.0070	54.2700	22.50	-0.1500
FEBRUARY 19	1991	95.0	14.0520	14.0072	-14.0000	20.20	-0.1200
FEBRUARY 15	1991	50.0	14.0020	14.0000	-14.0000	20.00	-0.1200
FEBRUARY 22	1991	50.0	14.0020	10.0005	-14.0100	21.20	-0.1100
FEBRUARY 29	1991	102.0	15.0025	14.0005	-14.0100	42.20	-0.1500
MARCH 7	1991	111.0	14.0020	10.0000	-14.0000	01.50	-0.1000

DISREGARD

Figure B.7 ME5 MP#7 D=14.81m

MARKET POINT RR.		B					
		TIME DAYS	IRTY. ROAD.	BEASTRES	DISPL CMS	LOCATION	
DECEMBER 23	1980	30.R	10.7743	10.7743	R.0	-30.50	R.0
FEBRUARY 1	1981	77.0	10.7743	10.7700	-R.3307	-30.30	R.R100
FEBRUARY 3	1981	78.R	10.7743	10.7703	-0.1745	-10.50	R.0300
FEBRUARY 8	1981	81.R	10.7743	10.7705	-0.0845	-10.50	0.0550
FEBRUARY 9	1981	83.R	10.7743	10.7700	-R.0027	-7.30	R.0050
FEBRUARY 8	1981	84.R	10.7743	10.7733	-R.0043	-7.20	-R.1050
FEBRUARY 8	1981	85.R	10.7743	10.7733	R.0304	-4.30	-R.1050
FEBRUARY 10	1981	88.R	10.7743	10.7710	-0.0043	-1.70	-R.3050
FEBRUARY 10	1981	88.R	10.7743	10.7713	R.0100	1.50	-0.3000
FEBRUARY 11	1981	87.0	10.7743	10.7680	R.1101	0.40	-0.3000
FEBRUARY 11	1981	87.R	10.7743	10.7710	-R.0545	0.70	-0.3050
FEBRUARY 13	1981	88.R	10.7743	10.7680	R.0401	0.50	-0.4100
FEBRUARY 13	1981	88.R	10.7743	10.7680	R.0100	14.20	-0.0150
FEBRUARY 16	1981	83.0	10.7743	10.7730	0.0704	17.70	-0.1050
FEBRUARY 17	1981	83.R	10.7743	10.7710	R.1000	33.00	-R.1000
FEBRUARY 16	1981	84.R	10.7743	10.7730	-R.0441	30.30	-R.1250
FEBRUARY 18	1981	85.R	10.7743	10.7730	R.0004	30.50	-0.1250
FEBRUARY 23	1981	88.R	10.7743	10.7730	-0.0301	31.30	-R.1100
FEBRUARY 30	1981	103.R	10.7743	10.7730	-R.0305	42.30	-R.1000
MARCH 7	1981	111.R	10.7743	10.7733	-R.0043	51.50	-R.1050




Figure B.8 ME5 MP#8 D=16.78m

MADGET POINT SE.							
5							
		TIME DAYS	INIT. ROAD	RECEIVED	DISPL. CMS	LOCATION	
DECEMBER 33	1980	35.0	18.0773	18.0773	0.0	-35.50	0.0
FEBRUARY 1	1981	77.0	18.0773	18.0765	-0.1255	-35.30	0.0100
FEBRUARY 3	1981	78.0	18.0773	18.0760	-0.1844	-15.50	0.0350
FEBRUARY 5	1981	81.0	18.0773	18.0775	0.0040	-10.50	0.0550
FEBRUARY 6	1981	83.0	18.0773	18.0752	0.1154	-7.30	0.0550
FEBRUARY 8	1981	84.0	18.0773	18.0753	-0.0043	-7.30	-0.1050
FEBRUARY 9	1981	85.0	18.0773	18.0755	0.0553	-4.30	-0.1550
FEBRUARY 10	1981	85.0	18.0773	18.0743	0.0155	-1.70	-0.3550
FEBRUARY 10	1981	85.0	18.0773	18.0735	0.0555	1.00	-0.3500
FEBRUARY 11	1981	87.0	18.0773	18.0735	0.0355	5.40	-0.3400
FEBRUARY 11	1981	87.0	18.0773	18.0733	0.0545	5.70	-0.3450
FEBRUARY 13	1981	88.0	18.0773	18.0733	0.0505	5.50	-0.4100
FEBRUARY 13	1981	88.0	18.0773	18.0705	0.1350	14.30	-0.5150
FEBRUARY 15	1981	83.0	18.0773	18.0745	0.1355	17.70	-0.1550
FEBRUARY 17	1981	83.0	18.0773	18.0733	0.3155	33.50	-0.1500
FEBRUARY 18	1981	85.0	18.0773	18.0740	0.3045	35.30	-0.1350
FEBRUARY 19	1981	85.0	18.0773	18.0753	0.1855	35.50	-0.1350
FEBRUARY 23	1981	85.0	18.0773	18.0753	-0.0023	31.30	-0.1100
FEBRUARY 25	1981	103.0	18.0773	18.0745	0.0703	43.30	-0.1500
MARCH 7	1981	111.0	18.0773	18.0753	-0.0043	51.50	-0.1050




Figure B.9 ME5 MP#9 D=18.08m

ME9087 P810T 03.1

	TIME DAYS	LOIT. REPT.	33031033	SISPL CMS	LSCOTIRE	
33C8M68R 33 1330	33.0	1.4343	1.3344	0.0	-40.00	0.0
F33RUARY 3 1931	73.0	1.4344	1.4353	0.0330	-14.00	0.1030
F33RU03Y 3 1331	31.0	1.4343	1.4333	0.1100	-3.70	0.1300
F03RU43Y 3 1331	33.0	1.4345	1.4353	0.0400	-3.00	0.1300
F33RU03Y 3 1341	04.0	1.4343	1.4334	-0.0230	-3.00	0.0440
F33RU0RY 4 1331	03.0	1.4344	1.4343	0.0300	-3.40	0.0300
F303U0RY 10 1991	33.0	1.4344	1.3333	-0.1340	-0.30	-0.0440
F33RU0RY 10 1331	34.0	1.4343	1.4340	-0.1130	3.10	-0.1330
F033U0RY 11 1331	07.0	1.4344	1.4343	-0.1430	4.40	-0.3340
F33RU0RY 11 1331	37.0	1.4344	1.4340	-0.3000	7.40	-0.3300
F303U03Y 13 1331	34.0	1.4344	1.4334	-0.3100	11.00	-0.4400
F33RU03Y 13 1331	43.0	1.4333	1.4343	-0.4100	13.40	-0.4400
F33RU0RY 13 1431	33.0	1.4343	1.3343	-0.3330	13.40	-0.3340
F00RU0RY 14 1331	03.0	1.4344	1.4333	-0.4434	14.30	-4.0400
F00RU0RY 17 1331	33.0	1.4344	1.4343	-0.3100	33.10	-0.0100
F00RU0RY 13 1331	34.0	1.4344	1.4403	-0.4700	37.40	0.0400
F33RU0RY 13 1331	34.0	1.4344	1.4403	-0.4340	33.30	0.0330
F00RU0RY 33 1991	44.0	1.4344	1.4403	-0.4400	33.40	0.0440
F33RU0RY 33 1391	103.0	1.4344	1.4413	-0.4030	43.34	0.0440
MARCO 13 1931	133.0	1.4343	1.4413	-0.6300	113.00	0.0700




Figure B.10 ME9 MP#1 D=1.43m

HAGGETT POINT 00.		0					
		TIME DAYS	1917. 00AD.	READINGS	DISPL CM	LOCATION	
DECEMBER 30	1990	30.0	3.0310	3.0310	0.0	-40.00	0.0
FEBRUARY 3	1991	70.0	3.0310	0.0300	0.0001	-10.00	0.1000
FEBRUARY 9	1991	91.0	3.0310	0.0010	0.1001	-0.70	0.1000
FEBRUARY 8	1991	90.0	3.0010	0.0300	0.0001	-0.00	0.1000
FEBRUARY 9	1991	90.0	0.0010	3.0010	0.0400	-0.00	0.0400
FEBRUARY 9	1991	90.0	3.0310	0.0310	0.0001	-0.40	0.0300
FEBRUARY 10	1991	90.0	3.0310	0.0000	-0.1000	-0.00	-0.0000
FEBRUARY 10	1991	90.0	3.0310	3.0000	-0.0700	3.10	-0.1000
FEBRUARY 11	1991	97.0	3.0310	3.0000	-0.0000	0.00	-0.3000
FEBRUARY 11	1991	97.0	3.0310	3.0000	-0.1000	7.00	-0.0000
FEBRUARY 10	1991	90.0	0.0310	0.0000	-0.3400	11.00	-0.4400
FEBRUARY 13	1991	90.0	3.0010	3.0000	-0.3000	10.40	-0.4000
FEBRUARY 13	1991	90.0	3.0310	0.0000	-0.4000	10.40	-0.0300
FEBRUARY 10	1991	90.0	3.0310	0.0000	-0.4000	10.00	-0.0400
FEBRUARY 17	1991	90.0	3.0310	0.0000	-0.4000	00.10	-0.0100
FEBRUARY 10	1991	90.0	0.0310	0.0370	-0.0000	07.40	0.0000
FEBRUARY 10	1991	90.0	3.0010	3.0300	-0.0100	30.00	0.0000
FEBRUARY 33	1991	90.0	3.0010	3.0070	-0.0100	03.40	0.0000
FEBRUARY 30	1991	103.0	3.0010	0.0070	-0.0000	40.00	0.0400
MARCH 10	1991	100.0	0.0010	0.0000	-0.0000	110.00	0.0700




Figure B.11 ME9 MP#2 D=2.93m

MASSBY POINT 00.		3					
		TIME DAYS	1817. 03A0.	08431800	013PL CMB	LOCST188	
08CMB00 32	1880	20.0	4.8840	4.8840	0.0	-40.00	0.0
F308U08Y 3	1381	70.0	4.8840	4.8838	0.0088	-10.00	0.1000
F330U08Y 3	1881	31.0	4.8840	4.8840	0.1100	-0.70	0.1000
F308U08Y 8	1881	82.0	4.8840	4.8848	0.0000	-8.00	0.1000
F330U08Y 8	1381	34.0	4.8840	4.8840	0.0400	-8.00	0.0800
F088U08Y 8	1381	88.0	4.8840	4.8820	0.1388	-3.40	0.0200
F088U08Y 10	1881	80.0	4.8840	4.8823	-0.0100	-0.00	-0.0800
F308U08Y 10	1881	80.0	4.8840	4.8830	-0.0801	3.10	-0.1800
F308U08Y 11	1881	87.0	4.8840	4.8828	-0.1100	8.40	-0.2380
F308U08Y 11	1881	87.0	4.8840	4.8828	-0.3200	7.80	-0.2800
F308U08Y 13	1881	88.0	4.8840	4.8838	-0.2200	11.00	-0.4400
F330U08Y 13	1381	80.0	4.8840	4.8830	-0.3801	10.40	-0.4800
F308U08Y 13	1881	88.0	4.8840	4.8830	-0.4780	18.40	-0.8280
F088U08Y 18	1881	92.0	4.8840	4.8874	-0.4200	18.20	-0.8400
F308U08Y 17	1881	82.0	4.8840	4.8888	-0.4800	20.10	-0.9100
F088U08Y 18	1881	84.0	4.8840	4.8882	-0.3800	27.40	0.0800
F308U08Y 18	1881	88.0	4.8840	4.8888	-0.3800	30.80	8.0880
F330U08Y 32	1881	88.0	4.8840	4.8888	-0.4800	22.40	0.0800
F330U08Y 38	1881	102.0	4.8840	4.8800	-0.3381	42.30	0.0880
MARCH 18	1881	122.0	4.8840	4.8810	-0.4200	118.00	0.0700




Figure B.12 ME9 MP#3 D=4.89m

MAGNET POINT NO.		4					
		TIME SECS	INIT. RECD.	ADJUSTED	DISPL. CM	LOCATION	
DECEMBER 23	1980	35.0	7.0043	7.0043	0.0	-40.00	0.0
FEBRUARY 3	1981	78.0	7.0043	7.0038	-0.0150	-18.00	0.1088
FEBRUARY 8	1981	81.0	7.0043	7.0039	0.0000	-8.70	0.1800
FEBRUARY 8	1981	83.0	7.0043	7.0033	0.0001	-8.08	0.1800
FEBRUARY 8	1981	84.0	7.0043	7.0048	-0.0050	-8.00	0.0450
FEBRUARY 8	1981	88.0	7.0043	7.0038	0.1100	-3.40	0.0300
FEBRUARY 10	1981	88.0	7.0043	7.0043	-0.0550	-0.80	-0.0550
FEBRUARY 10	1981	88.0	7.0043	7.0038	-0.1100	3.10	-0.1850
FEBRUARY 11	1981	87.0	7.0043	7.0033	-0.1350	8.80	-0.3300
FEBRUARY 11	1981	87.0	7.0043	7.0038	-0.1300	7.80	-0.3800
FEBRUARY 13	1981	88.0	7.0043	7.0033	-0.3400	11.00	-0.4400
FEBRUARY 13	1981	88.0	7.0043	7.0030	-0.3300	18.40	-0.4800
FEBRUARY 13	1981	88.0	7.0043	7.0033	-0.4350	18.40	-0.8300
FEBRUARY 15	1981	83.0	7.0043	7.0078	-0.3800	18.30	-0.0400
FEBRUARY 17	1981	83.0	7.0043	7.0058	-0.8800	38.10	-0.0100
FEBRUARY 18	1981	84.0	7.0043	7.0053	-0.3300	37.40	0.0000
FEBRUARY 18	1981	88.0	7.0043	7.0088	-0.3548	38.80	0.0880
FEBRUARY 23	1981	88.0	7.0043	7.0088	-0.4358	33.40	0.0800
FEBRUARY 28	1981	102.0	7.0043	7.0100	-0.8380	43.80	0.0480
MARCH 18	1981	123.0	7.0043	7.0108	-0.8808	118.00	0.0700




Figure B.13 ME9 MP#4 D=7.01m

BENCHMARK POINT NO.		B					
		TIME DAYS	INIT. 0000	00001000	010PL CMS	LOCATION	
DECEMBER 22	1980	30.0	0.0300	0.0300	0.0	-40.00	0.0
FEBRUARY 3	1981	70.0	0.0300	0.0313	-0.0400	-10.00	0.1000
FEBRUARY 9	1981	81.0	0.0300	0.0310	0.0400	-0.70	0.1000
FEBRUARY 9	1981	82.0	0.0300	0.0310	0.0000	-0.00	0.1000
FEBRUARY 9	1981	84.0	0.0300	0.0300	0.0300	-0.00	0.0400
FEBRUARY 9	1981	86.0	0.0300	0.0300	0.0000	-0.40	0.0300
FEBRUARY 10	1981	89.0	0.0300	0.0300	-0.0000	-0.00	-0.0000
FEBRUARY 10	1981	90.0	0.0300	0.0300	-0.1000	3.10	-0.1000
FEBRUARY 11	1981	97.0	0.0300	0.0300	-0.3000	0.00	-0.3000
FEBRUARY 11	1981	97.0	0.0300	0.0300	-0.1000	7.00	-0.3400
FEBRUARY 12	1981	99.0	0.0300	0.0300	-0.3400	11.00	-0.4400
FEBRUARY 12	1981	99.0	0.0300	0.0370	-0.3300	10.40	-0.4000
FEBRUARY 13	1981	99.0	0.0300	0.0000	-0.0000	10.40	-0.0300
FEBRUARY 16	1981	93.0	0.0304	0.0330	-0.3100	10.30	-0.0400
FEBRUARY 17	1981	98.0	0.0300	0.0000	-0.3000	20.10	-0.0100
FEBRUARY 19	1981	94.0	0.0300	0.0333	-0.0700	27.40	0.0400
FEBRUARY 19	1981	99.0	0.0300	0.0333	-0.0000	20.00	0.0000
FEBRUARY 20	1981	99.0	0.0300	0.0300	-0.4300	23.40	0.0000
FEBRUARY 20	1981	103.0	0.0300	0.0340	-0.4300	40.00	0.0000
MARCH 10	1981	133.0	0.0000	0.0303	-0.0000	110.00	0.0700




Figure B.14 ME9 MP#5 D=8.93m

MAGNET POINT NO.		S				
	TIME DAYS	INIT. ROAD.	OBASIRSS	SLIPFL CMB	LOCATION	
DECEMBER 22 1990	20.0	11.1600	11.1600	0.0	-40.00	0.0
FEBRUARY 3 1991	70.0	11.1600	11.1610	0.0000	-18.00	0.1000
FEBRUARY 8 1991	81.0	11.1600	11.1605	0.0000	-8.70	0.1000
FEBRUARY 8 1991	83.0	11.1600	11.1610	0.0000	-8.00	0.1000
FEBRUARY 8 1991	84.0	11.1600	11.1608	-0.0000	-8.00	0.0400
FEBRUARY 8 1991	85.0	11.1600	11.1608	0.1000	-2.40	0.0200
FEBRUARY 10 1991	88.0	11.1600	11.1600	-0.0000	-0.00	-0.0500
FEBRUARY 10 1991	88.0	11.1600	11.1608	-0.0400	2.10	-0.1000
FEBRUARY 11 1991	87.0	11.1600	11.1670	-0.0100	8.00	-0.2300
FEBRUARY 11 1991	87.0	11.1600	11.1688	0.0700	7.00	-0.2000
FEBRUARY 12 1991	88.0	11.1600	11.1670	-0.1400	11.00	-0.4400
FEBRUARY 12 1991	88.0	11.1600	11.1688	-0.0400	16.40	-0.4000
FEBRUARY 12 1991	88.0	11.1600	11.1688	-0.1700	18.40	-0.8200
FEBRUARY 16 1991	93.0	11.1600	11.1618	-0.1000	18.30	-0.0400
FEBRUARY 17 1991	92.0	11.1600	11.1616	-0.1000	26.10	-0.0100
FEBRUARY 18 1991	94.0	11.1600	11.1616	-0.0200	27.60	0.0000
FEBRUARY 18 1991	99.0	11.1600	11.1618	-0.0000	28.60	0.0000
FEBRUARY 22 1991	99.0	11.1600	11.1622	-0.3400	22.40	0.0000
FEBRUARY 28 1991	102.0	11.1600	11.1622	-0.1000	42.00	0.0400
MARCH 18 1991	122.0	11.1600	11.1648	-0.2000	116.00	0.0700




Figure B.15 ME9 MP#6 D=11.16m

MAGNET FOIST 00.		7					
		TIME DAYS	INIT. MAG.	SEASON	DISPL. CM	LOCATION	
DECEMBER 22	1980	28.0	12.8840	12.8840	0.0	-40.00	0.0
FEBRUARY 2	1981	78.0	12.8840	12.8888	-0.0781	-18.00	0.1880
FEBRUARY 8	1981	81.0	12.8840	12.8882	0.0200	-8.70	0.1890
FEBRUARY 8	1981	82.0	12.8840	12.8880	0.0800	-8.00	0.1890
FEBRUARY 8	1981	88.0	12.8840	12.8888	-0.0880	-8.00	0.0480
FEBRUARY 8	1981	88.0	12.8840	12.8820	0.1288	-2.40	0.0200
FEBRUARY 10	1981	88.0	12.8840	12.8828	-0.0280	-0.80	-0.0880
FEBRUARY 10	1981	88.0	12.8840	12.8818	0.0280	2.10	-0.1820
FEBRUARY 11	1981	87.0	12.8840	12.8808	0.0880	8.80	-0.2280
FEBRUARY 11	1981	87.0	12.8840	12.8788	0.1888	7.80	-0.2800
FEBRUARY 12	1981	88.0	12.8840	12.8780	0.0880	11.00	-0.4400
FEBRUARY 12	1981	88.0	12.8848	12.8788	0.0888	18.40	-0.4800
FEBRUARY 12	1981	88.0	12.8840	12.8780	-0.0280	18.40	-0.8280
FEBRUARY 18	1981	82.0	12.8840	12.8828	0.0100	18.20	-0.0400
FEBRUARY 17	1981	82.0	12.8840	12.8848	-0.0800	28.10	-0.0108
FEBRUARY 18	1981	84.0	12.8848	12.8840	0.0800	27.40	0.0800
FEBRUARY 18	1981	88.0	12.8840	12.8828	0.1080	28.80	0.0880
FEBRUARY 22	1981	88.0	12.8840	12.8882	-0.0400	22.40	0.0800
FEBRUARY 28	1981	102.0	12.8840	12.8848	-0.0880	42.80	0.0480
MARCH 18	1981	122.0	12.8840	12.8870	-0.2200	118.00	0.0700




Figure B.16 ME9 MP#7 D=13.89m

HARVEST POINT 00. 8						
	TIME DAYS	1017. READ.	ROAD1000	DISPL CM	LOCATION	
DECEMBER 23 1990	25.0	15.5035	10.5035	0.0	-40.00	0.0
FEBRUARY 3 1991	75.0	15.5035	15.5050	-0.1450	-15.00	0.1050
FEBRUARY 5 1991	81.0	15.5030	15.5052	0.0101	-5.70	0.1200
FEBRUARY 5 1991	83.0	15.5035	15.5045	0.0501	-5.00	0.1500
FEBRUARY 5 1991	84.0	15.5035	15.5045	-0.0545	-5.00	0.0450
FEBRUARY 5 1991	85.0	15.5035	15.5035	0.1000	-3.40	0.0300
FEBRUARY 10 1991	88.0	15.5035	15.5035	-0.0850	-0.50	-0.0850
FEBRUARY 10 1991	88.R	15.5035	15.5005	0.1000	3.10	-0.1550
FEBRUARY 11 1991	87.0	15.5035	15.5005	0.0550	5.50	-0.3350
FEBRUARY 11 1991	87.0	15.5035	15.5000	0.1700	7.50	-0.3000
FEBRUARY 13 1991	89.0	15.5035	15.5000	0.1101	11.00	-0.4400
FEBRUARY 13 1991	85.0	15.5035	15.5575	0.1401	10.40	-0.4500
FEBRUARY 13 1991	85.0	15.5035	15.5575	0.0751	15.40	-R.5350
FEBRUARY 15 1991	83.0	15.5035	15.5035	0.0500	15.30	-0.0400
FEBRUARY 17 1991	83.0	15.5035	15.5035	0.0500	25.10	-0.0100
FEBRUARY 18 1991	84.0	15.5035	15.5035	0.2001	27.40	0.0500
FEBRUARY 18 1991	85.0	15.5035	15.5035	0.1500	25.00	0.0550
FEBRUARY 23 1991	85.0	15.5035	15.5045	-0.0085	33.40	R.2500
FEBRUARY 26 1991	103.0	15.5035	15.5035	0.0450	43.50	0.0450
MARCH 15 1991	123.R	15.5035	15.1050	48.5300	115.00	R.0700




Figure B.17 ME9 MP#8 D=15.61m

MAGNET PEIOT 08.		0					
		TIME SATD	LOIT. READ.	ROADINGS	DISPL CMS	LOCATION	
DECEMBER 32	1990	30.0	10.0103	10.0103	0.0	-40.00	0.0
FEBRUARY 3	1991	70.0	10.0103	10.0310	-0.1001	-10.00	0.1000
FEBRUARY 6	1991	81.0	10.0103	10.0100	0.0410	-0.70	0.1000
FEBRUARY 8	1991	83.0	10.0103	10.0100	0.0010	-0.00	0.1000
FEBRUARY 8	1991	84.0	10.0103	10.0100	0.0303	-0.00	0.0400
FEBRUARY 9	1991	86.0	10.0103	10.0170	0.1007	-3.00	0.0300
FEBRUARY 10	1991	88.0	10.0103	10.0100	0.0001	-0.00	-0.0000
FEBRUARY 10	1991	89.0	10.0103	10.0100	0.0000	3.10	-0.1000
FEBRUARY 11	1991	87.0	10.0103	10.0100	0.1100	0.00	-0.3300
FEBRUARY 11	1991	87.0	10.0103	10.0133	0.3300	7.00	-0.3000
FEBRUARY 12	1991	88.0	10.0103	10.0133	0.1013	11.00	-0.4400
FEBRUARY 12	1991	89.0	10.0103	10.0110	0.1000	10.40	-0.0000
FEBRUARY 13	1991	89.0	10.0103	10.0110	0.1300	10.40	-0.0300
FEBRUARY 16	1991	93.0	10.0103	10.0100	0.1401	10.30	-0.0400
FEBRUARY 17	1991	93.0	10.0103	10.0100	0.1701	30.10	-0.0100
FEBRUARY 18	1991	90.0	10.0103	10.0103	0.3700	37.40	0.0000
FEBRUARY 19	1991	90.0	10.0103	10.0100	0.3001	30.00	0.0000
FEBRUARY 23	1991	90.0	10.0103	10.0100	0.1300	33.40	0.0000
FEBRUARY 26	1991	103.0	10.0103	10.0170	0.1300	03.00	0.0400
MARCH 10	1991	123.0	10.0103	10.0200	-0.0004	110.00	0.0700




Figure B.18 ME9 MP#9 D=16.92m

MAGNET POINT NO.		10					
		TIME DAYS	IRIT. 33AS.	3EABIRRS	DISPL. CM	LOCATION	
DEC30033	33	1880	38.0	18.3833	18.3832	0.0	-50.00 0.0
F30RUARY	2	1881	76.0	18.3833	18.3848	-0.1483	-18.00 0.1080
F30RUARY	8	1881	81.0	18.3822	18.3840	-0.0064	-8.70 0.1800
F30RUARY	8	1881	83.0	18.3833	18.3838	0.0102	-8.00 0.1800
F30RUARY	8	1881	88.8	18.3833	18.3832	-0.0053	-8.00 0.0480
F30RUARY	8	1881	88.0	18.3823	18.3812	0.1307	-2.40 0.0300
F30RUARY	10	1881	88.0	18.3823	18.2718	-1.0081	-0.80 -0.0880
F30RUARY	10	1881	88.0	18.3822	18.2888	0.0062	3.10 -0.1880
F30RUARY	11	1881	87.0	18.3833	18.2883	0.1848	8.80 -0.3380
F30RUARY	11	1881	87.0	18.3833	18.2870	0.3810	7.80 -0.3880
F30RUARY	13	1881	88.0	18.3833	18.3888	0.1288	11.00 -0.4880
F30RUARY	13	1881	88.0	18.3833	18.3888	0.1800	18.40 -0.4880
F30RUARY	12	1881	88.0	18.3833	18.3888	0.1380	18.40 -0.0380
F30RUARY	18	1881	83.8	18.3833	18.3888	0.1111	18.30 -0.0480
F30RUARY	17	1881	82.0	18.3833	18.3888	0.1701	28.10 -0.0180
F30RUARY	18	1881	88.0	18.3832	18.3888	0.3311	37.40 0.0880
F30RUARY	18	1881	88.0	18.3833	18.3888	0.2881	28.80 0.0880
F30RUARY	32	1881	88.0	18.2823	18.2838	0.0703	32.40 0.0880
F30RUARY	28	1881	102.0	18.3822	18.3888	-0.8343	83.80 0.0480
MARCH	18	1881	132.0	18.2823	18.2848	-0.1887	118.00 0.0780




Figure B.19 ME9 MP#10 D=18.36m

MASSBY POINT NO.		1					
		TIME DAYS	INIT. STAGE	STAGE 1020	DISPL. CMS	LOCATION	
DISCHARGE	22	1000	28.0	2.0200	2.0200	0.0	-48.00 0.0
F000UARY	1	1001	77.0	2.2200	2.0200	-0.0220	-24.00 0.0100
F000UARY	2	1001	78.0	2.2200	2.0202	-0.0100	-21.00 0.0100
F000UARY	8	1001	81.0	2.0200	2.0202	-0.0100	-12.00 0.0100
F220UARY	8	1001	82.0	2.0200	2.0202	0.0020	-11.00 0.0220
F000UARY	2	1001	86.0	2.2200	2.0202	-0.0120	-11.00 0.0170
F220UARY	8	1001	92.0	2.2200	2.0270	0.1271	-8.00 0.0170
F220UARY	10	1001	88.0	2.2200	2.2200	0.0200	-8.00 0.0100
F000UARY	10	1001	88.0	2.0200	2.0200	0.0200	-2.00 0.0000
F200UARY	11	1001	87.0	2.0200	2.0200	0.0200	-1.00 0.0000




Figure B.20 ME10 MP#1 D=253 m

MARRET POINT RD.		3					
		TIME RAYS	INIT. READ.	READINGS	DISPL. CMS	LOCATION	
DECEMBER 22	1990	30.0	8.8778	8.8778	0.0	-48.00	0.0
FEBRUARY 1	1991	77.0	8.8779	8.8785	-0.0020	-56.00	0.0180
FEBRUARY 3	1991	78.0	8.8779	8.8788	-0.0010	-51.00	0.0180
FEBRUARY 9	1991	81.0	8.8779	8.8783	-0.0011	-19.00	0.0180
FEBRUARY 9	1991	82.0	8.8778	8.8773	0.0720	-11.00	0.0020
FEBRUARY 8	1991	88.0	8.8778	8.8773	0.0070	-11.00	0.0170
FEBRUARY 8	1991	89.0	8.8779	8.8789	0.1180	-8.00	0.0170
FEBRUARY 10	1991	89.0	8.8778	8.8778	0.0180	-8.00	0.0180
FEBRUARY 10	1991	88.0	8.8779	8.8773	0.0040	-3.00	0.0040
FEBRUARY 11	1991	97.0	8.8779	8.8779	0.0378	-1.00	0.0080




Figure B.21 ME10 MP# 2 D= 4.58 m

		HA3RET P810T 00. 3					
		TIME DAYS	IRIT. READ.	SEAD1033	SISPL CMS	LCERT13R	
SEC3M033 33	10R0	36.0	6.3R03	R.3R03	0.0	-R3.00	0.0
F33RURRY 1	1R31	77.0	3.3R03	3.3R13	-0.0R30	-34.00	0.01R0
F33RURRY 3	1R31	7R.0	3.3303	3.3913	-0.0310	-31.00	0.0100
F333UR3Y 3	13R1	31.0	6.3303	3.3303	0.0180	-1R.00	0.01R0
FERRURRY 6	1R31	63.0	3.3303	3.37R3	0.0730	-11.00	0.0320
FR3RU03Y R	1331	04.0	3.3R03	3.3303	0.0170	-11.00	0.0170
F33RU03Y 6	13R1	3R.0	6.3303	3.3730	0.1470	-3.00	0.0170
FER3URRY 10	1R31	36.0	3.3303	3.3763	0.0RR0	-3.00	0.0160
FERRURRY 10	1RR1	36.0	3.3303	3.3763	0.1030	-3.00	0.0040
F33RURRY 11	1R31	37.0	6.3303	R.3733	0.1070	-1.00	0.00R0




FIG B.22 ME10 MP# 3 D= 638m

MAGNET PEISY 85.		4					
		TIME DAYS	181T. READ.	SEAD1888	DISPL CMS	LOCATION	
DECEMBER 22	1980	28.0	8.4018	8.4018	0.0	-48.00	0.0
FEBRUARY 1	1981	77.0	8.4018	8.4020	-0.1020	-24.00	0.0180
FEBRUARY 2	1981	78.0	8.4018	8.4028	-0.0808	-21.00	0.0180
FEBRUARY 5	1981	81.0	8.4018	8.4020	-0.1010	-18.00	0.0180
FEBRUARY 8	1981	82.0	8.4018	8.4018	0.0220	-11.00	0.0220
FEBRUARY 8	1981	84.0	8.4018	8.4018	0.0470	-11.00	0.0170
FEBRUARY 9	1981	85.0	8.4018	8.4008	0.1470	-8.00	0.0170
FEBRUARY 10	1981	86.0	8.4018	8.4008	0.1180	-8.00	0.0180
FEBRUARY 10	1981	88.0	8.4018	8.4010	0.0440	-2.00	0.0040
FEBRUARY 11	1981	87.0	8.4018	8.4002	0.1880	-1.00	0.0080




FIG B.23 ME10 MP#4 D= 8.40 m

HARBOY POINT NO.		S				
		TIME DAYS	IRIT. ROAD	REDSING	SIRPL CMB	LOCATION
DECEMBER 22	1980	36.0	10.8188	10.2188	0.0	-48.00 0.0
FEBRUARY 1	1981	77.0	10.8188	10.8800	-0.1280	-54.00 0.0180
FEBRUARY 3	1981	78.0	10.8188	10.8202	-0.1810	-21.00 0.0180
FEBRUARY 8	1981	81.0	10.8188	10.8188	-0.0808	-18.00 0.0180
FEBRUARY 8	1981	88.0	10.8188	10.2188	0.0280	-11.00 0.0880
FEBRUARY 8	1981	84.0	10.8188	10.2188	0.0170	-11.00 0.0170
FEBRUARY 8	1981	88.0	10.2188	10.8178	0.1170	-8.00 0.0170
FEBRUARY 10	1981	88.0	10.8188	10.2888	-1.0810	-8.00 0.0180
FEBRUARY 10	1981	88.0	10.2188	10.8178	0.0740	-8.00 0.0040
FEBRUARY 11	1981	87.0	10.8188	10.2172	0.1280	-1.00 0.0040




Figure B.24 ME10 MP#5 D=10.22m

MAGNET POINT NO.		E				
		TIME DAYE	1017. READ.	BRAB1000	DISPL. CM0	LOCATION0
DECEMBER 22	1980	20.0	12.2770	12.2770	0.0	-40.00 0.0
FEBRUARY 1	1981	77.0	12.2770	12.2769	-0.1020	-24.00 0.0180
FEBRUARY 2	1981	78.0	12.2770	12.2768	-0.1010	-21.00 0.0180
FEBRUARY 8	1981	81.0	12.2770	12.2762	-0.1110	-18.00 0.0180
FEBRUARY 9	1981	82.0	12.2770	12.2772	-0.0070	-11.00 0.0220
FEBRUARY 9	1981	84.0	12.2770	12.2772	-0.0120	-11.00 0.0170
FEBRUARY 9	1981	88.0	12.2770	12.2769	0.1170	-8.00 0.0170
FEBRUARY 10	1981	88.0	12.2770	12.2770	0.0180	-8.00 0.0180
FEBRUARY 10	1981	88.0	12.2770	12.2769	0.1040	-2.00 0.0040
FEBRUARY 11	1981	87.0	12.2770	12.2768	0.1800	-1.00 0.0080




Figure B.25 ME10 MP#6 D=12.28m

MAGNET POINT NO.		7						
		TIME DAYS	1617 0240.	R2421000	DISPL CM	LOCATION		
22C2M000	22	1000	20.0	14.2020	14.2020	0.0	-48.00	0.0
F00RUARY	1	1441	77.0	14.2020	14.2440	-0.1220	-24.00	0.0140
F00RUARY	2	1241	70.0	14.2020	14.2040	-0.1410	-21.00	0.0100
F00RUARY	2	1201	01.0	14.2220	14.2447	-0.1010	-10.00	0.0140
F00RUARY	3	1001	02.0	14.2222	14.2420	0.0020	-11.00	0.0220
F00RUARY	3	1001	04.0	14.2020	14.2222	-0.0221	-11.00	0.0170
F00RUARY	2	1041	00.0	14.2220	14.2022	0.0070	-4.00	0.0170
F00RUARY	10	1001	02.0	14.2020	14.2420	-0.0010	-4.00	0.0140
F00RUARY	10	1401	00.0	14.2020	14.2414	0.1024	-2.00	0.0040
F00RUARY	11	1401	07.0	14.2420	14.2002	0.2270	-1.00	0.0040




Figure B.26 ME10 MP#7 D=14.29m

MAGNETY PRINT NO.		8					
		TIME DAYS	1917 READ.	08A01600	010PL CMS	LOCATION	
DECEMBER 00	1000	20.0	10.0400	10.0400	0.0	-40.00	0.0
FEBRUARY 1	1001	77.0	10.0400	10.0400	-0.1004	-04.00	0.0100
FEBRUARY 2	1001	78.0	10.2400	10.2400	-0.1000	-01.00	0.0100
FEBRUARY 8	1001	81.0	10.2400	10.0420	-0.0012	-10.00	0.0100
FEBRUARY 8	1001	80.0	10.2420	10.0400	0.0020	-11.00	0.0000
FEBRUARY 8	1001	84.0	10.2400	10.0400	0.0470	-11.00	0.0170
FEBRUARY 8	1001	88.0	10.2400	10.2412	0.1000	-0.00	0.0170
FEBRUARY 10	1001	88.0	10.2400	10.2410	0.1100	-0.00	0.0100
FEBRUARY 10	1001	88.0	10.2420	10.2410	0.1041	-2.00	0.0040
FEBRUARY 11	1001	87.0	10.0400	10.2200	0.2071	-1.00	0.0000




Figure B.27 ME10 MP#8 D=16.25m

MAGNET POINT NO		1				
		TIME DAYS	INIT READ	HEADINGS	DISPL CMs	LOCATION
MARCH 3	1881	107.0	3.0087	3.0087	0.0	-27.40 0.0
MARCH 4	1881	108.0	3.0087	3.0087	0.1100	-21.40 0.1100
MARCH 6	1881	108.0	3.0087	3.0082	0.1700	-18.80 0.1200
MARCH 7	1881	111.0	3.0087	3.0082	0.2700	-7.10 0.2200
MARCH 8	1881	113.0	3.0087	3.0082	-0.1200	-3.40 -0.1700
MARCH 10	1881	114.0	3.0087	3.0082	0.0800	0.0 0.0300
MARCH 10	1881	114.0	3.0087	2.8680	-0.2100	3.80 -2.2800
MARCH 11	1881	118.0	3.0087	2.8282	-0.2700	10.20 -8.1200
MARCH 13	1881	117.0	3.0087	2.8280	-0.7861	18.80 -8.8260
MARCH 18	1881	123.0	3.0087	2.8282	-1.1380	24.80 -8.8880




Figure B.28 ME17 MP#1 D=3.01m

MAGNET POINT NO		3					
		TIME DAYS	INIT	READ	READINGS	DISPL CMS	LOCATION
MARCH 3	1991	107.0	4.2008	4.2008	0.0	-27.40	0.0
MARCH 4	1991	108.0	4.3008	4.2002	0.1388	-21.40	0.1100
MARCH 8	1991	108.0	4.2008	4.3000	0.1700	-18.80	0.1200
MARCH 7	1991	111.0	4.2008	4.1887	0.3888	-7.10	0.2200
MARCH 8	1991	112.0	4.2008	4.1887	-0.0801	-2.40	-0.1700
MARCH 10	1991	114.0	4.2008	4.1887	0.1088	0.0	0.0200
MARCH 10	1991	114.0	4.2008	4.1802	-0.3800	2.80	-2.2800
MARCH 11	1991	118.0	4.2008	4.1243	-0.4800	10.20	-8.1200
MARCH 12	1991	117.0	4.2008	4.1242	-0.8880	18.80	-8.8280
MARCH 18	1991	133.0	4.2008	4.1282	-1.4881	24.80	-8.8880




Figure B.29 ME17 MP#2 D=4.20m

MARET POINT NO		2					
		TIME DAYS	INIT READ	READINGS	DISPL CMS	LOCATION	
MARCH 2	1991	107.0	9.2427	9.2427	0.0	-27.40	0.0
MARCH 4	1991	109.0	9.2427	9.2420	0.0900	-21.40	0.1100
MARCH 6	1991	109.0	9.2427	9.2422	0.1700	-19.90	0.1200
MARCH 7	1991	111.0	9.2427	9.2420	0.2900	-7.10	0.2200
MARCH 9	1991	112.0	9.2427	9.2422	-0.1200	-2.40	-0.1700
MARCH 10	1991	119.0	9.2927	9.2422	0.0900	0.0	0.0200
MARCH 10	1991	114.0	9.2427	9.2222	-0.2201	2.90	-2.2900
MARCH 11	1991	115.0	9.2427	9.2027	-4.1200	10.20	-9.1200
MARCH 12	1991	117.0	9.2427	9.2092	-4.9790	19.90	-9.9290
MARCH 19	1991	122.0	9.2427	9.2097	-9.2990	24.90	-9.9990




Figure B.30 ME17 MP#3 D=5.24m

MAGNET POINT NO		8					
		TIME DAYS	INIT READ	READINGS	DISPL CMs	LOCATION	
MARCH 2	1961	107.0	8.8852	8.8852	0.0	-27.40	0.0
MARCH 4	1961	108.0	8.8852	8.8850	0.1288	-21.80	0.1100
MARCH 8	1961	108.0	8.8852	8.8850	0.1288	-18.80	0.1200
MARCH 7	1961	111.0	8.8852	8.8857	0.2700	-7.10	0.2200
MARCH 8	1961	112.0	8.8852	8.8848	-0.1000	-2.40	-0.1700
MARCH 10	1961	118.0	8.8852	8.8850	0.0888	0.0	0.0200
MARCH 10	1961	114.0	8.8852	8.8857	-0.4201	2.80	-2.2600
MARCH 11	1961	118.0	8.8852	8.8778	-7.2800	10.20	-8.1200
MARCH 12	1961	117.0	8.8852	8.8828	-6.2800	18.80	-8.8280
MARCH 18	1961	122.0	8.8852	8.8828	-6.7150	24.80	-8.8850




Figure B.31 ME17 MP#4 D=6.69m

MARKET POINT NO		5					
		TIME DAYS	LEIT. READ	SEAORCS	DISPL CMs	LOCATION	
MARCH 3	1991	107.0	7.5530	7.5530	0.0	-37.50	0.0
MARCH 4	1991	108.0	7.5530	7.5535	0.1501	-31.40	0.1100
MARCH 5	1991	109.0	7.5530	7.5535	0.1701	-15.50	0.1300
MARCH 7	1991	111.0	7.5530	7.5533	0.3000	-7.10	0.3300
MARCH 8	1991	113.0	7.5530	7.5530	-0.0700	-3.50	-0.1700
MARCH 10	1991	114.0	7.5530	5.4115	-51.5155	0.0	0.0300
MARCH 10	1991	114.0	7.5530	5.4115	-55.1355	3.50	-3.3500
MARCH 11	1991	115.0	7.5530	5.4115	-55.5555	10.30	-5.1300
MARCH 13	1991	117.0	7.5530	5.4115	-50.5755	15.50	-5.5350
MARCH 15	1991	123.0	7.5530	5.4115	-50.5355	35.50	-5.5550




Figure B.32 ME17 MP#5 D=7.59m

BASIC DATA FOR COMPUTATION						
THE HOLE WAS MEAS READ ON 7 OCCASIONS						
CALIBRATION READINGS WERE TAKEN ON DECEMBER 22 1980						
THE DEEPEST READING IN 99.00 FEET						
THE SHALLOWEST READING IN 2.00 FEET						
THE CLAMP WAS 2.00 FEET ABOVE GROUND						
THE ANGLE BETWEEN THE "A" AXIS						
AND THE AXIS OF PRINCIPAL						
DEFORMATION IS 21.90 DEGREES						

ALGEBRAIC DIFFERENCE IN CALIBRATION READINGS						
A DIRECTION B DIRECTION						
DEPTH	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B
-28.92	94	20	39	-119	92	-142
-28.21	-234	309	-929	-192	140	-322
-28.90	-492	524	-494	-229	190	-419
-24.99	-492	990	-1043	-452	449	-940
-24.38	404	-349	791	-425	591	-1199
-22.77	970	-902	1073	-920	474	-1004
-22.19	410	-949	1199	-444	404	-949
-22.99	799	-700	1499	-379	329	-701
-21.55	790	-722	1512	-200	254	-554
-21.34	1004	-990	1994	-149	101	-290
-20.73	979	-504	1999	-149	109	-297
-20.12	747	-990	1427	-120	92	-202
-19.51	594	-519	1103	-109	94	-179
-19.40	932	-494	999	-20	-4	-29
-19.29	420	-344	745	-97	9	-94
-17.99	409	-341	799	-100	49	-149
-17.07	575	-919	1092	19	-79	94
-16.45	929	-959	1197	47	-124	141
-16.95	794	-710	1499	124	-197	291
-16.24	979	-957	1475	199	-210	379
-14.53	1049	-979	2024	249	-301	547
-14.02	540	-929	1919	240	-294	724
-12.41	999	-920	1919	344	-442	934
-12.90	1027	-450	1447	297	-259	994
-12.19	972	-999	1972	-32	-29	-7
-11.59	940	-974	1919	-70	22	-43
-10.97	990	-994	1944	1	-44	99
-10.39	909	-947	1799	97	-149	244
-9.79	504	-542	1744	99	-154	291
-9.14	799	-731	1929	7	-92	70
-8.93	990	-520	1210	-15	-29	20
-7.92	929	-574	1210	-99	39	-122
-7.32	994	-499	1044	4	-92	90
-6.71	904	-441	949	20	-52	92
-6.10	299	-152	492	-72	24	-57
-5.99	199	-124	209	-299	210	-499
-4.94	247	-219	902	-295	220	-499
-4.27	494	-402	944	-140	92	-222
-2.99	999	-499	1042	-41	40	-121
-3.09	279	-314	490	-340	274	-914
-2.44	194	-109	270	-999	529	-1111
-1.93	159	-99	297	-970	909	-1279
-1.22	177	-120	297	-733	940	-1412
-0.91	192	-109	297	-920	774	-1904

Figure B.33 SI6-FIELD DATA

ALGEBRAIC DIFFERENCE P06 SET 3 OBTAINED ON FEBRUARY 01 1981										DEFLECTION COMPONENTS RESOLVED INTO			
DEPTH	A DIRECTION		B DIRECTION		C DIRECTION		D DIRECTION		DEPTH	PROPOSED DEFORMATION DIRECTIONS		TRUE DEFLECTION	
	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	C1	C2		TAUS DEFLECTION OF A IN CMS	TAUS DEFLECTION OF B IN CMS	TAUS DEFLECTION OF A IN CMS	TAUS DEFLECTION OF B IN CMS
-28 82	47	3	44	-130	97	-187	-187	-187	-28 82	1.8838E-02	-1.8838E-02	-1.8838E-02	-1.8838E-02
-28 21	-338	283	-621	-188	130	-328	-328	-328	-28 21	2.8448E-02	-7.8733E-03	-7.8733E-03	-7.8733E-03
-28 80	-862	888	-1750	-238	181	-388	-388	-388	-28 80	4.9220E-02	3.4804E-02	3.4804E-02	3.4804E-02
-24 88	-911	959	-1077	-488	428	-513	-513	-513	-24 88	-1.9204E-02	8.3488E-02	8.3488E-02	8.3488E-02
-24 38	381	-331	712	-833	884	-1187	-1187	-1187	-24 38	-8.8823E-02	2.4188E-02	2.4188E-02	2.4188E-02
-33 77	886	-613	1099	-838	488	-1004	-1004	-1004	-33 77	-8.3888E-02	2.1348E-02	2.1348E-02	2.1348E-02
-33 18	880	-682	1142	-686	382	-896	-896	-896	-33 18	-1.0810E-01	-7.8208E-02	-7.8208E-02	-7.8208E-02
-22 88	740	-708	1448	-380	324	-714	-714	-714	-32 88	-1.1810E-01	-3.8824E-02	-3.8824E-02	-3.8824E-02
-21 88	771	-732	1503	-318	244	-580	-580	-580	-21 88	-1.3088E-01	-3.7888E-02	-3.7888E-02	-3.7888E-02
-21 34	860	-658	1518	-170	88	-288	-288	-288	-21 34	-1.4188E-01	-7.1843E-02	-7.1843E-02	-7.1843E-02
-20 73	858	-824	1682	-188	108	-280	-280	-280	-20 73	-1.3488E-01	-7.3812E-02	-7.3812E-02	-7.3812E-02
-20 12	741	-884	1435	-138	78	-204	-204	-204	-20 12	-1.3827E-01	-7.7788E-02	-7.7788E-02	-7.7788E-02
-18 81	878	-830	1108	-118	83	-182	-182	-182	-18 81	-1.2822E-01	-8.4832E-02	-8.4832E-02	-8.4832E-02
-18 80	818	-878	884	-81	32	-83	-83	-83	-18 80	-1.2811E-01	-1.8048E-01	-1.8048E-01	-1.8048E-01
-18 28	413	-341	784	-91	32	-83	-83	-83	-18 28	-1.2727E-01	-1.8308E-01	-1.8308E-01	-1.8308E-01
-17 84	383	-384	747	-110	38	-148	-148	-148	-17 84	-1.2788E-01	-1.8183E-01	-1.8183E-01	-1.8183E-01
-17 07	870	-822	1082	14	-81	88	88	88	-17 07	-1.3788E-01	-1.8041E-01	-1.8041E-01	-1.8041E-01
-18 48	814	-688	1178	88	-130	188	188	188	-18 48	-1.3788E-01	-1.8041E-01	-1.8041E-01	-1.8041E-01
-18 88	747	-721	1488	100	-183	283	283	283	-18 88	-1.2873E-01	-1.8848E-01	-1.8848E-01	-1.8848E-01
-18 24	881	-808	1880	138	-218	384	384	384	-18 24	-1.3800E-01	-2.2488E-01	-2.2488E-01	-2.2488E-01
-14 83	1031	-888	2017	238	-301	937	937	937	-14 83	-1.4221E-01	-2.4278E-01	-2.4278E-01	-2.4278E-01
-14 02	878	-838	1814	333	-387	730	730	730	-14 02	-1.4888E-01	-2.8071E-01	-2.8071E-01	-2.8071E-01
-13 41	878	-830	1818	380	-448	838	838	838	-13 41	-1.4872E-01	-2.4703E-01	-2.4703E-01	-2.4703E-01
-12 80	1818	-871	1887	248	-307	888	888	888	-12 80	-1.4872E-01	-2.4703E-01	-2.4703E-01	-2.4703E-01
-12 18	888	-818	1881	38	-40	1	1	1	-12 18	-1.4884E-01	-2.3080E-01	-2.3080E-01	-2.3080E-01
-11 88	832	-888	1820	-78	13	-82	-82	-82	-11 88	-1.3828E-01	-2.2808E-01	-2.2808E-01	-2.2808E-01
-10 87	848	-884	1834	-7	-84	87	87	87	-10 87	-1.8288E-01	-2.3232E-01	-2.3232E-01	-2.3232E-01
-10 38	803	-888	1788	88	-188	244	244	244	-10 38	-1.4802E-01	-2.3401E-01	-2.3401E-01	-2.3401E-01
-8 78	884	-884	1748	81	-187	248	248	248	-8 78	-1.4448E-01	-2.3712E-01	-2.3712E-01	-2.3712E-01
-8 14	780	-788	1848	8	-83	88	88	88	-8 14	-1.2842E-01	-1.8848E-01	-1.8848E-01	-1.8848E-01
-6 83	878	-832	1311	-34	-83	18	18	18	-6 83	-1.2848E-01	-2.0030E-01	-2.0030E-01	-2.0030E-01
-7 82	831	-884	1211	-83	33	-128	-128	-128	-7 82	-1.1768E-01	-2.0170E-01	-2.0170E-01	-2.0170E-01
-7 32	880	-808	1088	880	4	-88	82	82	-7 32	-1.1318E-01	-1.8888E-01	-1.8888E-01	-1.8888E-01
-6 71	887	-847	844	17	-88	88	88	88	-6 71	-1.2248E-01	-1.8378E-01	-1.8378E-01	-1.8378E-01
-8 10	270	-308	478	-80	20	-80	-80	-80	-8 10	-8.8218E-02	-1.8810E-01	-1.8810E-01	-1.8810E-01
-8 48	178	-132	307	-288	200	-488	-488	-488	-8 48	-1.0108E-01	-1.8724E-01	-1.8724E-01	-1.8724E-01
-4 88	288	-228	487	-278	212	-480	-480	-480	-4 88	-1.0888E-01	-1.8772E-01	-1.8772E-01	-1.8772E-01
-4 27	482	-417	898	-147	71	-218	-218	-218	-4 27	-1.0472E-01	-1.8038E-01	-1.8038E-01	-1.8038E-01
-3 88	843	-828	1042	-84	28	-112	-112	-112	-3 88	-1.1128E-01	-1.4820E-01	-1.4820E-01	-1.4820E-01
-3 08	378	-331	707	-338	283	-888	-888	-888	-3 08	-8.8738E-02	-1.1733E-01	-1.1733E-01	-1.1733E-01
-2 44	182	-114	288	-888	828	-1114	-1114	-1114	-2 44	-8.8888E-02	-1.2388E-01	-1.2388E-01	-1.2388E-01
-1 83	180	-188	288	-878	808	-1283	-1283	-1283	-1 83	-8.8888E-02	-1.2388E-01	-1.2388E-01	-1.2388E-01
-1 22	187	-128	288	-748	888	-1413	-1413	-1413	-1 22	-8.7412E-02	-1.2888E-01	-1.2888E-01	-1.2888E-01
-0 81	147	-108	288	-848	778	-1824	-1824	-1824	-0 81	-1.0188E-01	-1.8403E-01	-1.8403E-01	-1.8403E-01

ALGEBRAIC DIFFERENCE P06 SET 3 OBTAINED ON FEBRUARY 08 1981										DEFLECTION COMPONENTS RESOLVED INTO			
A DIRECTION					B DIRECTION					PROPOSED DEFORMATION DIRECTIONS			
DEPTH	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	DEPTH IN MS	TAUS DEFLECTION OF A IN CMS		TAUS DEFLECTION OF B IN CMS			
-28 82	48	3	43	-148	80	-208	-28 82	2.3841E-02	-2.8888E-02	-2.8888E-02	-2.8888E-02		
-28 21	-238	267	-823	-301	130	-331	-28 21	4.8888E-03	-1.8488E-02	-1.8488E-02	-1.8488E-02		
-28 80	-488	811	-888	-238	188	-407	-28 80	7.0482E-02	8.8112E-03	8.8112E-03	8.8112E-03		
-24 88	-818	873	-1082	-808	427	-838	-24 88	-1.8771E-03	-1.2172E-02	-1.2172E-02	-1.2172E-02		
-24 38	378	-320	888	-831	881	-1182	-24 38	-6.1820E-02	-4.1788E-02	-4.1788E-02	-4.1788E-02		
-33 77	880	-808	1088	-840	482	-1002	-33 77	-1.0288E-01	-4.2810E-02	-4.2810E-02	-4.2810E-02		
-33 18	888	-844	1140	-470	382	-882	-33 18	-1.2301E-01	-9.7881E-02	-9.7881E-02	-9.7881E-02		
-22 88	748	-701	1448	-380	321	-711	-22 88	-1.3870E-01	-7.8180E-02	-7.8180E-02	-7.8180E-02		
-21 88	778	-728	1506	-312	244	-587	-21 88	-1.8210E-01	-8.7428E-02	-8.7428E-02	-8.7428E-02		
-21 34	884	-848	1830	-188	88	-283	-21 34	-1.7822E-01	-1.1808E-01	-1.1808E-01	-1.1808E-01		
-20 73	878	-822	1700	-188	103	-288	-20 73	-1.8800E-01	-1.2877E-01	-1.2877E-01	-1.2877E-01		
-20 12	782	-704	1488	-133	74	-207	-20 12	-1.2828E-01	-1.2304E-01	-1.2304E-01	-1.2304E-01		
-18 81	887	-833	1120	-122	81	-183	-18 81	-6.7703E-02	-1.7488E-01	-1.7488E-01	-1.7488E-01		
-18 80	824	-873	887	-88	8	-84	-18 80	-7.8808E-02	-1.8813E-01	-1.8813E-01	-1.8813E-01		
-18 28	418	-388	784	-88	2	-71	-18 28	-8.4338E-02	-1.8310E-01	-1.8310E-01	-1.8310E-01		
-17 88	384	-348	742	-113	38	-181	-17 88	-8.8412E-02	-1.7800E-01	-1.7800E-01	-1.7800E-01		
-17 07	884	-818	1082	8	-88	82	-17 07	-7.2418E-02	-1.8361E-01	-1.8361E-01	-1.8361E-01		
-18 48	813	-880	1173	83	-133	188	-18 48	-8.8388E-02	-1.8888E-01	-1.8888E-01	-1.8888E-01		
-18 88	748	-718	1483	88	-188	283	-18 88	-8.7822E-02	-2.2740E-01	-2.2740E-01	-2.2740E-01		
-18 24	888	-888	1883	147	-231	388	-18 24	-1.1478E-01	-2.4880E-01	-2.4880E-01	-2.4880E-01		
-14 83	1038	-882	2021	232	-303	838	-14 83	-1.1217E-01	-2.8848E-01	-2.8848E-01	-2.8848E-01		
-14 02	888	-838	1822	328	-408	733	-14 02	-1.0888E-01	-2.8782E-01	-2.8782E-01	-2.8782E-01		
-13 41	880	-837	1817	388	-448	834	-13 41	-1.0340E-01	-2.8888E-01	-2.8888E-01	-2.8888E-01		
-12 80	1018	-881	1887	238	-301	837	-12 80	-1.0731E-01	-3.0101E-01	-3.0101E-01	-3.0101E-01		
-12 18	873	-814	1887	-40	-38	-4	-12 18	-8.7800E-02	-2.8824E-01	-2.8824E-01	-2.8824E-01		
-11 88	832	-888	1817	-88	8	-87	-11 88	-8.8840E-02	-2.8447E-01	-2.8447E-01	-2.8447E-01		
-10 87	844	-888	1833	-10	-88	88	-10 87	-1.0183E-01	-3.0214E-01	-3.0214E-01	-3.0214E-01		
-10 38	808	-888	1788	88	-188	241	-10 38	-8.2014E-02	-3.0838E-01	-3.0838E-01	-3.0838E-01		
-8 78	888	-880	1748	88	-180	248	-8 78	-8.7481E-02	-3.0847E-01	-3.0847E-01	-3.0847E-01		
-8 14	803	-788	1881	-3	-81	78	-8 14	-4.2837E-02	-2.7828E-01	-2.7828E-01	-2.7828E-01		
-6 83	883	-832	1318	-28	-48	18	-6 83	-3.4330E-02	-2.7828E-01	-2.7828E-01	-2.7828E-01		
-7 82	838	-883	1318	-88	24	-122	-7 82	-2.3887E-02	-2.7228E-01	-2.7228E-01	-2.7228E-01		
-7 32	884	-808	1082	-8	-82	88	-7 32	-1.0001E-02	-2.7340E-01	-2.7340E-01	-2.7340E-01		
-8 71	807	-807	883	-14	-74	88	-8 71	8.3881E-03	-2.8888E-01	-2.8888E-01	-2.8888E-01		
-8 10	282	-222	804	-73	18	-88	-8 10	7.4788E-02	-2.1487E-01	-2.1487E-01	-2.1487E-01		
-8 48	173	-128	301	-288	187	-488	-8 48	8.1781E-02	-2.1487E-01	-2.1487E-01	-2.1487E-01		
-4 88	288	-212	478	-280	210	-480	-4 88	8.2722E-02	-2.8288E-01	-2.8288E-01	-2.8288E-01		
-4 27	488	-408	810	-147	74	-221	-4 27	2.1824E-02	-2.7888E-01	-2.7888E-01	-2.7888E-01		
-3 88	848	-488	1041	-81	32	-123	-3 88	1.8843E-02	-2.1488E-01	-2.1488E-01	-2.1488E-01		
-3 08	378	-337	713	-343	281	-804	-3 08	4.8781E-02	-2.4143E-01	-2.4143E-01	-2.4143E-01		
-2 44	187	-118	272	-888	831	-1127	-2 44	8.8704E-02	-2.3882E-01	-2.3882E-01	-2.3882E-01		
-1 83	187	-108	283	-878	807	-1288	-1 83	7.0888E-02	-2.4088E-01	-2.4088E-01	-2.4088E-01		
-1 22	178	-128	300	-781	874	-1428	-1 22	8.1882E-02	-2.8888E-01	-2.8888E-01	-2.8888E-01		
-0 81	188	-108	383	-848	770	-1818	-0 81	8.3884E-02	-2.7832E-01	-2.7832E-01	-2.7832E-01		

ALGEBRAIC DIFFERENCE FOR SET 4 OBTAINED ON FEBRUARY 09 1961						DEFLECTION COMPONENTS RESOLVED INTO			
S DIRECTION			E DIRECTION			PREFERRED DEFORMATION DIRECTIONS		TRUE DEFLECTION	
DEPTH	A1	S2	DIFFERENCE IN S	S1	S2	DIFFERENCE IN S	IN MS.	OF A IN CMs	OF S IN CMs
-29.92	98	9	81	-135	99	-201	-29.92	3 2011E-02	-1.9340E-02
-29.21	-229	299	-927	-205	129	-331	-29.21	4 8410E-02	-1.0108E-02
-29.90	-490	921	-971	-247	179	-429	-29.90	7 9999E-02	-1.1798E-02
-24.99	-911	973	-1894	-465	430	-819	-24.99	9 9199E-03	-3.6905E-03
-24.36	404	-342	749	-929	997	-1163	-24.36	-1 9400E-02	-6.2392E-03
-23.77	996	-603	1071	-632	470	-1002	-23.77	-2 0366E-02	-9.9440E-03
-23.19	902	-639	1140	-499	399	-994	-23.19	-4 9263E-02	-6.9929E-03
-22.96	790	-993	1443	-379	329	-709	-22.96	-9 9613E-02	-2.4734E-02
-21.99	999	-723	1909	-309	249	-690	-21.99	-7 6064E-02	-1.6062E-02
-21.34	999	-942	1937	-191	100	-261	-21.34	-9 6964E-02	-3.0166E-02
-20.73	990	-912	1992	-160	109	-299	-20.73	-9 7097E-02	-4.4664E-02
-20.12	790	-992	1442	-130	81	-211	-20.12	-7 4601E-02	-6.4746E-02
-19.91	999	-923	1112	-119	94	-179	-19.91	-9 6601E-02	-9.9296E-02
-19.60	929	-497	999	-49	-3	-43	-19.60	-4 9999E-02	-6.0740E-02
-19.29	423	-393	776	-92	11	-84	-19.29	-3 6464E-02	-7.3399E-02
-17.69	409	-339	744	-104	39	-142	-17.69	-4 9299E-02	-7.1666E-02
-17.07	979	-912	1997	20	-66	109	-17.07	-9 1692E-02	-9.6262E-02
-19.49	921	-999	1179	91	-129	169	-19.49	-7 1797E-02	-9.6626E-02
-19.56	790	-710	1670	103	-161	294	-19.56	-9 0660E-02	-6.0066E-02
-19.24	999	-992	1969	167	-220	-377	-19.24	-6 9669E-02	-9.6934E-02
-14.93	1044	-974	2019	244	-301	-646	-14.93	-6 3212E-02	-1.0317E-01
-14.02	990	-927	1917	344	-363	-737	-14.02	-9 9332E-02	-9.6466E-02
-13.41	669	-932	1916	390	-436	-629	-13.41	-6 6926E-02	-1.0926E-01
-12.60	1029	-999	1964	260	-300	-690	-12.60	-6 0929E-02	-1.1704E-01
-12.19	972	-603	1979	-34	-31	-3	-12.19	-9 9966E-02	-1.0967E-01
-11.66	939	-979	1919	-76	17	-99	-11.66	-9 2061E-02	-1.1421E-01
-10.97	649	-992	1931	-2	-66	93	-10.97	-1 1442E-01	-1.1170E-01
-10.36	913	-945	1792	92	-199	246	-10.36	-1 0706E-01	-1.0649E-01
-9.79	903	-842	1746	69	-196	291	-9.79	-1 0646E-01	-1.0903E-01
-9.14	609	-747	1992	7	-70	77	-9.14	-9 9704E-02	-9.1361E-02
-9.93	699	-929	1313	-19	-42	23	-9.93	-7 3197E-02	-7.6404E-02
-7.92	942	-977	1219	-99	27	-119	-7.92	-6 4666E-02	-6.6679E-02
-7.32	990	-499	1096	9	-94	99	-7.32	-9 7360E-02	-6.7646E-02
-9.71	909	-449	994	20	-91	91	-9.71	-4 9711E-02	-9.6120E-02
-9.10	293	-210	463	-66	16	-96	-9.10	2 0107E-03	-1.7290E-02
-9.49	192	-123	399	-299	204	-490	-9.49	-6 1626E-03	-6.2211E-03
-4.66	279	-210	499	-270	214	-464	-4.66	-3 4214E-02	-1.7036E-02
-4.27	499	-400	999	-141	80	-221	-4.27	-4 6094E-02	-2.0172E-02
-3.99	992	-499	1037	-79	36	-119	-3.99	-9 7966E-02	-1.9066E-02
-3.09	392	-330	712	-339	292	-921	-3.09	-2 2602E-02	-1.2491E-02
-2.44	194	-109	273	-602	930	-1132	-2.44	-6 7223E-03	-4.0461E-02
-1.63	190	-99	299	-661	911	-1292	-1.63	3 4663E-03	-6.7729E-02
-1.22	192	-122	304	-760	977	-1427	-1.22	2 1392E-02	-7.3943E-02
-0.61	193	-100	293	-937	770	-1907	-0.61	1 7401E-02	-6.0066E-02

ALGEBRAIC DIFFERENCE FOR SET 9 OBTAINED ON FEBRUARY 10 1961						DEFLECTION COMPONENTS RESOLVED INTO			
S DIRECTION			E DIRECTION			PREFERRED DEFORMATION DIRECTIONS		TRUE DEFLECTION	
DEPTH	A1	S2	DIFFERENCE IN A	S1	S2	DIFFERENCE IN S	IN MS.	OF A IN CMs	OF S IN CMs
-29.92	49	9	37	-147	94	-211	-29.92	1 7969E-02	-4.0439E-02
-29.21	-236	299	-934	-197	129	-323	-29.21	1 9993E-02	-2.4670E-02
-29.90	-499	919	-979	-292	173	-429	-29.90	4 2214E-02	-2.7376E-02
-24.99	-919	970	-1099	-909	433	-939	-24.99	-1 9312E-02	-4.9429E-02
-24.36	392	-336	721	-936	997	-1169	-24.36	-9 9797E-02	-9.3696E-02
-23.77	990	-904	1094	-943	483	-1009	-23.77	-6 1349E-02	-6.1622E-02
-23.19	999	-949	1143	-467	401	-866	-23.19	-9 4044E-02	-1.1326E-01
-22.96	744	-997	1441	-392	321	-713	-22.96	-1 1299E-01	-1.4096E-01
-21.99	779	-724	1902	-319	249	-964	-21.99	-1 2366E-01	-1.9913E-01
-21.34	999	-949	1939	-164	103	-269	-21.34	-1 3976E-01	-1.6976E-01
-20.73	672	-919	1999	-170	109	-276	-20.73	-1 2724E-01	-2.2960E-01
-20.12	749	-997	1442	-142	99	-229	-20.12	-1 0939E-01	-2.4062E-01
-19.91	993	-929	1109	-129	97	-169	-19.91	-9 9940E-02	-2.9999E-01
-19.60	924	-470	994	-62	0	-92	-19.60	-7 3021E-02	-3.2901E-01
-19.29	419	-399	774	-79	12	-60	-19.29	-9 0994E-02	-3.9994E-01
-17.69	400	-346	744	-112	44	-199	-17.69	-9 1712E-02	-3.7323E-01
-17.07	970	-916	1099	4	-79	92	-17.07	-9 0949E-02	-3.9317E-01
-19.49	919	-999	1174	99	-129	191	-19.49	-9 3244E-02	-4.1470E-01
-19.56	797	-719	1472	64	-190	294	-19.56	-4 2696E-02	-4.9116E-01
-19.24	999	-902	1990	144	-212	399	-19.24	-9 4066E-02	-4.6667E-01
-14.93	1040	-976	2019	232	-292	-924	-14.93	-4 6091E-02	-9.2193E-01
-14.02	997	-930	1917	329	-399	-717	-14.02	-3 9612E-02	-9.4964E-01
-13.41	999	-934	1620	372	-436	-911	-13.41	-1 6649E-02	-9.7692E-01
-12.60	1022	-969	1999	236	-297	-939	-12.60	-7 7304E-03	-9.0992E-01
-12.19	999	-909	1974	-43	-26	-14	-12.19	-6 2334E-04	-6.1466E-01
-11.66	933	-976	1912	-94	22	-109	-11.66	-2 0179E-03	-9.3647E-01
-10.97	944	-997	1931	-12	-90	49	-10.97	-1 9693E-02	-9.9917E-01
-10.36	909	-691	1796	93	-164	237	-10.36	-6 4649E-03	-6.6616E-01
-9.79	999	-646	1747	94	-166	239	-9.79	1 7409E-03	-9.9299E-01
-9.14	799	-749	1943	-9	-97	92	-9.14	3 0326E-02	-6.6424E-01
-9.93	999	-929	1311	-29	-36	12	-9.93	3 9296E-02	-6.6466E-01
-7.92	937	-679	1216	-92	34	-127	-7.92	4 7049E-02	-6.9723E-01
-7.32	669	-602	1069	-9	-64	46	-7.32	6 9923E-02	-7.1193E-01
-9.71	909	-461	999	-17	-72	99	-9.71	6 6011E-02	-7.4442E-01
-9.10	279	-219	493	-70	11	-61	-9.10	1 3799E-01	-6.6666E-01
-4.69	177	-126	302	-266	202	-460	-4.69	1 2349E-01	-9.9116E-01
-4.69	274	-211	499	-269	212	-491	-4.69	9 9716E-02	-6.9973E-01
-4.27	464	-402	597	-149	62	-231	-4.27	9 9109E-02	-7.1397E-01
-3.69	946	-460	1039	-69	40	-129	-3.69	9 3312E-02	-7.2207E-01
-3.09	376	-332	710	-341	276	-917	-3.09	1 1330E-01	-7.1469E-01
-3.44	196	-109	297	-690	924	-1114	-3.44	1 1079E-01	-7.2066E-01
-1.93	199	-102	297	-962	907	-1296	-1.93	1 1646E-01	-9.3602E-01
-1.22	174	-129	299	-747	961	-1426	-1.22	1 2760E-01	-7.9911E-01
-0.61	192	-102	294	-943	799	-1909	-0.61	1 1226E-01	-7.9697E-01

Figure B.35 SI6-FIELD DATA

ALGEBRAIC DIFFERENCES FOR SET 8 OBTAINED ON FEBRUARY 11 1991						DEFLECTION COMPONENTS RESOLVED INTO				
A DISSECTION			B DISSECTION			DEPTH IN M.	PREFERRED DEFORMATION DIRECTIONS		TRUE DEFLECTION OF A IN CM	TRUE DEFLECTION OF B IN CM
DEPTH	A1	S2	DIFFERENCES IN A	B1	S2		DIFFERENCES IN B			
-20.02	47.	5.	42.	-140.	82.	-202.	-20.02	1.8835E-02	-2.4870E-02	
-20.21	-335.	254.	-533.	-205.	120.	-333.	-20.21	2.8808E-02	-2.2873E-02	
-20.80	-480.	817.	-877.	-253.	150.	-432.	-20.80	8.2888E-02	-2.7821E-02	
-24.08	-518.	589.	-1084.	-808.	437.	-543.	-24.08	-3.2828E-02	-8.6378E-02	
-24.28	351.	-228.	720.	-827.	557.	-1184.	-24.28	-8.2285E-02	-8.8888E-02	
-23.77	580.	-507.	1087.	-823.	485.	-888.	-23.77	-7.4280E-02	-8.0782E-02	
-32.18	587.	-848.	1142.	-485.	357.	-855.	-32.18	-8.4278E-02	-8.2820E-02	
-22.88	748.	-701.	1448.	-382.	327.	-719.	-22.88	-1.0823E-01	-1.0248E-01	
-21.88	778.	-728.	1508.	-311.	241.	-882.	-21.88	-1.1882E-01	-1.0237E-01	
-21.34	887.	-882.	1828.	-188.	85.	-254.	-21.34	-1.3878E-01	-1.1888E-01	
-20.73	874.	-818.	1883.	-154.	110.	-274.	-20.73	-1.2202E-01	-1.3778E-01	
-20.12	748.	-700.	1448.	-134.	55.	-223.	-20.12	-8.7288E-02	-1.8232E-01	
-18.81	558.	-820.	1118.	-120.	58.	-188.	-18.81	-7.1018E-02	-1.7472E-01	
-18.80	523.	-475.	885.	-50.	0.	-50.	-18.80	-5.2877E-02	-2.0888E-01	
-18.28	415.	-350.	778.	-70.	12.	-83.	-18.28	-3.4882E-02	-2.2788E-01	
-17.88	358.	-248.	748.	-104.	38.	-138.	-17.88	-4.4080E-02	-2.2138E-01	
-17.07	588.	-818.	1088.	8.	-52.	81.	-17.07	-8.0828E-03	-2.2802E-01	
-15.48	818.	-882.	1175.	88.	-125.	187.	-15.48	-5.8847E-02	-2.3824E-01	
-15.85	782.	-718.	1470.	87.	-193.	280.	-15.85	-4.8818E-02	-2.8838E-01	
-18.24	888.	-801.	1858.	147.	-221.	387.	-18.24	-8.8404E-02	-2.8808E-01	
-14.82	1040.	-882.	2022.	238.	-537.	537.	-14.82	-8.8847E-02	-3.0434E-01	
-14.02	888.	-838.	1822.	323.	-388.	725.	-14.02	-8.7481E-02	-2.1088E-01	
-12.41	882.	-840.	1822.	374.	-437.	511.	-12.41	-2.4788E-02	-2.4248E-01	
-13.80	1018.	-587.	1888.	238.	-288.	534.	-12.80	-2.4383E-02	-2.7278E-01	
-12.18	881.	-810.	1871.	-48.	-28.	-21.	-12.18	-1.7718E-02	-2.8312E-01	
-11.88	823.	-854.	1817.	-88.	11.	-87.	-11.88	-1.8888E-02	-3.8828E-01	
-10.87	848.	-881.	1837.	-8.	-82.	54.	-10.87	-2.8820E-02	-4.0418E-01	
-10.38	807.	-887.	1784.	88.	-151.	237.	-10.38	-8.1821E-03	-4.1432E-01	
-8.75	888.	-880.	1748.	51.	-155.	247.	-8.75	-4.0802E-02	-4.1888E-01	
-8.14	800.	-787.	1857.	-3.	-71.	8.	-8.14	4.0881E-02	-4.0488E-01	
-8.82	885.	-533.	1315.	-20.	-42.	22.	-8.82	8.1057E-02	-2.8888E-01	
-7.82	837.	-887.	1224.	-84.	28.	-132.	-7.82	7.0882E-02	-2.8872E-01	
-7.33	852.	-808.	1080.	0.	-58.	58.	-7.32	8.1811E-02	-3.8887E-01	
-6.71	804.	-451.	885.	15.	-85.	81.	-6.71	8.0882E-02	-2.8887E-01	
-8.10	281.	-215.	485.	-88.	23.	-82.	-8.10	1.4880E-03	-2.4184E-01	
-8.48	178.	-130.	308.	-288.	204.	-472.	-8.48	1.4720E-01	-2.4882E-01	
-4.88	288.	-218.	484.	-387.	210.	-477.	-4.88	1.1878E-01	-3.4831E-01	
-4.27	481.	-408.	888.	-148.	81.	-228.	-4.27	1.0882E-01	-2.8488E-01	
-3.88	847.	-481.	1028.	-80.	37.	-117.	-3.88	8.8277E-02	-2.8207E-01	
-2.08	385.	-342.	727.	-247.	275.	-828.	-3.08	1.8488E-01	-2.8880E-01	
-2.44	188.	-118.	372.	-888.	521.	-1117.	-2.44	1.8280E-01	-2.8238E-01	
-1.83	183.	-108.	258.	-850.	804.	-1284.	-1.82	1.8878E-01	-2.8888E-01	
-1.32	172.	-127.	258.	-740.	888.	-1408.	-1.22	1.8874E-01	-2.4187E-01	
-0.81	180.	-188.	390.	-818.	750.	-1888.	-0.81	1.2281E-01	-2.2184E-01	

ALGEBRAIC DIFFERENCES FOR SET 7 OBTAINED ON FEBRUARY 25 1991						DEFLECTION COMPONENTS RESOLVED INTO				
A DISSECTION			B DISSECTION			DEPTH IN M	PREFERRED DEFORMATION DIRECTIONS		TRUE DEFLECTION OF A IN CM.	TRUE DEFLECTION OF B IN CM
DEPTH	A1	S2	DIFFERENCE IN A	B1	S2		DIFFERENCE IN B			
-38.82	45.	10.	38.	-150.	81.	-211.	-28.82	1.8488E-02	-4.1007E-02	
-26.21	-228.	252.	-822.	-302.	128.	-230.	-20.21	2.8248E-02	-3.4200E-02	
-25.80	-488.	818.	-878.	-241.	187.	-408.	-28.80	3.7844E-02	-1.2870E-02	
-24.88	-513.	571.	-1084.	-482.	428.	-818.	-24.88	-3.1888E-02	-8.2810E-02	
-24.28	384.	-328.	710.	-842.	588.	-1188.	-24.28	-8.7282E-02	-8.2328E-02	
-23.77	582.	-508.	1088.	-840.	473.	-1012.	-23.77	-8.8218E-02	-8.7808E-02	
-23.18	802.	-848.	1147.	-484.	284.	-888.	-22.18	-1.1184E-01	-7.2824E-02	
-22.88	745.	-700.	1448.	-280.	327.	-717.	-22.88	-1.1840E-01	-1.0180E-01	
-21.88	781.	-727.	1808.	-318.	380.	-888.	-21.88	-1.1878E-01	-1.1878E-01	
-21.34	885.	-845.	1827.	-188.	108.	-272.	-21.34	-1.3132E-01	-1.8888E-01	
-20.72	877.	-818.	1888.	-172.	108.	-280.	-20.72	-1.0838E-01	-1.8810E-01	
-20.12	747.	-700.	1447.	-138.	88.	-224.	-20.12	-8.1702E-02	-2.1382E-01	
-18.81	587.	-828.	1118.	-128.	87.	-182.	-18.81	-8.3088E-02	-2.2188E-01	
-18.80	525.	-471.	888.	-58.	2.	-80.	-18.80	-3.2183E-02	-2.8108E-01	
-18.28	420.	-388.	778.	-88.	5.	-78.	-18.28	-1.2388E-02	-2.8888E-01	
-17.88	404.	-248.	750.	-113.	38.	-182.	-17.88	-7.8788E-02	-3.0707E-01	
-17.07	571.	-518.	1080.	4.	-88.	-88.	-17.07	-1.1330E-02	-2.2212E-01	
-15.48	820.	-881.	1181.	84.	-128.	-182.	-15.48	1.1118E-02	-3.7488E-01	
-15.85	788.	-718.	1470.	88.	-188.	-244.	-15.85	1.7148E-02	-4.2872E-01	
-14.82	884.	-802.	1888.	138.	-203.	-342.	-14.82	4.1824E-02	-4.8882E-01	
-14.02	1047.	-884.	2021.	228.	-288.	-521.	-14.02	8.7826E-02	-4.8882E-01	
-13.41	882.	-835.	1827.	324.	-387.	-711.	-13.41	8.8828E-02	-8.4810E-01	
-12.80	1024.	-887.	1881.	233.	-288.	-832.	-12.80	1.1728E-01	-8.8782E-01	
-12.18	871.	-810.	1881.	-88.	-27.	-28.	-12.18	1.4781E-01	-8.8782E-01	
-11.88	838.	-884.	1822.	-82.	22.	-118.	-11.88	1.8877E-01	-8.1888E-01	
-10.87	848.	-880.	1838.	-18.	-82.	-33.	-10.87	1.7028E-01	-8.5288E-01	
-10.38	810.	-853.	1783.	78.	-144.	-222.	-10.38	1.8322E-01	-8.8112E-01	
-8.75	802.	-848.	1781.	83.	-151.	-224.	-8.75	2.1008E-01	-7.0233E-01	
-8.14	808.	-782.	1555.	-8.	-85.	-87.	-8.14	2.8270E-01	-7.0282E-01	
-8.82	858.	-828.	1312.	-30.	-33.	-3.	-8.82	2.7881E-01	-7.2488E-01	
-7.82	838.	-881.	1218.	-102.	28.	-137.	-7.82	2.8728E-01	-7.8821E-01	
-7.32	888.	-803.	1088.	-12.	-48.	-27.	-7.32	2.1742E-01	-7.2882E-01	
-6.71	805.	-448.	588.	-78.	20.	-88.	-6.71	2.2472E-01	-7.8814E-01	
-8.10	277.	-210.	487.	-284.	208.	-488.	-8.10	3.8478E-01	-7.8828E-01	
-8.48	175.	-128.	488.	-278.	217.	-482.	-8.48	3.7828E-01	-7.8828E-01	
-4.88	272.	-218.	488.	-147.	51.	-528.	-4.88	3.8182E-01	-7.8888E-01	
-4.27	488.	-408.	883.	-140.	42.	-142.	-4.27	3.8837E-01	-8.3888E-01	
-3.88	880.	-481.	1041.	-100.	42.	-142.	-3.88	2.8848E-01	-8.3888E-01	
-3.08	381.	-330.	711.	-340.	288.	-808.	-3.08	3.8478E-01	-8.1048E-01	
-2.44	188.	-107.	282.	-888.	528.	-1128.	-2.44	3.8328E-01	-8.8888E-01	
-1.83	184.	-57.	281.	-882.	810.	-1282.	-1.83	3.8387E-01	-8.8888E-01	
-1.22	172.	-120.	253.	-747.	870.	-1417.	-1.22	3.8848E-01	-8.8472E-01	
-0.81	180.	-87.	347.	-802.	722.	-1524.	-0.81	3.1872E-01	-7.8487E-01	

Figure B.36 SI6-FIELD DATA

.....

BASIC DATA FOR COMPUTATION

THE HOLE HAS BEEN MADE ON 7 OCTOBER
CALIBRATION READINGS WERE TAKEN ON 05 SEPTEMBER 22 1980
THE DEEPEST READING IS 89.00 FEET
THE SHALLOWEST READING IS 2.00 FEET
THE CLAMP RISES 2.00 FEET ABOVE GROUND

THE ANGLE BETWEEN THE "A" AXIS
AND THE AXIS OF PRINCIPAL
DEFORMATION IS 2.18 DEGREES

.....

ALGEBRAIC DIFFERENCE IN CALIBRATION READINGS						
A DIRECTION				B DIRECTION		
DEPTH	R1	R2	DIFFERENCE IN A	R1	R2	DIFFERENCE IN B
-28.82	892.	-827	1808	-648	374.	-820
-28.21	764.	-705	1888	81.	-122	184
-28.80	1108.	-1092	2184	88.	-187	262
-24.88	1288.	-1282	2880	-85.	44	-128
-24.28	877.	-841	1214	-808	740	-1844
-22.77	484	-421	819.	-1014.	428.	-1882
-22.18	827	-472	864	-1082.	1024	-2118.
-22.84	804	-448.	890.	-1148	1102.	-2281
-21.88	448.	-277	822.	-1147.	1128.	-2222
-21.24	205	-248	892.	-1218	1125.	-2284
-20.72	222	-180	412.	-1118	1048.	-2184
-20.12	288	-222	811.	-1048	878	-2028
-18.81	185.	-108	278.	-842	822.	-1714
-18.80	248	-162.	427.	-880	781.	-1821
-18.28	280	-200.	880	-827	487.	-1884
-17.88	412.	-284	747.	-427	270.	-787
-17.07	427	-282	780.	-244	282	-828
-16.44	444	-427	821.	-222	125	-281
-16.88	270.	-208	878.	-47	8.	-72
-16.24	228	-271	860	-88	15	-74
-14.82	288	-280.	428	-48	10.	-70
-14.02	288	-204	870.	-4	-82.	88
-12.41	410	-248	784	88.	-128	181
-12.80	204.	-222	828.	-28.	-22.	-17
-12.18	148	-44	222.	-288	180	-428
-11.88	218	-141	288	-288	228	-828
-10.87	287	-242.	828	-221	288	-888
-10.28	228	-282	421	-482	288	-888.
-8.75	428	-287	782.	-822	488	-1882
-8.14	471	-414	888.	-802.	827	-1140
-8.82	888.	-807	1072.	-880	880	-1240
-7.82	888	-828	1128.	-881	818	-1287
-7.22	475	-424	802	-807	720	-1827
-6.71	488	-422.	807	-728	870	-1404
-4.10	218	-288	872.	-880	408	-1288.
-5.48	221	-188	278.	-814	884	-1187
-4.88	148.	-82	241	-842	480	-1022
-4.27	128	-87	182	-488	287	-888
-2.84	75.	-8.	44.	-480	248	-748
-2.08	-82	118	-188	-282	228	-821
-2.44	-125	180.	-218.	-240	188	-428
-1.82	-118	170	-288	-212	287	-888
-1.22	-84	122	-184	-280	228	-788
-0.81	-88	148.	-227	-428	272	-788

Figure B.37 SI7-FIELD DATA

ALGEBRAIC DIFFERENCE FOR SET 2 OBTAINED ON FEBRUARY 1 1961								DEFLECTION COMPONENTS RESOLVED INTO PREFERRED DEFORMATION DIRECTIONS			
S DIRECTION				S DIRECTION				TRUE DEFLECTION OF A IR CMS		TRUE DEFLECTION OF B IR CMS	
DEPTH	S1	A2	DIFFERENCE IN S	S1	S2	DIFFERENCE IR S	IN MS.	DP A	IR CMS	DP B	IR CMS
-25.82	854.	-828	1622.	-451.	373.	-824.	-25.82	2.0120E-02		-4.5676E-03	
-25.21	783.	-705.	1472.	80.	-136.	188.	-25.21	2.3670E-02		1.3628E-02	
-25.80	1128.	-1048.	3176.	88.	-174.	273.	-25.80	4.8883E-02		3.0180E-03	
-24.86	1333.	-1354.	2837.	-132.	28.	-165.	-24.86	1.8882E-02		-3.1108E-02	
-25.38	701.	-847.	1346.	-758.	735.	-1634.	-24.38	8.1827E-02		-1.0313E-02	
-23.77	482.	-436.	821.	-1018.	820.	-1846.	-23.77	7.0186E-02		6.4887E-04	
-23.18	824.	-475.	1003.	-1088.	1018.	-2103.	-23.18	6.5888E-02		2.0888E-02	
-22.88	802.	-468.	888.	-1152.	1080.	-2232.	-22.88	6.5888E-02		3.8328E-02	
-21.88	440.	-384.	824.	-1152.	1136.	-2322.	-21.88	6.8087E-02		3.8421E-02	
-21.34	318.	-243.	888.	-1217.	1135.	-2362.	-21.34	6.7047E-02		3.8572E-02	
-20.73	227.	-187.	414.	-1121.	1048.	-2167.	-20.73	1.0034E-01		3.4878E-02	
-20.12	282.	-331.	513.	-1053.	588.	-3036.	-20.12	1.0338E-01		3.4788E-02	
-18.81	188.	-118.	283.	-880.	815.	-1708.	-18.81	1.1808E-01		4.4881E-02	
-18.80	242.	-155.	438.	-847.	777.	-1624.	-18.80	1.1888E-01		6.8287E-02	
-18.28	348.	-304.	853.	-827.	371.	-1004.	-18.28	1.1788E-01		6.8841E-03	
-17.88	408.	-357.	765.	-247.	270.	-718.	-17.88	1.2427E-01		7.1011E-02	
-17.07	422.	-373.	788.	-248.	270.	-718.	-17.07	1.2708E-01		7.8788E-02	
-16.48	458.	-445.	833.	-217.	141.	-358.	-16.48	1.3148E-01		7.8042E-02	
-15.88	370.	-308.	878.	-87.	4.	-71.	-15.88	1.3128E-01		6.2088E-02	
-15.24	324.	-276.	800.	-87.	5.	-72.	-15.24	1.2888E-01		6.8044E-02	
-14.82	340.	-358.	828.	-85.	0.	-85.	-14.82	1.3284E-01		6.8213E-02	
-14.02	380.	-312.	872.	-13.	-71.	58.	-14.02	1.4134E-01		6.3328E-02	
-13.41	408.	-368.	784.	-84.	-132.	188.	-13.41	1.3878E-01		6.3078E-02	
-12.80	282.	-241.	533.	-284.	181.	-468.	-12.80	1.3184E-01		7.7820E-02	
-12.18	142.	-87.	228.	-303.	332.	-838.	-12.18	1.3184E-01		6.8770E-02	
-11.88	208.	-151.	388.	-341.	288.	-807.	-11.88	1.3882E-01		6.8882E-02	
-10.87	288.	-248.	844.	-488.	381.	-867.	-10.87	1.4270E-01		7.8882E-02	
-10.38	338.	-287.	823.	-833.	482.	-855.	-10.38	1.3784E-01		7.8882E-02	
-8.78	418.	-370.	788.	-888.	831.	-1128.	-8.78	1.4701E-01		1.0127E-01	
-8.14	470.	-422.	882.	-888.	580.	-1338.	-8.14	1.4811E-01		1.0887E-01	
-8.83	882.	-811.	1073.	-884.	810.	-1284.	-7.82	1.5888E-01		1.1412E-01	
-7.52	880.	-842.	1122.	-810.	728.	-1638.	-7.52	1.8887E-01		1.1108E-01	
-7.32	478.	-428.	803.	-740.	888.	-1408.	-7.32	1.8324E-01		1.1133E-01	
-6.71	481.	-428.	881.	-852.	803.	-1268.	-6.71	1.8402E-01		1.1288E-01	
-6.10	307.	-288.	858.	-815.	847.	-1152.	-6.10	1.8888E-01		1.2188E-01	
-6.48	218.	-163.	378.	-882.	480.	-1032.	-6.48	1.8341E-01		1.0828E-01	
-4.88	148.	-88.	248.	-480.	388.	-868.	-4.88	1.8788E-01		1.1007E-01	
-4.27	130.	-78.	188.	-403.	344.	-747.	-4.27	1.8824E-01		1.1318E-01	
-3.88	88.	-17.	88.	-288.	237.	-833.	-3.88	1.8817E-01		6.8841E-02	
-3.08	88.	88.	-180.	-240.	178.	-418.	-2.44	2.0128E-01		1.1348E-01	
-2.44	-130.	183.	-313.	-318.	243.	-881.	-1.83	1.8788E-01		1.4888E-01	
-1.83	-121.	188.	-287.	-381.	312.	-883.	-1.83	2.0288E-01		1.4887E-01	
-1.22	-88.	113.	-182.	-430.	388.	-788.	-0.81	1.8308E-01		1.5118E-01	
-0.81	-88.	148.	-243.								

ALGEBRAIC DIFFERENCE FOR SET 3 OBTAINED ON FEBRUARY 8 1961								DEFLECTION COMPONENTS RESOLVED INTO PREFERRED DEFORMATION DIRECTIONS			
S DIRECTION				S DIRECTION				TRUE DEFLECTION OF A IR CMS		TRUE DEFLECTION OF B IR CMS	
DEPTH	S1	S2	DIFFERENCE IR S	S1	S2	DIFFERENCE IR S	IN MS.	DP A	IR CMS	DP B	IR CMS
-25.82	854.	-840.	1524.	-443.	388.	-827.	-25.82	2.3517E-02		-8.5834E-03	
-25.21	788.	-711.	1477.	88.	-127.	183.	-25.21	3.4828E-02		4.8877E-03	
-25.80	1082.	-1028.	2120.	104.	-171.	275.	-25.80	-2.4008E-02		2.0038E-02	
-24.86	1368.	-1313.	2881.	-88.	15.	-118.	-24.86	6.8473E-03		4.1882E-02	
-24.38	712.	-887.	1378.	-801.	733.	-1834.	-24.38	8.8884E-02		6.8008E-02	
-23.77	482.	-441.	833.	-1011.	838.	-1846.	-23.77	1.2871E-01		7.2817E-02	
-23.18	827.	-478.	1003.	-1088.	1033.	-2122.	-23.18	1.3230E-01		6.3828E-02	
-22.88	808.	-457.	888.	-1158.	1100.	-2258.	-22.88	1.8848E-01		6.8007E-02	
-21.88	448.	-383.	831.	-1180.	1138.	-2328.	-21.88	1.8814E-01		6.8833E-02	
-21.34	320.	-258.	878.	-1214.	1141.	-2388.	-21.34	2.0778E-01		6.1230E-02	
-20.73	238.	-181.	428.	-1118.	1081.	-2188.	-20.73	2.2852E-01		4.4808E-02	
-20.12	283.	-233.	828.	-1080.	858.	-2048.	-20.12	2.8318E-01		3.0888E-02	
-18.81	170.	-118.	288.	-888.	821.	-1718.	-18.81	2.7314E-01		2.8812E-02	
-18.80	248.	-187.	438.	-854.	778.	-1833.	-18.80	2.8848E-01		2.8848E-02	
-18.28	342.	-287.	838.	-842.	472.	-1014.	-18.28	2.8888E-01		1.0388E-02	
-17.88	411.	-357.	768.	-428.	378.	-802.	-17.88	2.7183E-01		2.7808E-03	
-17.07	422.	-388.	787.	-338.	278.	-817.	-17.07	2.8820E-01		1.8318E-02	
-16.48	487.	-448.	843.	-210.	137.	-347.	-16.48	2.8328E-01		3.8834E-02	
-15.88	388.	-307.	875.	-88.	3.	-71.	-15.88	2.8188E-01		4.1883E-02	
-15.24	328.	-278.	801.	-83.	14.	-77.	-15.24	2.8337E-01		3.7112E-02	
-14.82	343.	-284.	827.	-82.	4.	-88.	-14.82	2.8488E-01		4.2833E-02	
-14.02	380.	-302.	882.	-84.	58.	58.	-14.02	2.7284E-01		3.8884E-02	
-13.41	410.	-384.	784.	-88.	-133.	188.	-13.41	2.8108E-01		5.0723E-02	
-12.80	304.	-243.	847.	-38.	-28.	-8.	-12.80	2.8888E-01		6.8381E-02	
-12.18	150.	-88.	238.	-288.	188.	-442.	-12.18	3.0881E-01		6.8248E-02	
-11.88	203.	-141.	344.	-301.	233.	-834.	-11.88	2.8827E-01		6.4784E-02	
-10.87	287.	-242.	838.	-338.	287.	-805.	-10.87	2.8878E-01		4.8824E-02	
-10.38	337.	-283.	820.	-483.	380.	-883.	-10.38	2.8878E-01		6.8888E-02	
-8.78	420.	-388.	788.	-834.	483.	-887.	-8.78	2.7718E-01		6.8770E-02	
-8.14	474.	-421.	888.	-802.	833.	-1138.	-8.14	2.8188E-01		7.4224E-02	
-8.83	882.	-801.	1083.	-884.	882.	-1248.	-8.83	2.7880E-01		6.4333E-02	
-7.83	883.	-842.	1138.	-881.	818.	-1388.	-7.83	2.8383E-01		6.8700E-02	
-7.32	488.	-438.	820.	-804.	728.	-1830.	-7.32	3.1821E-01		7.8788E-02	
-6.71	487.	-428.	818.	-738.	887.	-1408.	-6.71	3.3113E-01		6.4030E-02	
-6.10	328.	-282.	807.	-878.	808.	-1284.	-6.10	3.8422E-01		6.0032E-02	
-6.48	228.	-188.	382.	-814.	880.	-1184.	-6.48	4.0823E-01		6.7471E-02	
-4.88	150.	-88.	248.	-848.	888.	-1032.	-4.88	4.2118E-01		6.4483E-02	
-4.27	128.	-78.	204.	-880.	402.	-882.	-4.27	4.3883E-01		7.8338E-02	
-3.88	72.	-14.	88.	-387.	347.	-744.	-3.88	4.4288E-01		6.4118E-02	
-3.08	-42.	104.	-147.	-283.	231.	-834.	-3.08	4.7828E-01		6.1410E-02	
-2.44	-128.	187.	-318.	-238.	188.	-423.	-2.44	4.7802E-01		6.8878E-02	
-1.83	-118.	171.	-380.	-313.	388.	-888.	-1.83	4.5833E-01		6.7074E-02	
-1.22	-88.	118.	-181.	-388.	324.	-710.	-1.22	4.7828E-01		6.1410E-02	
-0.81	-88.	150.	-248.	-428.	383.	-811.	-0.81	4.8380E-01		6.2388E-02	

Figure B.38 SI7-FIELD DATA

ALGEBRAIC DIFFERENCE FOR SET 4 OBTAINED ON FEBRUARY 11 1961										DEFLECTION COMPONENTS RESOLVED INTO			
A DIRECTION					B DIRECTION					PREFERRED DEFORMATION DIRECTIONS			
DEPTH	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	DEPTH IN MS.	TRUE DEFLECTION OF A IN CME	TRUE DEFLECTION OF B IN CME	TRUE DEFLECTION OF A IN CME	TRUE DEFLECTION OF B IN CME	TRUE DEFLECTION OF A IN CME	TRUE DEFLECTION OF B IN CME
-25.82	877.	-824.	1881.	-412.	365.	-777.	-25.82	-1.8888E-02	7.8480E-02	1.8888E-02	7.8480E-02	1.8888E-02	7.8480E-02
-25.21	780.	-704.	1484.	-88.	-127.	212.	-25.31	-2.8848E-02	1.2082E-01	1.2082E-01	1.2082E-01	1.2082E-01	1.2082E-01
-25.80	1118.	-1071.	2188.	108.	-185.	-279.	-25.80	1.8132E-02	1.2874E-01	1.2874E-01	1.2874E-01	1.2874E-01	1.2874E-01
-24.88	1388.	-1287.	2885.	-88.	48.	-144.	-24.88	8.7814E-02	1.1848E-01	1.1848E-01	1.1848E-01	1.1848E-01	1.1848E-01
-24.38	888.	-848.	1340.	-800.	782.	-1843.	-24.38	4.1820E-02	1.2444E-01	1.2444E-01	1.2444E-01	1.2444E-01	1.2444E-01
-22.77	487.	-431.	814.	-1008.	841.	-1848.	-22.77	4.8184E-02	1.3078E-01	1.3078E-01	1.3078E-01	1.3078E-01	1.3078E-01
-22.18	830.	-477.	1007.	-1077.	1034.	-2111.	-23.18	8.7807E-02	1.3808E-01	1.3808E-01	1.3808E-01	1.3808E-01	1.3808E-01
-22.88	888.	-488.	888.	-1148.	1104.	-2248.	-22.88	7.4478E-02	1.4204E-01	1.4204E-01	1.4204E-01	1.4204E-01	1.4204E-01
-21.88	448.	-384.	888.	-1141.	1141.	-2322.	-21.88	8.8882E-02	1.4388E-01	1.4388E-01	1.4388E-01	1.4388E-01	1.4388E-01
-21.34	312.	-288.	888.	-1313.	1142.	-2384.	-21.34	1.1421E-01	1.4218E-01	1.4218E-01	1.4218E-01	1.4218E-01	1.4218E-01
-20.72	221.	-144.	888.	-1118.	1084.	-2158.	-20.72	1.1820E-01	1.3844E-01	1.3844E-01	1.3844E-01	1.3844E-01	1.3844E-01
-20.12	280.	-231.	821.	-1081.	882.	-2023.	-20.12	1.2288E-01	1.4228E-01	1.4228E-01	1.4228E-01	1.4228E-01	1.4228E-01
-18.81	188.	-117.	282.	-848.	838.	-1713.	-18.81	1.4488E-01	1.4840E-01	1.4840E-01	1.4840E-01	1.4840E-01	1.4840E-01
-18.80	248.	-188.	434.	-848.	778.	-1824.	-18.80	1.8482E-01	1.8888E-01	1.8888E-01	1.8888E-01	1.8888E-01	1.8888E-01
-18.28	380.	-288.	848.	-834.	477.	-1011.	-18.28	1.8288E-01	1.4881E-01	1.4881E-01	1.4881E-01	1.4881E-01	1.4881E-01
-17.88	408.	-382.	782.	-418.	277.	-788.	-17.88	1.4888E-01	1.4701E-01	1.4701E-01	1.4701E-01	1.4701E-01	1.4701E-01
-17.07	430.	-387.	787.	-322.	284.	-818.	-17.07	1.8880E-01	1.8282E-01	1.8282E-01	1.8282E-01	1.8282E-01	1.8282E-01
-18.48	483.	-404.	888.	-787.	144.	-381.	-18.48	1.8408E-01	1.7884E-01	1.7884E-01	1.7884E-01	1.7884E-01	1.7884E-01
-18.48	388.	-308.	888.	-88.	12.	-78.	-18.48	1.8288E-01	1.7888E-01	1.7888E-01	1.7888E-01	1.7888E-01	1.7888E-01
-18.24	327.	-271.	888.	-82.	21.	-74.	-18.24	1.8884E-01	1.7888E-01	1.7888E-01	1.7888E-01	1.7888E-01	1.7888E-01
-14.83	342.	-284.	827.	-88.	14.	-88.	-14.83	1.8128E-01	1.7228E-01	1.7228E-01	1.7228E-01	1.7228E-01	1.7228E-01
-14.02	388.	-308.	888.	3.	-84.	81.	-14.02	1.8382E-01	1.7842E-01	1.7842E-01	1.7842E-01	1.7842E-01	1.7842E-01
-13.41	410.	-383.	783.	78.	-138.	200.	-13.41	1.8028E-01	1.8088E-01	1.8088E-01	1.8088E-01	1.8088E-01	1.8088E-01
-12.80	387.	-238.	822.	-37.	-22.	-18.	-12.80	1.8411E-01	1.8238E-01	1.8238E-01	1.8238E-01	1.8238E-01	1.8238E-01
-12.18	180.	-88.	228.	-347.	180.	-427.	-12.18	1.8884E-01	1.8048E-01	1.8048E-01	1.8048E-01	1.8048E-01	1.8048E-01
-11.87	308.	-142.	382.	-281.	238.	-820.	-11.87	1.8222E-01	1.8772E-01	1.8772E-01	1.8772E-01	1.8772E-01	1.8772E-01
-10.87	300.	-243.	843.	-328.	277.	-802.	-10.87	1.8887E-01	1.8380E-01	1.8380E-01	1.8380E-01	1.8380E-01	1.8380E-01
-10.28	338.	-281.	820.	-482.	382.	-848.	-10.28	1.8887E-01	2.1472E-01	2.1472E-01	2.1472E-01	2.1472E-01	2.1472E-01
-8.78	422.	-384.	787.	-822.	488.	-881.	-8.78	1.4742E-01	2.3104E-01	2.3104E-01	2.3104E-01	2.3104E-01	2.3104E-01
-8.14	472.	-418.	848.	-881.	848.	-1128.	-8.14	1.8188E-01	2.3788E-01	2.3788E-01	2.3788E-01	2.3788E-01	2.3788E-01
-4.83	888.	-807.	1073.	-843.	888.	-1242.	-4.83	1.8238E-01	2.3442E-01	2.3442E-01	2.3442E-01	2.3442E-01	2.3442E-01
-7.82	882.	-838.	1122.	-878.	834.	-1288.	-7.82	1.8417E-01	2.1878E-01	2.1878E-01	2.1878E-01	2.1878E-01	2.1878E-01
-7.22	488.	-428.	818.	-801.	730.	-1831.	-7.22	1.8182E-01	2.4211E-01	2.4211E-01	2.4211E-01	2.4211E-01	2.4211E-01
-8.71	488.	-428.	811.	-738.	878.	-1412.	-8.71	1.8828E-01	2.3888E-01	2.3888E-01	2.3888E-01	2.3888E-01	2.3888E-01
-8.10	317.	-270.	887.	-873.	810.	-1283.	-8.10	2.1082E-01	2.4220E-01	2.4220E-01	2.4220E-01	2.4220E-01	2.4220E-01
-8.48	328.	-188.	381.	-813.	888.	-1188.	-8.48	2.3374E-01	2.4247E-01	2.4247E-01	2.4247E-01	2.4247E-01	2.4247E-01
-4.88	182.	-100.	283.	-841.	481.	-1032.	-4.88	2.8278E-01	2.3078E-01	2.3078E-01	2.3078E-01	2.3078E-01	2.3078E-01
-4.27	127.	-74.	201.	-488.	488.	-881.	-4.27	2.8888E-01	2.2384E-01	2.2384E-01	2.2384E-01	2.2384E-01	2.2384E-01
-3.88	72.	-14.	87.	-381.	388.	-743.	-3.88	2.7128E-01	2.2728E-01	2.2728E-01	2.2728E-01	2.2728E-01	2.2728E-01
-2.88	-48.	108.	-187.	-383.	228.	-828.	-2.88	2.8012E-01	2.1780E-01	2.1780E-01	2.1780E-01	2.1780E-01	2.1780E-01
-2.44	-128.	188.	-318.	-230.	180.	-420.	-2.44	2.8882E-01	2.2738E-01	2.2738E-01	2.2738E-01	2.2738E-01	2.2738E-01
-1.83	-118.	173.	-283.	-308.	288.	-882.	-1.83	2.7848E-01	2.3827E-01	2.3827E-01	2.3827E-01	2.3827E-01	2.3827E-01
-1.22	-88.	120.	-148.	-288.	228.	-887.	-1.22	2.7770E-01	2.4888E-01	2.4888E-01	2.4888E-01	2.4888E-01	2.4888E-01
-0.81	-108.	187.	-288.	-428.	388.	-828.	-0.81	2.3738E-01	2.0881E-01	2.0881E-01	2.0881E-01	2.0881E-01	2.0881E-01

ALGEBRAIC DIFFERENCE FOR SET 5 OBTAINED ON FEBRUARY 11 1961							DEFLECTION COMPONENTS RESOLVED INTO					
A DIRECTION				B DIRECTION			PREFERRED DEFORMATION DIRECTIONS					
DEPTH	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	DEPTH IN ME.	TRUE DEFLECTION OF A IN CME.		TRUE DEFLECTION OF B IN CME		
-38.82	874.	-824.	1808.	-418.	388.	-781.	-38.82	-4.8187E-02	8.8280E-02			
-28.21	783.	-708.	1472.	78.	-131.	208.	-28.21	-2.1127E-03	8.2880E-02			
-28.80	1122.	-1048.	2171.	102.	-187.	-270.	-28.80	1.7078E-02	1.0474E-01			
-24.88	1388.	-1388.	2888.	-102.	82.	-188.	-24.88	1.4708E-02	8.4824E-02			
-24.38	882.	-883.	1348.	-814.	788.	-1888.	-24.38	8.8280E-02	3.2322E-02			
-23.77	488.	-440.	828.	-1010.	843.	-1883.	-23.77	7.8888E-02	2.2222E-02			
-22.18	827.	-474.	1001.	-1081.	1023.	-2114.	-22.18	7.8872E-02	3.8428E-02			
-22.88	803.	-483.	888.	-1148.	1101.	-3248.	-22.88	8.7878E-02	4.4881E-02			
-21.88	444.	-383.	827.	-1184.	1138.	-2218.	-21.88	8.3412E-02	4.8448E-02			
-21.34	312.	-388.	871.	-1212.	1148.	-2388.	-21.34	1.2114E-01	4.4888E-02			
-20.72	234.	-180.	424.	-1113.	1048.	-2182.	-20.72	1.3822E-01	4.8847E-02			
-20.12	280.	-221.	821.	-1082.	884.	-2028.	-20.12	1.8428E-01	8.2888E-02			
-18.81	188.	-118.	284.	-880.	820.	-1710.	-18.81	1.8784E-01	8.8882E-02			
-18.80	248.	-180.	428.	-847.	778.	-1828.	-18.80	1.7828E-01	8.7888E-02			
-18.28	348.	-301.	847.	-832.	470.	-1002.	-18.28	1.7488E-01	7.0788E-02			
-17.88	408.	-288.	788.	-418.	372.	-781.	-17.88	1.7110E-01	7.8718E-02			
-17.07	422.	-388.	781.	-222.	278.	-810.	-17.07	1.7127E-01	1.0418E-01			
-16.48	484.	-448.	830.	-208.	143.	-248.	-16.48	1.8872E-01	1.2222E-01			
-16.88	388.	-310.	878.	-87.	-11.	-88.	-16.88	1.8720E-01	1.4818E-01			
-16.24	328.	-277.	802.	-83.	18.	-88.	-16.24	1.8882E-01	1.8887E-01			
-14.82	341.	-288.	827.	-81.	11.	-72.	-14.82	1.7181E-01	1.8201E-01			
-14.02	280.	-308.	888.	8.	-88.	81.	-14.02	1.8278E-01	1.8718E-01			
-13.41	408.	-388.	781.	71.	-128.	188.	-13.41	1.8788E-01	1.8042E-01			
-12.80	288.	-248.	844.	-488.	-22.	-22.	-12.80	1.8087E-01	1.8888E-01			
-12.18	148.	-80.	238.	-288.	188.	-480.	-12.18	1.8488E-01	1.3281E-01			
-11.88	202.	-143.	348.	-281.	228.	-820.	-11.88	1.8824E-01	1.4087E-01			
-10.87	283.	-244.	837.	-321.	274.	-888.	-10.87	1.8888E-01	1.4888E-01			
-10.38	338.	-288.	820.	-488.	281.	-880.	-10.38	1.8388E-01	1.8020E-01			
-8.78	422.	-388.	781.	-222.	278.	-810.	-8.78	1.8888E-01	1.7848E-01			
-8.16	418.	-388.	808.	-803.	848.	-1148.	-8.16	1.8780E-01	1.8884E-01			
-8.82	881.	-808.	1087.	-848.	882.	-1241.	-8.82	1.8028E-01	1.8488E-01			
-7.82	882.	-848.	1137.	-882.	818.	-1288.	-7.82	1.7871E-01	1.8288E-01			
-7.32	488.	-428.	888.	-808.	734.	-1838.	-7.32	2.0827E-01	1.8104E-01			
-8.71	482.	-420.	812.	-728.	872.	-1411.	-8.71	2.1412E-01	1.8880E-01			
-8.10	318.	-277.	888.	-878.	812.	-1287.	-8.10	2.4821E-01	1.8722E-01			
-8.48	228.	-188.	388.	-810.	884.	-1184.	-8.48	2.7778E-01	1.8082E-01			
-4.88	180.	-103.	282.	-828.	488.	-1028.	-4.88	2.8821E-01	1.8288E-01			
-4.27	128.	-81.	208.	-481.	388.	-848.	-4.27	3.1887E-01	1.7828E-01			
-3.88	72.	-17.	88.	-382.	280.	-742.	-3.88	2.2888E-01	1.8048E-01			
-3.08.	-81.	188.	-188.	-188.	237.	813.	-3.08	2.4278E-01	1.8027E-01			
-4.48	-128.	188.	-288.	-238.	182.	-410.	-3.44	3.2888E-01	3.3783E-01			
-1.83.	-123.	171.	-213.	-304.	283.	-887.	-1.83	3.3288E-01	2.4841E-01			
-1.22.	-88.	118.	-187.	-383.	330.	-683.	-1.22	3.3022E-01	2.8022E-01			
-0.81.	-111.	181.	-273.	-418.	378.	-780.	-0.81	2.8820E-01	3.8108E-01			

ALGEBRAIC DIFFERENCE FOR SET 6 OBTAINED ON FEBRUARY 12 1961										DEFLECTION COMPONENTS RESOLVED INTO			
DEPTH	A SECTION		B SECTION		C SECTION		D SECTION		DEPTH	PREFERRED DEFORMATION DIRECTIONS		TRUE DEFLECTION	
	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	C1	C2		DP A IN CMS	DP R IN CMS	DP A IN CMS	DP R IN CMS
-25.82	878.	-631.	1507.	-418.	371.	-788.	-25.82	-8.5177E-03	5.1887E-02				
-25.21	784.	-708.	1472.	72.	-131.	203.	-25.21	-2.8580E-03	5.0732E-02				
-25.80	1118.	-1048.	2167.	100.	-187.	267.	-25.80	1.0385E-02	5.7678E-02				
-24.89	1388.	-1308.	2692.	-111.	38.	-147.	-24.89	1.4883E-02	5.0368E-02				
-24.38	848.	-883.	1341.	-631.	788.	-1877.	-24.38	5.2882E-02	5.1122E-02				
-23.77	480.	-436.	826.	-1012.	842.	-1854.	-23.77	7.3885E-02	1.4764E-02				
-23.18	827.	-473.	1000.	-1089.	1034.	-3122.	-23.18	7.8898E-02	5.7487E-03				
-22.88	804.	-483.	887.	-1148.	1088.	-2247.	-22.88	5.8311E-02	1.2427E-02				
-21.88	447.	-382.	828.	-1188.	1134.	-2320.	-21.88	5.8272E-02	1.8878E-02				
-21.34	317.	-288.	878.	-1213.	1148.	-2368.	-21.34	1.2808E-01	1.1781E-02				
-20.73	232.	-189.	421.	-1120.	1080.	-2170.	-20.73	1.4328E-01	3.3818E-03				
-20.12	283.	-232.	526.	-1087.	887.	-2044.	-20.12	1.5882E-01	4.4788E-03				
-18.81	188.	-117.	388.	-884.	833.	-1717.	-18.81	1.5881E-01	-5.1148E-03				
-18.80	248.	-188.	432.	-880.	782.	-1832.	-18.80	1.9131E-01	-8.2138E-03				
-18.28	247.	-288.	843.	-832.	471.	-1803.	-18.28	1.8087E-01	-5.2840E-03				
-17.88	410.	-387.	787.	-428.	387.	-783.	-17.88	1.8018E-01	-5.788E-04				
-17.07	422.	-388.	788.	-338.	387.	-802.	-17.07	1.7807E-01	3.8878E-02				
-16.48	484.	-444.	828.	-211.	138.	-380.	-16.48	1.8480E-01	5.3088E-02				
-16.88	384.	-308.	888.	-78.	8.	-84.	-16.88	1.7807E-01	3.8878E-02				
-18.24	332.	-272.	884.	-72.	17.	-88.	-18.24	1.8721E-01	1.2343E-02				
-14.83	340.	-283.	823.	-87.	7.	-74.	-14.83	1.8288E-01	5.0028E-03				
-14.02	388.	-301.	888.	-8.	88.	81.	-14.02	1.4884E-01	-8.8780E-03				
-13.41	403.	-380.	783.	80.	-118.	178.	-13.41	1.4028E-01	-2.4282E-02				
-12.80	288.	-243.	841.	-44.	-17.	-27.	-12.80	1.4870E-01	-3.8088E-02				
-12.18	147.	-89.	238.	-384.	183.	-487.	-12.18	1.8812E-01	-7.2278E-02				
-11.88	201.	-138.	340.	-384.	242.	-848.	-11.88	1.3171E-01	-8.0388E-02				
-10.87	288.	-344.	842.	-332.	270.	-802.	-10.87	1.3883E-01	-8.4890E-02				
-10.38	340.	-281.	821.	-487.	381.	-848.	-10.38	1.3880E-01	-7.7842E-02				
-8.79	427.	-387.	788.	-830.	484.	-884.	-8.79	1.3788E-01	-8.8908E-02				
-8.14	474.	-420.	884.	-888.	848.	-1148.	-8.14	1.8208E-01	-7.2447E-02				
-8.83	888.	-804.	1070.	-880.	801.	-1381.	-8.83	1.4887E-01	-5.8384E-02				
-7.82	888.	-848.	1143.	-889.	818.	-1308.	-7.82	1.7803E-01	-1.0001E-01				
-7.32	488.	-437.	828.	-804.	733.	-1837.	-7.32	2.1181E-01	-5.8148E-02				
-8.71	488.	-431.	818.	-737.	883.	-1400.	-8.71	2.2483E-01	-5.8212E-02				
-8.10	333.	-273.	888.	-873.	808.	-1282.	-8.10	2.8071E-01	-7.7088E-02				
-8.48	223.	-188.	382.	-812.	841.	-1183.	-8.48	2.8278E-01	-8.2818E-02				
-4.88	182.	-103.	288.	-838.	478.	-1013.	-4.88	3.0428E-01	-3.8818E-02				
-4.27	130.	-83.	213.	-447.	382.	-828.	-4.27	3.3282E-01	5.3412E-02				
-3.88	78.	-18.	88.	-383.	338.	-718.	-3.88	3.4804E-01	5.4442E-02				
-3.08	-43.	103.	-148.	-289.	223.	-808.	-3.08	3.8202E-01	7.4847E-02				
-2.44	-138.	188.	-314.	-233.	180.	-413.	-2.44	3.8244E-01	5.4132E-02				
-1.83	-118.	170.	-288.	-308.	248.	-887.	-1.83	3.7888E-01	1.1282E-01				
-1.22	-87.	113.	-180.	-388.	310.	-889.	-1.22	3.8288E-01	1.8823E-01				
-0.81	-118.	188.	-284.	-424.	388.	-780.	-0.81	3.1088E-01	1.7808E-01				

ALGEBRAIC DIFFERENCE FOR SET 7 OBTAINED ON FEBRUARY 17 1961										DEFLECTION COMPONENTS RESOLVED INTO			
DEPTH	A SECTION		B SECTION		C SECTION		D SECTION		DEPTH	PREFERRED DEFORMATION DIRECTIONS		TRUE DEFLECTION	
	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	C1	C2		DP A IN CMS	DP R IN CMS	DP A IN CMS	DP R IN CMS
-25.82	887.	-637.	1524.	-422.	373.	-788.	-25.82	2.0711E-02	3.8308E-02				
-25.21	778.	-711.	1489.	88.	-120.	188.	-25.21	5.2891E-02	4.2808E-02				
-25.80	1089.	-1034.	2123.	104.	-172.	278.	-25.80	-1.7784E-03	9.8428E-02				
-24.89	1384.	-1312.	2878.	-101.	23.	-124.	-24.89	2.2148E-02	9.8308E-02				
-24.38	708.	-683.	1398.	-811.	739.	-1848.	-24.38	1.0001E-01	5.8137E-02				
-23.77	488.	-436.	828.	-1014.	842.	-1858.	-23.77	1.3088E-01	5.8282E-02				
-23.18	828.	-478.	1008.	-1080.	1031.	-2121.	-23.18	1.4481E-01	5.8418E-02				
-22.88	807.	-488.	888.	-1187.	1088.	-2288.	-22.88	1.8808E-01	5.2078E-02				
-21.88	448.	-388.	834.	-1188.	1128.	-2318.	-21.88	1.8488E-01	5.8081E-02				
-21.34	322.	-287.	878.	-1218.	1144.	-2368.	-21.34	2.2444E-01	5.3881E-02				
-20.73	238.	-181.	427.	-1118.	1048.	-2188.	-20.73	2.4781E-01	4.8882E-02				
-20.12	283.	-238.	528.	-1087.	888.	-2048.	-20.12	2.7418E-01	3.8127E-02				
-18.81	187.	-118.	288.	-884.	821.	-1718.	-18.81	2.8848E-01	3.7480E-02				
-18.80	248.	-187.	432.	-882.	781.	-1832.	-18.80	2.8723E-01	3.4830E-02				
-18.28	247.	-288.	838.	-843.	478.	-1018.	-18.28	2.8178E-01	1.1078E-02				
-17.88	413.	-388.	771.	-428.	388.	-783.	-17.88	2.8781E-01	1.7800E-02				
-17.07	420.	-387.	787.	-342.	284.	-828.	-17.07	2.8284E-01	1.7288E-02				
-16.48	484.	-444.	828.	-213.	147.	-880.	-16.48	2.8381E-01	1.8380E-02				
-16.88	384.	-303.	888.	-78.	20.	-88.	-16.88	2.8487E-01	-1.8273E-02				
-18.24	334.	-271.	888.	-74.	28.	-88.	-18.24	2.7844E-01	-5.7278E-02				
-14.83	338.	-283.	822.	-72.	13.	-84.	-14.83	2.7487E-01	-7.8378E-02				
-14.02	388.	-302.	888.	-10.	-47.	37.	-14.02	2.8808E-01	-1.1238E-01				
-13.41	404.	-348.	782.	81.	-117.	188.	-13.41	2.8040E-01	-1.4788E-01				
-12.80	300.	-243.	843.	-83.	-18.	-37.	-12.80	2.8328E-01	-1.7788E-01				
-12.18	148.	-80.	238.	-288.	188.	-481.	-12.18	2.7487E-01	-2.1878E-01				
-11.88	200.	-137.	337.	-300.	241.	-841.	-11.88	2.4817E-01	-2.2788E-01				
-10.87	284.	-242.	828.	-338.	274.	-808.	-10.87	2.4248E-01	-2.4288E-01				
-10.38	338.	-278.	814.	-483.	387.	-880.	-10.38	2.3188E-01	-2.4807E-01				
-8.79	424.	-388.	780.	-848.	470.	-1018.	-8.79	2.3002E-01	-2.8884E-01				
-8.14	488.	-418.	888.	-808.	884.	-1182.	-8.14	2.3188E-01	-3.0002E-01				
-8.83	888.	-802.	1080.	-882.	801.	-1283.	-8.83	2.1887E-01	-3.8903E-01				
-7.82	882.	-840.	1122.	-880.	828.	-1318.	-7.82	2.2783E-01	-3.8438E-01				
-7.32	488.	-433.	818.	-813.	738.	-1881.	-7.32	2.8338E-01	-3.8430E-01				
-8.71	488.	-428.	818.	-733.	880.	-1383.	-8.71	2.8874E-01	-3.8072E-01				
-8.10	321.	-278.	888.	-878.	801.	-1278.	-8.10	3.0148E-01	-3.4387E-01				
-8.48	228.	-187.	382.	-810.	842.	-1182.	-8.48	3.2448E-01	-3.1777E-01				
-4.88	183.	-101.	284.	-933.	488.	-888.	-4.88	3.4220E-01	-2.8018E-01				
-4.27	132.	-82.	318.	-438.	378.	-814.	-4.27	3.7388E-01	-2.1430E-01				
-3.88	77.	-30.	87.	-388.	338.	-728.	-3.88	3.8140E-01	-1.7888E-01				
-3.08	-42.	103.	-144.	-289.	239.	-827.	-3.08	4.3888E-01	-1.8370E-01				
-2.44	-128.	188.	-312.	-238.	183.	-420.	-2.44	4.3401E-01	-1.7431E-01				
-1.83	-118.	170.	-288.	-330.	289.	-889.	-1.83	4.3408E-01	-2.0331E-01				
-1.22	-87.	108.	-188.	-388.	318.	-701.	-1.22	4.8410E-01	-1.8401E-01				
-0.81	-108.	183.	-287.	-401.	383.	-783.	-0.81	4.2878E-01	-1.2870E-01				

Figure B.40 SI7-FIELD DATA

BASIC DATA FOR COMPUTATION
THE HOLE HAS BEEN READ ON 6 OCCASIONS
CALIBRATION READINGS WERE TAKEN ON DECEMBER 22 1980
THE DEEPEST READING IN 88.00 FEET
THE SHALLOWEST READING IN 2.00 FEET
THE CLAMP RISES 2.00 FEET ABOVE GROUND
THE ANGLE BETWEEN THE "A" AXIS
AND THE AXIS OF PRINCIPAL
DEFORMATION IS 2.22 DEGREES

ALGEBRAIC DIFFERENCE IN CALIBRATION READINGS						
DEPTH	A DIRECTION			B DIRECTION		
	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B
-28.82	828	-448	872	-127	82	-180
-28.21	228	-170	288	-881	488	-1018
-28.80	282	-288	882	-828	888	-1228
-24.88	288	-224	708	-478	412	-882
-24.28	882	-820	1812	-148	88	-202
-23.77	888	-822	1810	-218	128	-284
-22.18	872	-820	1882	-188	120	-218
-22.88	878	-820	1888	-181	81	-242
-21.88	888	-801	1880	-224	180	-284
-21.24	1184	-1077	2241	-248	288	-818
-20.73	1378	-1221	2808	-287	227	-824
-20.12	1073	-1021	2084	-212	248	-882
-18.81	1012	-880	1882	-272	188	-470
-18.80	888	-822	1707	-174	82	-288
-18.28	800	-842	1742	222	-404	728
-17.88	1378	-1228	2708	882	-780	1422
-17.07	1880	-1821	2201	324	-410	724
-16.48	1328	-1288	2814	-12	-72	88
-16.88	1281	-1227	2828	24	-80	114
-18.24	1084	-1024	2088	-117	28	-182
-18.82	880	-822	1702	-288	187	-482
-18.02	827	-788	1888	-288	220	-828
-12.41	807	-747	1884	-288	280	-848
-12.80	802	-747	1880	-478	408	-881
-12.18	884	-888	1242	-808	481	-880
-11.88	888	-802	1087	-248	288	-818
-10.87	840	-480	1020	-222	180	-282
-10.28	827	-888	1182	-288	218	-718
-8.78	828	-872	1208	-482	280	-842
-8.14	840	-874	1014	-416	222	-748
-8.82	884	-827	1121	-407	224	-741
-7.82	822	-874	1188	-474	284	-888
-7.22	880	-822	1102	-421	287	-788
-8.71	828	-888	1181	-218	248	-884
-8.10	882	-482	1044	-127	82	-180
-8.48	822	-478	1011	-22	-42	10
-4.88	448	-280	828	18	-87	108
-4.27	228	-270	808	88	-128	200
-2.88	287	-228	822	-102	-187	270
-2.08	280	-228	828	114	-180	204
-2.44	272	-218	488	82	-188	281
-1.82	220	-171	401	148	-218	282
-1.22	202	-144	248	188	-244	412
-0.81	84	-24	118	208	-280	488

Figure B.41 SI12-FIELD DATA

ALGEBRAIC DIFFERENCE FOR SET 2 OBTAINED ON FEBRUARY 01 1961										DEFLECTION COMPONENTS RESOLVED INTO									
A DIRECTION					B DIRECTION					PREFERRED DEFORMATION DIRECTIONS					TRUE DEFLECTION				
DEPTH	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	DEPTH	IN MS.	TRUE DEFLECTION OF A IN CMS	DEPTH	IN MS.	TRUE DEFLECTION OF B IN CMS	DEPTH	IN MS.	TRUE DEFLECTION OF R IN CMS				
-26.62	624	-466	550	-126	52	-167	-26.62	2	9319E-02	-9.5105E-03	-26.62	2	9319E-02	-9.5105E-03	-26.62	2	9319E-02		
-26.21	230	-177	407	-662	467	-1006	-26.21	3	6099E-02	1.6423E-03	-26.21	3	6099E-02	1.6423E-03	-26.21	3	6099E-02		
-26.60	366	-306	664	-661	660	-1231	-26.60	4	1494E-02	-7.4709E-03	-26.60	4	1494E-02	-7.4709E-03	-26.60	4	1494E-02		
-24.56	664	-647	666	-476	414	-560	-24.56	2	6134E-02	-6.0422E-03	-24.56	2	6134E-02	-6.0422E-03	-24.56	2	6134E-02		
-23.77	667	-630	1641	-131	61	-162	-23.77	6	5915E-02	1.3467E-02	-23.77	6	5915E-02	1.3467E-02	-23.77	6	5915E-02		
-23.16	673	-622	1666	-210	136	-346	-23.16	7	6715E-02	2.7634E-02	-23.16	7	6715E-02	2.7634E-02	-23.16	7	6715E-02		
-22.66	676	-626	1900	-163	76	-231	-22.66	6	2024E-02	4.8030E-02	-22.66	6	2024E-02	4.8030E-02	-22.66	6	2024E-02		
-21.66	666	-601	1660	-221	182	-374	-21.66	5	7436E-02	6.3927E-02	-21.66	5	7436E-02	6.3927E-02	-21.66	5	7436E-02		
-21.36	1161	-1100	2291	-336	366	-607	-21.36	6	6202E-02	6.3462E-02	-21.36	6	6202E-02	6.3462E-02	-21.36	6	6202E-02		
-20.72	1277	-1220	2607	-266	211	-600	-20.72	1	1699E-01	1.1147E-01	-20.72	1	1699E-01	1.1147E-01	-20.72	1	1699E-01		
-20.12	1073	-1026	2101	-306	242	-660	-20.12	1	1802E-01	1.4807E-01	-20.12	1	1802E-01	1.4807E-01	-20.12	1	1802E-01		
-19.61	1012	-660	1672	-267	167	-494	-19.61	1	2664E-01	1.9676E-01	-19.61	1	2664E-01	1.9676E-01	-19.61	1	2664E-01		
-19.50	666	-636	1720	-166	66	-266	-19.50	1	4090E-01	1.7663E-01	-19.50	1	4090E-01	1.7663E-01	-19.50	1	4090E-01		
-17.66	1374	-1326	2702	-666	761	-1446	-17.66	1	6069E-01	1.7733E-01	-17.66	1	6069E-01	1.7733E-01	-17.66	1	6069E-01		
-17.07	1667	-1620	2267	-316	421	-737	-17.07	1	6139E-01	1.7649E-01	-17.07	1	6139E-01	1.7649E-01	-17.07	1	6139E-01		
-16.46	1329	-1276	2907	-6	-72	67	-16.46	1	4121E-01	2.0400E-01	-16.46	1	4121E-01	2.0400E-01	-16.46	1	4121E-01		
-16.66	1260	-1246	2636	-40	-66	126	-16.66	1	3493E-01	2.0632E-01	-16.66	1	3493E-01	2.0632E-01	-16.66	1	3493E-01		
-16.24	1067	-1016	2063	-116	34	-160	-16.24	1	2379E-01	2.2009E-01	-16.24	1	2379E-01	2.2009E-01	-16.24	1	2379E-01		
-14.63	694	-634	1716	-1906	170	-414	-14.63	1	3370E-01	2.3976E-01	-14.63	1	3370E-01	2.3976E-01	-14.63	1	3370E-01		
-14.02	631	-777	1664	-260	226	-619	-14.02	1	2666E-01	2.4162E-01	-14.02	1	2666E-01	2.4162E-01	-14.02	1	2666E-01		
-12.41	606	-766	1664	-346	261	-626	-12.41	1	4709E-01	2.6609E-01	-12.41	1	4709E-01	2.6609E-01	-12.41	1	4709E-01		
-12.60	601	-769	1667	-466	406	-674	-12.60	1	6644E-01	3.3099E-01	-12.60	1	6644E-01	3.3099E-01	-12.60	1	6644E-01		
-12.16	647	-662	1236	-607	462	-669	-12.16	1	6031E-01	3.4176E-01	-12.16	1	6031E-01	3.4176E-01	-12.16	1	6031E-01		
-11.66	666	-606	1072	-321	266	-666	-11.66	1	6064E-01	3.4303E-01	-11.66	1	6064E-01	3.4303E-01	-11.66	1	6064E-01		
-10.67	639	-467	1072	-226	162	-367	-10.67	1	6021E-01	3.6646E-01	-10.67	1	6021E-01	3.6646E-01	-10.67	1	6021E-01		
-10.36	626	-673	1166	-363	316	-706	-10.36	1	6441E-01	3.6661E-01	-10.36	1	6441E-01	3.6661E-01	-10.36	1	6441E-01		
-9.76	636	-663	1216	-461	361	-642	-9.76	2	0311E-01	4.0794E-01	-9.76	2	0311E-01	4.0794E-01	-9.76	2	0311E-01		
-9.16	641	-660	1021	-406	331	-740	-9.16	2	1629E-01	4.0869E-01	-9.16	2	1629E-01	4.0869E-01	-9.16	2	1629E-01		
-8.63	669	-641	1140	-403	336	-736	-8.63	2	2697E-01	4.1666E-01	-8.63	2	2697E-01	4.1666E-01	-8.63	2	2697E-01		
-7.62	629	-662	1210	-466	364	-666	-7.62	2	4209E-01	4.2469E-01	-7.62	2	4209E-01	4.2469E-01	-7.62	2	4209E-01		
-7.32	679	-626	1107	-426	366	-793	-7.32	2	6299E-01	4.3924E-01	-7.32	2	6299E-01	4.3924E-01	-7.32	2	6299E-01		
-6.71	626	-671	1166	-316	247	-662	-6.71	2	6693E-01	4.4710E-01	-6.71	2	6693E-01	4.4710E-01	-6.71	2	6693E-01		
-6.10	663	-496	1049	-126	46	-173	-6.10	2	7612E-01	4.6049E-01	-6.10	2	7612E-01	4.6049E-01	-6.10	2	7612E-01		
-5.46	631	-499	1017	-26	-44	16	-5.46	2	6331E-01	4.9143E-01	-5.46	2	6331E-01	4.9143E-01	-5.46	2	6331E-01		
-4.66	441	-397	926	20	-67	107	-4.66	2	9441E-01	4.7063E-01	-4.66	2	9441E-01	4.7063E-01	-4.66	2	9441E-01		
-4.27	322	-274	666	72	-136	209	-4.27	2	9666E-01	4.7410E-01	-4.27	2	9666E-01	4.7410E-01	-4.27	2	9666E-01		
-3.66	264	-236	623	104	-170	274	-3.66	2	6090E-01	4.6673E-01	-3.66	2	6090E-01	4.6673E-01	-3.66	2	6090E-01		
-3.06	266	-243	641	116	-163	312	-3.06	2	2697E-01	4.9162E-01	-3.06	2	2697E-01	4.9162E-01	-3.06	2	2697E-01		
-2.44	272	-222	464	66	-169	269	-2.44	2	9310E-01	6.0413E-01	-2.44	2	9310E-01	6.0413E-01	-2.44	2	9310E-01		
-1.63	223	-179	406	146	-223	372	-1.63	2	6169E-01	6.1099E-01	-1.63	2	6169E-01	6.1099E-01	-1.63	2	6169E-01		
-1.22	200	-149	346	174	-244	419	-1.22	3	0209E-01	6.2472E-01	-1.22	3	0209E-01	6.2472E-01	-1.22	3	0209E-01		
-0.61	69	-26	61	210	-260	460	-0.61	2	0493E-01	6.2244E-01	-0.61	2	0493E-01	6.2244E-01	-0.61	2	0493E-01		

ALGEBRAIC DIFFERENCE FOR SET 3 OBTAINED ON FEBRUARY 06 1961										DEFLECTION COMPONENTS RESOLVED INTO									
S DIRECTION					S DIRECTION					PREFERRED DEFORMATION DIRECTIONS									
DEPTH	A1	A2	DIFFERENCE IN A	B1	B2	DIFFERENCE IN B	DEPTH	IN MS	TRUE DEFLECTION OF A IN CMS	DEPTH	IN MS	TRUE DEFLECTION OF B IN CMS	DEPTH	IN MS	TRUE DEFLECTION OF B IN CMS				
-26.62	616	-460	976	-131	61	-162	-26.62	4	6619E-03	-2	6604E-03								
-26.21	232	-177	406	-636	472	-1006	-26.21	1	9426E-02	6	9399E-03								
-26.60	363	-304	667	-647	663	-1230	-26.60	1	2120E-02	2	0163E-03								
-24.66	366	-330	666	-490	414	-604	-24.66	-3	6699E-03	-1	6636E-02								
-24.39	669	-632	1621	-127	66	-162	-24.39	6	1366E-02	3	7016E-04								
-23.77	660	-631	1621	-204	130	-334	-23.77	2	4693E-02	3	1604E-02								
-23.16	674	-622	1666	-166	116	-302	-23.16	2	9172E-02	9	7679E-02								
-22.66	677	-629	1909	-146	79	-226	-22.66	4	0929E-02	6	4016E-02								
-21.66	690	-603	1663	-220	167	-367	-21.66	4	4666E-02	6	4692E-02								
-21.36	1166	-1101	2297	-327	266	-602	-21.36	6	6342E-02	1	2021E-01								
-20.72	1264	-1221	2616	-261	221	-612	-20.72	6	1309E-02	1	3904E-01								
-20.12	1079	-1029	2106	-306	236	-643	-20.12	6	6407E-02	1	6671E-01								
-19.61	1014	-661	1676	-290	166	-496	-19.61	1	1749E-01	1	9776E-01								
-19.60	696	-638	1723	-161	63	-26	-19.60	1	4109E-01	2	0799E-01								
-19.26	661	-626	1734	-217	61	-16	-19.26	1	2696E-01	1	690E-01								
-17.66	1377	-1332	2709	-666	-766	1664	-17.66	1	1973E-01	2	2337E-01								
-17.07	1664	-1626	2313	-342	-413	766	-17.07	1	4673E-01	2	6606E-01								
-16.49	1343	-1261	2624	1	-73	74	-16.49	1	6103E-01	2	7949E-01								
-16.66	1260	-1246	2639	36	-100	136	-16.66	1	7496E-01	3	1214E-01								
-16.24	1066	-1026	2116	-104	30	-134	-16.24	2	1466E-01	3	4121E-01								
-14.63	667	-641	1726	-244	174	-419	-14.63	2	6196E-01	3	7930E-01								
-14.02	632	-790	1612	-299	227	-616	-14.02	2	7669E-01	3	6409E-01								
-13.41	609	-767	1666	-390	266	-636	-13.41	2	3009E-01	4	0644E-01								
-12.60	604	-766	1660	-469	406	-671	-12.60	3	6796E-01	4	2429E-01								
-12.19	669	-666	1644	-604	604	-661	-12.16	3	0276E-01	2	2929E-01								
-11.66	666	-607	1072	-330	292	-662	-11.66	3	1626E-01	4	6272E-01								
-10.67	634	-467	1021	-229	166	-396	-10.67	3	1660E-01	4	7040E-01								
-10.39	627	-676	1202	-396	320	-709	-10.39	3	3129E-01	4	6167E-01								
-6.76	636	-666	1222	-449	260	-639	-6.76	3	6236E-01	4	6993E-01								
-9.14	644	-462	1029	-406	333	-736	-9.14	3	7014E-01	6	0199E-01								
-6.63	662	-641	1133	-403	333	-739	-6.63	3	7266E-01	6	0929E-01								
-7.92	661	-666	1217	-464	262	-666	-7.92	4	0412E-01	9	2699E-01								
-7.32	661	-630	1111	-427	367	-764	-7.32	4	1909E-01	6	3644E-01								
-6.71	626	-671	1166	-703	240	-643	-6.71	4	2237E-01	6	6773E-01								
-6.10	663	-466	1061	-106	44	-162	-6.10	4	3130E-01	6	1080E-01								
-6.66	631	-467	1019	-74	-40	16	-6.66	4	4166E-01	6	2039E-01								
-4.66	446	-364	626	20	-61	111	-4.66	4	4676E-01	6	2666E-01								
-4.27	226	-274	666	72	-140	212	-4.27	4	2666E-01	6	4766E-01								
-3.66	263	-236	616	106	-162	276	-3.66	4	2761E-01	6	6949E-01								
-2.06	300	-346	646	120	-162	312	-2.06	4	3797E-01	6	7209E-01								
-2.44	266	-216	466	66	-170	269	-2.44	4	3764E-01	6	6274E-01								
-1.62	232	-176	410	149	-226	376	-1.62	4	6044E-01	7	0309E-01								
-1.22	166	-149	249	172	-244	419	-1.22	4	6029E-01	7	0769E-01								
-0.61	71	-21	62	206	-276	466	-0.61	4	1076E-01	7	0301E-01								

ALGEBRAIC DIFFERENCES FOR SET 4 OBTAINED ON FEBRUARY 05 1951							DEFLECTION COMPONENTS RESOLVED INTO		
DEPTH IN MS	S DIRECTION			B DIRECTION			PREFERRED DEFLECTION DIRECTIONS		TRUE DEFLECTION OF S IN CMS
	S1	S2	DIFFERENCE IN S	B1	B2	DIFFERENCE IN B	TRUE DEFLECTION OF A IN CMS	TRUE DEFLECTION OF S IN CMS	
-28.52	523	-478	885	-134	51	-185	3.5377E-02	-8.0714E-03	
-28.21	232	-178	408	-848	470	-1015	5.3257E-02	-1.0084E-02	
-28.80	284	-305	585	-854	888	-1222	4.7814E-02	-5.7013E-03	
-24.58	372	-328	700	-451	417	-804	3.4785E-02	-3.0821E-02	
-24.38	878	-828	1507	-142	83	-208	2.7308E-02	-3.3874E-02	
-23.77	880	-827	1517	-211	133	-344	3.7348E-02	-1.8318E-02	
-23.18	873	-815	1581	-188	114	-303	3.2318E-02	8.8288E-03	
-22.58	878	-825	1504	-153	77	-230	4.4787E-02	2.4882E-02	
-21.88	881	-801	1582	-237	154	-381	4.7815E-02	2.8384E-02	
-21.34	1148	-1050	2228	-343	384	-807	4.3853E-02	4.8011E-02	
-20.73	1258	-1220	2818	-250	215	-805	8.1178E-02	7.1118E-02	
-20.12	1077	-1030	2107	-305	244	-852	8.0385E-02	5.7144E-02	
-18.51	1817	-881	1578	-352	153	-488	1.0380E-01	1.1087E-01	
-18.80	880	-834	1724	-183	84	-287	1.2813E-01	1.2873E-01	
-18.28	880	-837	1727	310	-384	884	1.0828E-01	7.8073E-02	
-17.88	1345	-1308	3858	881	-784	1455	2.7885E-02	1.0788E-01	
-17.07	1555	-1525	3311	345	-415	781	4.1221E-02	1.4882E-01	
-18.48	1348	-1277	2828	1	-88	70	5.4818E-02	1.8711E-01	
-18.88	1287	-1283	2820	30	-88	128	8.1121E-02	1.8881E-01	
-18.24	1084	-1023	2127	-100	32	-132	1.1827E-01	2.1527E-01	
-14.83	881	-838	1728	-245	178	-422	1.8783E-01	2.8043E-01	
-14.02	535	-777	1512	-282	220	-623	1.8338E-01	2.6482E-01	
-13.41	808	-755	1584	-383	262	-625	1.8783E-01	2.7483E-01	
-12.80	803	-783	1588	-488	408	-872	2.0840E-01	2.8801E-01	
-12.18	883	-803	1288	-908	448	-888	2.4112E-01	2.8804E-01	
-11.58	887	-808	1072	-338	272	-811	2.4830E-01	3.0801E-01	
-10.87	538	-484	1018	-232	184	-388	2.4888E-01	3.0438E-01	
-10.38	824	-871	1188	-388	320	-718	2.8171E-01	3.0900E-01	
-8.78	838	-850	1215	-481	282	-853	2.8842E-01	3.0888E-01	
-8.14	845	-851	1027	-487	324	-741	2.8481E-01	3.0888E-01	
-8.53	853	-828	1132	-403	338	-735	2.8824E-01	3.1280E-01	
-7.82	838	-854	1220	-487	281	-888	3.2217E-01	3.3030E-01	
-7.32	880	-828	1108	-430	387	-787	3.2872E-01	3.3214E-01	
-6.71	828	-888	1187	-313	282	-888	3.3882E-01	3.3088E-01	
-6.10	888	-487	1088	-121	48	-188	3.5488E-01	3.4841E-01	
-5.48	828	-488	1021	-30	-47	17	3.8878E-01	3.8888E-01	
-4.88	448	-380	828	18	-82	111	3.8788E-01	3.8888E-01	
-4.27	330	-278	808	83	-162	208	3.8738E-01	3.8888E-01	
-3.88	284	-233	817	102	-175	188	3.7788E-01	3.8888E-01	
-3.08	384	-248	848	115	-182	310	3.8215E-01	3.8874E-01	
-2.44	272	-215	480	55	-170	288	3.8841E-01	4.0488E-01	
-1.83	232	-178	407	150	-228	378	4.0382E-01	4.2817E-01	
-1.22	203	-148	381	173	-242	418	4.1111E-01	4.3182E-01	
-0.81	75	-28	107	308	-278	488	3.8448E-01	4.2780E-01	

ALGEBRAIC DIFFERENCES FOR SET 5 OBTAINED ON FEBRUARY 05 1951							DEFLECTION COMPONENTS RESOLVED INTO		
DEPTH IN MS	S DIRECTION			B DIRECTION			PREFERRED DEFLECTION DIRECTIONS		TRUE DEFLECTION OF S IN CMS
	S1	S2	DIFFERENCE IN S	B1	B2	DIFFERENCE IN B	TRUE DEFLECTION OF A IN CMS	TRUE DEFLECTION OF S IN CMS	
-28.52	528	-482	887	-131	58	-188	2.1874E-02	-1.2841E-02	
-28.21	237	-188	408	-838	458	-1002	3.1885E-02	-5.8083E-03	
-28.80	388	-300	888	-848	888	-1231	2.8130E-02	1.8888E-08	
-24.58	378	-320	888	-481	428	-810	1.7822E-02	-2.8284E-02	
-24.38	884	-831	1518	-120	71	-201	2.2387E-02	-2.8023E-02	
-23.77	883	-820	1513	-208	138	-343	2.8287E-02	-8.0877E-03	
-23.18	878	-814	1582	-184	121	-208	2.3870E-02	1.3188E-02	
-22.58	883	-815	1582	-148	81	-228	3.2020E-02	3.7802E-02	
-21.88	888	-881	1585	-213	171	-384	2.8312E-02	8.2884E-02	
-21.34	1188	-1088	2242	-340	288	-808	2.8218E-02	8.8173E-02	
-20.73	1281	-1220	2811	-288	238	-814	3.3218E-02	8.3708E-02	
-20.12	1082	-1021	2102	-302	243	-848	4.8871E-02	1.1018E-01	
-18.51	1018	-883	1572	-287	184	-481	8.8858E-02	1.3870E-01	
-18.80	883	-828	1718	-188	103	-288	7.8244E-02	1.8104E-01	
-18.28	883	-828	1721	318	-384	700	4.8871E-02	1.1018E-01	
-17.88	1381	-1305	2888	887	-782	1455	-1.8781E-02	1.4887E-01	
-17.07	1888	-1822	2311	344	-413	787	-8.8420E-03	1.8431E-01	
-18.48	1348	-1278	2823	-2	-88	88	7.8478E-03	1.8030E-01	
-18.88	1283	-1238	2828	38	-81	128	8.8482E-03	2.0320E-01	
-18.24	1084	-1023	2108	-102	28	-128	3.7820E-02	2.4088E-01	
-14.83	887	-833	1730	-244	180	-424	7.7823E-02	2.7008E-01	
-14.02	841	-770	1511	-388	238	-628	1.0188E-01	2.7108E-01	
-13.41	813	-748	1581	-381	287	-628	1.1183E-01	2.8871E-01	
-12.80	808	-745	1582	-482	415	-878	1.1831E-01	2.8148E-01	
-12.18	881	-888	1288	-488	487	-882	1.4018E-01	3.0483E-01	
-11.58	874	-800	1074	-328	288	-882	1.4824E-01	3.4888E-01	
-10.87	538	-478	1014	-220	188	-388	1.3878E-01	3.8180E-01	
-10.38	827	-880	1187	-288	328	-720	1.3304E-01	3.3027E-01	
-8.78	840	-873	1213	-447	400	-847	1.3838E-01	3.2442E-01	
-8.14	880	-875	1025	-602	335	-727	1.8888E-01	3.2881E-01	
-8.53	887	-830	1127	-387	237	-734	1.4808E-01	3.4822E-01	
-7.82	840	-878	1218	-481	388	-888	1.7888E-01	3.8418E-01	
-7.32	883	-821	1104	-428	353	-788	1.7888E-01	3.7848E-01	
-6.71	833	-888	1188	-313	248	-881	1.8033E-01	3.8448E-01	
-6.10	884	-483	1087	-114	47	-181	2.0888E-01	4.1418E-01	
-5.48	840	-480	1020	-28	-48	23	2.2188E-01	4.3482E-01	
-4.88	483	-383	838	21	-88	107	2.3888E-01	4.2808E-01	
-4.27	338	-272	807	74	-138	210	2.3888E-01	4.8388E-01	
-3.88	280	-228	818	107	-172	278	2.3278E-01	4.8700E-01	
-3.08	307	-241	848	123	-188	212	2.4888E-01	4.7848E-01	
-2.44	278	-210	488	108	-187	275	2.4083E-01	8.0087E-01	
-1.83	238	-185	408	181	-222	373	2.4800E-01	8.1838E-01	
-1.22	208	-144	352	172	-243	418	2.8801E-01	8.1878E-01	
-0.81	81	-27	108	220	-258	508	2.3874E-01	8.4803E-01	

Figure B.43 SI12-FIELD DATA

ALGEBRAIC DIFFERENCE FOR SET A OBTAINED ON FEBRUARY 19 1961										DEFLECTION COMPONENTS RESOLVED INTO			
A DIRECTION					B DIRECTION					PREFERRED DEFORMATION DIRECTIONS			
DEPTH	A1	A3	DIFFERENCE 10 A	B1	B2	DIFFERENCE 10 B	DEPTH 10 MS.	TRUE DEFLECTION OF A 1R CMs	TRUE DEFLECTION OF B 1R CMs	TRUE DEFLECTION OF A 1R CMs	TRUE DEFLECTION OF B 1R CMs	TRUE DEFLECTION OF A 1R CMs	TRUE DEFLECTION OF B 1R CMs
-38.82	813.	-481.	573	-183	83.	-188.	-38.83	8 3838E-04	-3 3841E-02	-3 3841E-02	-3 3841E-02	-3 3841E-02	-3 3841E-02
-38.31	338	-171.	388	-883	483.	-1018.	-38.31	8 3838E-04	-3 3841E-02	-3 3841E-02	-3 3841E-02	-3 3841E-02	-3 3841E-02
-38.80	388	-388.	883.	-888	888.	-1331.	-38.80	-1.3028E-02	-1 7308E-02	-1 7308E-02	-1 7308E-02	-1 7308E-02	-1 7308E-02
-34.88	388	-331	880.	-483	420.	-803.	-34.88	-4.1280E-02	-3 8228E-03	-3 8228E-03	-3 8228E-03	-3 8228E-03	-3 8228E-03
-34.38	888	-828	1817.	-138.	70.	-208.	-34.38	-3.3888E-03	-4.2833E-02	-4.2833E-02	-4.2833E-02	-4.2833E-02	-4.2833E-02
-33.77	884	-833	1807.	-330.	138	-388.	-33.77	-3 7817E-02	-8.0332E-03	-8.0332E-03	-8.0332E-03	-8.0332E-03	-8.0332E-03
-33.18	888	-814.	1883.	-188.	130	-318	-33.18	-8 4388E-02	-8 1011E-02	-8 1011E-02	-8 1011E-02	-8 1011E-02	-8 1011E-02
-33.88	874	-818.	1883.	-183	83.	-348.	-33.88	-8 8888E-02	-8 7387E-03	-8 7387E-03	-8 7387E-03	-8 7387E-03	-8 7387E-03
-31.88	887	-884.	1881.	-338	178	-410.	-31.88	-7 1407E-02	-8 3388E-02	-8 3388E-02	-8 3388E-02	-8 3388E-02	-8 3388E-02
-31.34	1148	-1081	2240.	-383	370.	-823	-31.34	-7 2883E-02	-1 0387E-01	-1 0387E-01	-1 0387E-01	-1 0387E-01	-1 0387E-01
-30.73	1374	-1218	2483	-303	330.	-833	-30.73	-8 1833E-02	-8 7083E-02	-8 7083E-02	-8 7083E-02	-8 7083E-02	-8 7083E-02
-30.12	1070	-1018	3088.	-317.	341.	-888	-30.12	-8 8784E-02	-8 0830E-02	-8 0830E-02	-8 0830E-02	-8 0830E-02	-8 0830E-02
-18.81	1808	-884	1883	-373.	184	-488.	-18.81	-8 8808E-02	-8 7381E-02	-8 7381E-02	-8 7381E-02	-8 7381E-02	-8 7381E-02
-18.80	888	-830	1718	-170.	84.	-384.	-18.80	-8 8448E-02	-1.3238E-01	-1.3238E-01	-1.3238E-01	-1.3238E-01	-1.3238E-01
-18.28	883	-837.	1738.	318.	-381	887.	-18.28	-1.0488E-01	-1.3848E-01	-1.3848E-01	-1.3848E-01	-1.3848E-01	-1.3848E-01
-17.88	1387	-1318.	2883.	874.	-787	1431.	-17.88	-1 4388E-01	-1 4837E-01	-1 4837E-01	-1 4837E-01	-1 4837E-01	-1 4837E-01
-17.07	1878.	-1830	3288.	318.	-808.	728.	-17.07	-1 4800E-01	-1 8878E-01	-1 8878E-01	-1 8878E-01	-1 8878E-01	-1 8878E-01
-18.48	1340	-1277	2817	-33.	-88	33.	-18.48	-1 4183E-01	-1.8883E-01	-1.8883E-01	-1.8883E-01	-1.8883E-01	-1.8883E-01
-18.88	1280	-1342	3832	18.	-88	114.	-18.88	-1 3874E-01	-1 8314E-01	-1 8314E-01	-1 8314E-01	-1 8314E-01	-1 8314E-01
-18.24	1083	-1028	2113	-130.	38.	-188.	-18.24	-8 8843E-02	-1 7843E-01	-1 7843E-01	-1 7843E-01	-1 7843E-01	-1 7843E-01
-14.83	881.	-838	1737.	-248	183	-832	-14.83	-8 3014E-03	-1 8283E-01	-1 8283E-01	-1 8283E-01	-1 8283E-01	-1 8283E-01
-14.03	838	-780	1818.	-388.	331	-830	-14.03	-3 7882E-02	-1 8283E-01	-1 8283E-01	-1 8283E-01	-1 8283E-01	-1 8283E-01
-13.41	807	-782	1888	-381	283.	-883	-13.41	-1 8780E-02	-1 8883E-01	-1 8883E-01	-1 8883E-01	-1 8883E-01	-1 8883E-01
-12.80	803.	-781	1884.	-473	417	-880	-12.80	-1 3113E-02	-2 0338E-01	-2 0338E-01	-2 0338E-01	-2 0338E-01	-2 0338E-01
-13.18	880	-887	1347	-813.	452.	-884	-13.18	-8 7787E-03	-2 0823E-01	-2 0823E-01	-2 0823E-01	-2 0823E-01	-2 0823E-01
-11.88	884	-801	1088	-338	380	-888	-11.88	-1.1088E-02	-1.7880E-01	-1.7880E-01	-1.7880E-01	-1.7880E-01	-1.7880E-01
-10.87	838	-878	1008.	-331	188	-388	-10.87	-3 3828E-02	-1 8888E-01	-1 8888E-01	-1 8888E-01	-1 8888E-01	-1 8888E-01
-10.38	818	-881	1177	-404	334	-738	-10.38	-8 8010E-02	-2 2338E-01	-2 2338E-01	-2 2338E-01	-2 2338E-01	-2 2338E-01
-8.78	833	-888	1187	-488.	387	-883	-8.78	-4 7884E-02	-2 3887E-01	-2 3887E-01	-2 3887E-01	-2 3887E-01	-2 3887E-01
-8.14	838	-884	883	-613	338.	-748.	-8.14	-1 3127E-01	-3 4438E-01	-3 4438E-01	-3 4438E-01	-3 4438E-01	-3 4438E-01
-8.83	884	-828	1108	-408	333	-738	-8.83	-1.8488E-01	-2 4288E-01	-2 4288E-01	-2 4288E-01	-2 4288E-01	-2 4288E-01
-7.82	830	-878	1208	-473.	384	-887	-7.82	-1.3888E-01	-3 4043E-01	-3 4043E-01	-3 4043E-01	-3 4043E-01	-3 4043E-01
-7.33	878	-823	1088	-433	388	-801.	-7.33	-1 4288E-01	-2 4824E-01	-2 4824E-01	-2 4824E-01	-2 4824E-01	-2 4824E-01
-8.71	824	-887.	1181	-318	344.	-883	-8.71	-1 4288E-01	-2 4372E-01	-2 4372E-01	-2 4372E-01	-2 4372E-01	-2 4372E-01
-8.10	887	-888	1083	-120.	43.	-183	-8.10	-1 3888E-01	-2 1728E-01	-2 1728E-01	-2 1728E-01	-2 1728E-01	-2 1728E-01
-8.48	838	-888	1021	-38.	-44	8	-8.48	-1 1482E-01	-3 3778E-01	-3 3778E-01	-3 3778E-01	-3 3778E-01	-3 3778E-01
-4.88	448	-388	837	14	-83	88	-4.88	-8 7218E-02	-2 3878E-01	-2 3878E-01	-2 3878E-01	-2 3878E-01	-2 3878E-01
-4.37	330	-373	803	84	-138	188	-4.37	-1 0172E-01	-2 3748E-01	-2 3748E-01	-2 3748E-01	-2 3748E-01	-2 3748E-01
-3.88	387	-334	831	101	-170	271	-3.88	-1.0483E-01	-2 3808E-01	-2 3808E-01	-2 3808E-01	-2 3808E-01	-2 3808E-01
-3.08	308	-248	880	113	-187.	300	-3.08	-8 7832E-02	-2 4180E-01	-2 4180E-01	-2 4180E-01	-2 4180E-01	-2 4180E-01
-3.44	373	-318.	480	80.	-188	288	-3.44	-8 4883E-02	-2 4442E-01	-2 4442E-01	-2 4442E-01	-2 4442E-01	-2 4442E-01
-1.83	232	-178	408	147	-321	388	-1.83	-7 4312E-02	-2 3837E-01	-2 3837E-01	-2 3837E-01	-2 3837E-01	-2 3837E-01
-1.32	304	-147	381	188	-238	407	-1.32	-8 8328E-02	-2 4820E-01	-2 4820E-01	-2 4820E-01	-2 4820E-01	-2 4820E-01
-8.81	83	-38	111	223.	-288.	811.	-8.81	-7 8407E-02	-2 1081E-01	-2 1081E-01	-2 1081E-01	-2 1081E-01	-2 1081E-01

Figure B.44 SI12-FIELD DATA

C. APPENDIX - LINING INSTRUMENTS - FIELD DATA

LOAD CELL #5			
LOAD(N)	$\Delta \varepsilon$		
	(1)	(2)	(3)
0	0	0	0
100,000	145	257	202
200,000	273	404	379
300,000	423	546	537
400,000	583	709	710
500,000	750	870	881
600,000	928	1043	202
700,000	1113	1214	1219
600,000	932	1031	1039
500,000	754	850	858
400,000	580	667	680
300,000	409	492	500
200,000	249	325	325
100,000	120	187	171
0	0	0	0

LOAD CELL #3			
	$\Delta \varepsilon$		
	(1)	(2)	(3)
0	0	0	0
100,000	200	256	237
200,000	364	414	413
300,000	518	563	578
400,000	673	722	748
500,000	822	885	912
600,000	974	1052	1073
700,000	1118	1212	1198
600,000	956	1045	1066
500,000	798	877	902
400,000	638	708	734
300,000	483	535	566
200,000	431	386	401
100,000	179	226	231
0	4	-6	12

$\Delta \varepsilon$ is the sum of channels A and B.

TABLE C1 - LOAD CELLS #3 AND #5 - CALIBRATION

LOAD CELL #1			
$\Delta \epsilon$			
LOAD(N)	(1)	(2)	(3)
0	0	0	0
100,000	185	209	232
200,000	335	364	406
300,000	447	522	571
400,000	620	686	733
500,000	768	849	887
600,000	918	997	1029
700,000	1074	1156	1147
600,000	919	1990	1020
500,000	762	829	858
400,000	607	660	706
300,000	453	505	540
200,000	305	336	369
100,000	163	176	200
0	8	0	11

LOAD CELL #4			
$\Delta \epsilon$			
0	0	0	0
100,000	115	161	158
200,000	250	299	330
300,000	401	458	504
400,000	563	622	681
500,000	735	797	846
600,000	907	970	1016
700,000	1083	1140	1152
600,000	906	963	1008
500,000	737	782	833
400,000	564	607	652
300,000	400	424	476
200,000	250	265	300
100,000	113	130	140
0	5	0	7

$\Delta \epsilon$ is the sum of channels A and B.

TABLE C2 - LOAD CELLS #1 AND #4 - CALIBRATION

LOAD CELL #2			
$\Delta \epsilon$			
LOAD (N)	(1)	(2)	(3)
0	0	0	0
100,000	202	246	240
200,000	356	369	407
300,000	506	500	576
400,000	668	646	748
500,000	824	812	924
600,000	981	979	1097
700,000	1142	1149	1227
600,000	978	971	1087
500,000	811	794	904
400,000	645	619	725
300,000	477	451	541
200,000	314	295	364
100,000	153	164	188
0	-1	0	-1

LOAD CELL #7			
$\Delta \epsilon$			
0	0	0	0
100,000	156	170	191
200,000	301	283	367
300,000	460	423	537
400,000	613	574	705
500,000	781	738	872
600,000	891	908	1036
700,000	1107	1082	1169
600,000	942	909	1016
500,000	770	734	848
400,000	599	565	671
300,000	439	398	500
200,000	274	244	326
100,000	120	115	155
0	5	9	2

$\Delta \epsilon$ is the sum of channels A and B.

TABLE C3 - LOAD CELLS #2 AND #7 - CALIBRATION

LOAD CELL #6

LOAD (N)	$\Delta \varepsilon$		
	(1)	(2)	(3)
0	0	0	0
100,000	198	229	236
200,000	350	372	424
300,000	496	534	592
400,000	654	712	764
500,000	814	890	938
600,000	980	1070	1102
700,000	1152	1259	1229
600,000	979	1078	1085
500,000	806	885	911
400,000	635	700	728
300,000	338	505	546
200,000	306	322	357
100,000	163	188	176
0	-2	-3	0

LOAD CELL #8

	$\Delta \varepsilon$		
	(1)	(2)	(3)
0	0	0	0
100,000	208	245	253
200,000	334	364	384
300,000	448	481	508
400,000	567	617	641
500,000	688	775	779
600,000	810	935	915
700,000	936	1097	1017
600,000	803	925	899
500,000	672	750	746
400,000	522	583	592
300,000	394	421	438
200,000	266	274	302
100,000	152	158	165
0	-3	3	0

$\Delta \varepsilon$ is the sum of channels A and B.

TABLE C4 - LOAD CELLS #6 AND #8 - CALIBRATION

Load cell no.	Relationship	Coefficient of Determination (r^2)
1	$y = 0.6236 x - 17.8698$.9874
2	$y = 0.6039 x - 17.3285$.9882
3	$y = 0.6013 x - 24.0932$.9901
4	$y = 0.6091 x + 15.0796$.9897
5	$y = 0.5922 x - 1.3322$.9812
6	$y = 0.5804 x - 12.7504$.9889
7	$y = 0.6225 x - 3.3985$.9853
8	$y = 0.7053 x - 32.1037$.9793

where y = normal load (kN)
 x = sum of micro-strains read in both strain gauges ($x = \text{AVERAGE STRAIN} \times 10^{-6} \times 2$)

TABLE C5 - EQUATIONS RELATING LOADS TO MICROSTRAIN FOR THE LOAD CELLS 1 TO 8.

ZERO READINGS:	A	B	
	-385	-293*	* tunnel
	-362	-269	
	-366	-268	
	-366	-268	

DATE (81)	TIME	DIST.F/ TAIL (m)	A	B	Δ A+B (zero read/ tunnel)	LOAD KN
17-02	15:00	2.2	-740	-249	-358	210
18-02	07:00	2.2	-720	-262	-351	205
18-02	11:15	4.2	----	-291	----	---
18-02	13:40	6.4	-577	-302	-248	140
19-02	14:30	6.4	-616	-295	-280	160
20-02	08:58	6.4	-632	-284	-285	160
23-02	14:05	8.4	-655	-282	-306	175
24-02	09:20	10.0	-663	-276	-308	177
25-02	14:20	16.0	-678	-269	-316	180
26-02	11:45	18.4	-685	-270	-324	187
03-03	14:25	38.8	-694	-278	-294	170
10-03	11:16	65.2	-706	-274	-302	172
17-03	11:00	88.0	-719	-273	-314	180
19-03	18:00	88.0	-717	-274	-313	179
09-04	13:30	88.0	-755	-256	-333	192
27-05	15:05	88.0	-785	-248	-355	205

TABLE C6 - LOAD CELL #1 - FIELD DATA

ZERO READINGS:	A	B	
	-691	-1015	
	----	-1016	
	----	-1026*	* tunnel
	-692	-1016	

DATE (81)	TIME	DIST. TAIL (m)	A	B	Δ A+B (zero read/ lab)	LOAD kN
17-02	13:40	0.4	-850	-1137	-270	145
17-02	15:00	2.2	-861	-1083	-227	120
18-02	07:00	2.2	-878	-1093	-254	135
18-02	11:15	4.2	-883	-1065	-231	120
18-02	13:40	6.4	-834	-1080	-197	105
19-02	14:30	6.4	-868	-1098	-249	135
20-02	08:58	6.4	-888	-1097	-268	145
23-02	14:05	8.4	-897	-1095	-275	150
24-02	09:20	10.0	-933	-1097	-313	170
25-02	14:20	16.0	-911	-1114	-308	160
26-02	11:45	18.4	-937	-1115	-346	190
03-03	14:25	38.8	-931	-1123	-348	195
10-03	11:16	65.2	-923	-1136	-353	200
17-03	11:00	88.0	-926	-1145	-365	205
19-03	18:00	88.0	-922	-1147	-363	204
09-04	13:30	88.0	-953	-1142	-389	217
27-05	15:05	88.0	-981	-1141	-416	233

TABLE C7 - LOAD CELL #2 - FIELD DATA

ZERO READINGS:	A	B	
	+68*	-636*	* tunnel
	+87	-611	
	+89	-619	
	+82	-624	

DATE (81)	TIME	DIST.F/ TAIL (m)	A	B	Δ A+B (zero read/ tunnel)	LOAD KN
18-02	07:00	1.3	----	-659	----	---
18-02	10:10	2.8	-354	-672	-458	255
18-02	13:38	5.2	-345	-679	-456	255
19-02	14:30	5.2	-347	-698	-477	265
20-02	08:58	5.2	-352	-700	-484	267
23-02	14:05	7.2	-377	-710	-519	287
24-02	09:20	8.8	-354	-716	-502	275
25-02	14:20	14.8	-380	-721	-533	297
26-02	11:45	17.2	-390	-717	-539	300
03-03	14:25	37.6	-395	-723	-550	305
10-03	11:16	64.0	-395	-729	-556	310
17-03	11:00	86.8	-401	-734	-567	317
19-03	18:00	86.8	-397	-736	-565	315
09-04	13:30	86.8	-427	-723	-582	326
27-05	15:05	86.8	-452	-720	-604	336

TABLE C8 - LOAD CELL #3 - FIELD DATA

ZERO READINGS:	A	B	
	-228*	-343*	* tunnel
	-207	-323	
	-208	-326	

DATE (81)	TIME	DIST TAIL (m)	A	B	Δ A+B (z. r. tunnel)	LOAD kN
18-02	07:40	1.3	-456	-376	-261	173
18-02	13:38	5.2	-488	-360	-277	185
19-02	14:30	5.2	-505	-366	-300	197
20-02	08:58	5.2	-513	-358	-300	197
23-02	14:30	7.2	-539	-365	-333	217
24-02	09:30	8.8	-543	-362	-334	217
25-02	14:20	14.8	-548	-370	-347	224
26-02	11:45	17.2	-562	-365	-356	230
03-03	14:25	37.6	-572	-370	-371	240
10-03	11:16	64.0	-574	-372	-375	243
17-03	11:00	86.8	-582	-375	-386	250
19-03	18:00	86.8	-580	-378	-387	251
09-04	13:30	86.8	-604	-377	-410	264
27-05	15:05	86.8	-624	-383	-436	277

TABLE C9 - LOAD CELL #4 - FIELD DATA

ZERO READINGS:	A	B	
	-96*	-315*	* tunnel
	-87	-300	
	-84	-300	
	-89	-307	

DATE (81)	TIME	DIST TAIL(m)	A	B	Δ A+B (z. r. tunnel)	LOAD kN
18-02	07:40	1.6	-320	-324	-233	135
18-02	13:33	4.0	-322	-312	-223	130
19-02	14:30	4.0	-348	-333	-270	157
20-02	08:58	4.0	-366	-318	-273	160
23-02	14:05	6.0	-387	-331	-307	180
24-02	09:30	7.6	-383	-333	-305	180
25-02	14:20	13.6	-405	-333	-327	190
26-02	11:45	16.0	-428	-322	-339	200
03-03	14:25	36.4	-440	-331	-360	210
10-03	11:26	62.8	-449	-334	-372	215
17-03	11:00	85.6	-460	-338	-387	230
19-03	18:00	85.6	-456	-340	-385	220
09-04	13:30	85.6	-495	-328	-412	240
27-05	15:05	85.6	-520	-333	-442	258

TABLE C10 - LOAD CELL #5 - FIELD DATA

ZERO READINGS:	A	B	
	-422*	+115*	* tunnel
	-403	+141	
	-400	+141	
	-415	+131	

DATE (81)	TIME	DIST TAIL (m)	A	B	Δ A+B (z. r. tunnel)	LOAD kN
18-02	09:53	1.6	-578	+ 59	-212	110
18-02	13:33	4.0	-613	+ 81	-225	120
19-02	14:30	4.0	-630	+ 69	-254	137
20-02	08:58	4.0	-560	+ 49	-204	107
23-02	14:30	6.0	-589	+ 67	-215	114
24-02	09:30	7.6	-645	+102	-236	125
25-02	14:20	13.6	-645	+ 94	-244	130
26-02	11:45	16.0	-650	+ 91	-252	135
03-03	14:25	36.4	-657	+ 81	-269	145
10-03	11:16	62.8	-660	+ 80	-273	147
17-03	11:00	85.6	-672	+ 79	2864	155
19-03	18:00	85.6	-668	+ 77	-284	154
09-04	13:30	85.6	-685	+ 87	-291	158
27-05	15:05	85.6	-704	+ 86	-311	170

TABLE C11 - LOAD CELL #6 - FIELD DATA

ZERO READINGS:	A	B	
	+314*	-316*	* tunnel
	+386	-306	
	+380	-309	
	+372	-316	
	+378	-308	

DATE (81)	TIME	DIST TAIL (m)	A	B	Δ A+B (z. r. tunnel)	LOAD kN
18-02	11:06	1.6	+154	-313	-195	125
18-02	13:33	2.8	+313	-371	-58	40
19-02	14:30	2.8	+296	-383	-85	57
20-02	08:58	2.8	+329	-370	-39	30
23-02	14:30	4.8	+308	-361	-51	35
24-02	09:30	6.4	+286	-362	-74	50
25-02	14:20	12.4	+265	-355	-88	60
26-02	11:45	14.8	+267	-356	-87	60
03-03	14:25	35.2	+249	-361	-110	70
10-03	11:16	61.6	+241	-360	-117	75
17-03	11:00	84.4	+230	-358	-126	83
19-03	18:00	84.4	+234	-360	-129	81
09-04	13:30	84.4	+207	-347	-138	90
27-05	15:05	84.4	+176	-337	-159	103

TABLE C12 - LOAD CELL #7 - FIELD DATA

ZERO READINGS:	A	B	
	-883	-237	tunnel
	-867	-225	
	-871	-228	
	-872	-227	

DATE (81)	TIME	DIST TAIL (m)	A	B	Δ A+B (z. r. tunnel)	LOAD kN
18-02	11:00	1.6	-1034	-228	-142	70
18-02	13:33	2.8	-1066	-252	-198	108
19-02	14:30	2.8	-1091	-258	-229	130
20-02	08:58	2.8	- 986	-250	-116	50
23-02	14:10	4.8	-1023	-240	-143	70
24-02	09:25	6.4	-1036	-230	-146	70
25-02	14:20	12.4	-1055	-225	-160	80
26-02	11:45	14.8	-1060	-227	-167	86
03-03	14:25	35.2	-1073	-232	-185	100
10-03	11:16	61.6	-1079	-230	-189	105
17-03	11:00	84.4	-1092	-226	-198	110
19-03	18:00	84.4	-1091	-227	-198	110
09-04	13:30	84.4	-1123	-211	-214	117
27-05	15:05	84.4	-1157	-202	-239	135

TABLE C13 - LOAD CELL #8 - FIELD DATA

SL1

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	+2930	0	0
4000	+3068	138	4140
8000	+3194	264	7920
12000	+3318	388	11600
16000	+3440	510	15300
20000	+3560	630	18900
24000	+3677	747	22400
28000	+3795	865	26000
32000	+3911	981	29400
36000	+4030	1100	33000
32000	+3954	1024	30700
24000	+3761	831	24900
16000	+3508	578	17300
8000	+3230	300	9000
0	+2930	0	0

SL2

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	+0569	0	0
4000	+0703	134	4020
8000	+0823	254	7620
12000	+0947	378	11340
16000	+1068	499	15000
20000	+1180	611	18300
24000	+1295	726	21800
28000	+1406	837	25100
32000	+1513	944	28300
36000	+1627	1058	31700
32000	+1538	969	29100
24000	+1338	769	23100
16000	+1121	552	16600
8000	+0860	291	8730
0	+0572	3	90

Table C.14 STEEL LAGGING CALIBRATION - SL1 & SL2

SL 3

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-2360	0	0
4000	-2225	135	4050
8000	-2110	250	7500
12000	-1995	365	11000
16000	-1880	480	14400
20000	-1767	593	17800
24000	-1657	703	21100
28000	-1547	813	24400
32000	-1440	920	27600
36000	-1330	1030	30900
32000	-1405	955	28700
24000	-1585	775	23300
16000	-1818	542	16300
8000	-2084	276	8280
0	-2367	7	210

SL 4

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	+2107	0	0
4000	+2242	135	4050
8000	+2370	263	7890
12000	+2491	384	11500
16000	+2610	503	15100
20000	+2725	618	18500
24000	+2838	731	21900
28000	+2952	845	25400
32000	+3069	962	28900
36000	+3184	1077	32300
32000	+3090	983	29500
24000	+2880	773	23200
16000	+2667	560	16800
8000	+2395	288	8640
0	+2096	11	330

Table C.15 STEEL LAGGING CALIBRATION - SL3 & SL4

<u>SL5</u>			
Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-2457	0	0
4000	-2333	124	3720
8000	-2216	241	7230
12000	-2100	357	10700
16000	-1989	468	14000
20000	-1878	579	17400
24000	-1770	687	20600
28000	-1658	799	24000
32000	-1550	907	27200
36000	-1438	1019	30600
32000	-1519	938	28140
24000	-1722	735	22100
16000	-1932	525	15800
8000	-2180	277	8310
0	-2460	3	90

<u>SL6</u>			
Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-0520	0	0
4000	-0391	129	3870
8000	-0272	248	7440
12000	-0160	360	10800
16000	-0047	473	14200
20000	+0073	593	17800
24000	+0183	703	21100
28000	+0295	815	24500
32000	+0406	926	27800
36000	+0520	1040	31200
32000	+0428	948	28400
24000	+0229	749	22500
16000	+0010	530	15900
8000	+0250	270	8100
0	-0533	13	390

Table C.16 STEEL LAGGING CALIBRATION - SL5 & SL6

<u>SL 7</u>			
Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-1997	0	0
4000	-1861	136	4080
8000	-1737	260	7800
12000	-1617	380	11400
16000	-1500	497	14900
20000	-1382	615	18500
24000	-1273	724	21700
28000	-1162	835	25100
32000	-1052	945	28400
36000	-0941	1056	31700
32000	-1019	978	29300
24000	-1214	783	23500
16000	-1450	547	16400
8000	-1710	287	8610
0	-2000	3	90

<u>SL 8</u>			
Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-2774	0	0
4000	-2636	138	4140
8000	-2512	262	7860
12000	-2388	386	11600
16000	-2268	506	15200
20000	-2146	628	18800
24000	-2025	749	22500
28000	-1906	868	26000
32000	-1798	976	29300
36000	-1688	1086	32600
32000	-1768	1006	30200
24000	-1970	804	24100
16000	-2212	562	16900
8000	-2487	287	8610
0	-2788	14	420

Table C.17 STEEL LAGGING CALIBRATION - SL7 & SL8

SL 9

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-2780	0	0
4000	-2655	125	3750
8000	-2535	245	7350
12000	-2412	368	11000
16000	-2295	485	14600
20000	-2180	600	18000
24000	-2065	715	21500
28000	-1953	827	24800
32000	-1840	940	28200
36000	-1724	1056	31700
32000	-1812	968	29000
24000	-2017	763	22900
16000	-2240	540	16200
8000	-2500	280	8400
0	-2791	11	330

SL10

Load (N)	Gage (Microinches/inch)			Strain ($\times 10^{-6}$)			Centre Stress (lb/in. ²)
	Quarter Point	Centre	Quarter Point	Quarter Point	Centre	Quarter Point	
0	-2953	-2960	+3847	0	0	0	0
2000	-2896	-2894	+3490	57	66	43	1980
4000	-2955	-2835	+3935	98	125	88	3750
6000	-2809	-2773	+3979	144	187	132	5610
8000	-2765	-2714	+4023	188	246	176	7380
10000	-2719	-2653	+4066	234	307	219	9210
12000	-2675	-2594	+4110	278	366	263	11000
14000	-2632	-2534	+4152	321	426	305	12800
16000	-2590	-2476	+4196	363	484	349	14500
18000	-2545	-2418	+4236	408	542	389	16300
20000	-2503	-2362	+4280	450	598	433	17900
22000	-2460	-2304	+4320	493	656	473	19700
24000	-2421	-2246	+4365	532	714	518	21400
26000	-2375	-2187	+4407	578	773	560	23200
28000	-2337	-2133	+4450	616	827	603	24800
30000	-2290	-2071	+4492	663	889	645	26700
32000	-2254	-2015	+4540	699	945	693	28400
34000	-2210	-1960	+4575	743	1000	728	30000
32000	-2232	-1996	+4557	721	964	710	28900
24000	-2376	-2195	+4418	578	765	571	23000
16000	-2536	-2420	+4256	417	540	409	16200
8000	-2735	-2678	+4064	218	282	217	8460
0	-2961	-2968	+3845	8	8	2	240

Table C.18 STEEL LAGGING CALIBRATION - SL9 & SL10

SL11

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	-2472	0	0
4000	-2347	125	3750
8000	-2234	238	7140
12000	-2120	352	10600
16000	-2005	467	14000
20000	-1896	576	17300
24000	-1784	688	20600
28000	-1636	836	25100
32000	-1560	912	27400
36000	-1450	1022	30700
32000	-1529	943	28300
24000	-1703	769	23100
16000	-1935	537	16100
8000	-2200	272	8160
0	-2467	5	150

SL12

Load (N)	Centre Gage (Microinches/inch)	Strain ($\times 10^{-6}$)	Stress (lb./in. ²)
0	+0958	0	0
4000	+1086	128	3840
8000	+1200	242	7260
12000	+1317	359	10800
16000	+1433	475	14300
20000	+1547	589	17700
24000	+1654	696	20900
28000	+1765	807	24200
32000	+1873	915	27500
36000	+1983	1025	30800
32000	+1908	950	28500
24000	+1734	776	23300
16000	+1482	524	15700
8000	+1214	256	7680
0	+0933	25	750

Table C.19 STEEL LAGGING CALIBRATION - SL11 & SL12

PIECE OF LAGGING # 1

DATE	DIST.TAIL	$\Delta \epsilon . 10^{-6}$				$\Delta M (KN.M)$			
		E	C	W		E	C	W	
17-02	2.2	68	85	48		0.44	0.54	0.31	
18-02	2.2	55	68	15		0.35	0.44	0.10	
18-02	5.2	235	274	189		1.51	1.76	1.21	
19-02	6.4	183	277	195		1.17	1.78	1.25	
20-02	6.4	189	294	188		1.21	1.88	1.21	
23-02	8.4	200	288	184		1.28	1.85	1.18	
24-02	10.0	248	295	213		1.59	1.89	1.37	
25-02	17.0	213	---	198		1.37	---	1.27	
26-02	18.4	233	---	232		1.49	---	1.49	
03-03	38.8	---	---	208		---	---	1.33	
10-03	65.2	225	305	196		1.44	1.96	1.26	
17-03	88.0	203	290	193		1.30	1.86	1.24	
19-03	88.0	208	305	203		1.33	1.96	1.30	
9-04	88.0	198	295	188		1.27	1.89	1.21	

PIECE OF LAGGING # 2

DATE	DIST.TAIL	$\Delta \epsilon . 10^{-6}$				$\Delta M (KN.M)$			
		E	C	W		E	C	W	
17-02	2.2	-20	5	0		-0.13	0.03	0	
18-02	2.2	-12	22	15		-0.08	0.14	0.10	
18-02	5.2	-1	43	67		-0.01	0.28	0.43	
19-02	6.4	22	62	50		0.14	0.40	0.32	
20-02	6.4	39	53	49		0.25	0.34	0.31	
23-02	8.4	8	36	14		0.05	0.23	0.09	
24-02	10.0	39	75	8		0.25	0.48	0.05	
25-02	17.0	9	55	45		0.06	0.35	0.29	
26-02	18.4	64	112	89		0.41	0.72	0.57	
03-03	38.8	---	61	56		---	0.39	0.36	
10-03	65.2	34	64	40		0.22	0.41	0.26	
17-03	88.0	-1	50	20		-0.01	0.32	0.13	
19-03	88.0	34	55	40		0.22	0.35	0.26	
9-04	88.0	-21	50	-50		-0.13	0.32	-0.32	

TABLE C20 - STEEL LAGGING SL1 AND SL2 - FIELD DATA

PIECE OF LAGGING # 3

DATE	DIST. TAIL	$\Delta \varepsilon \cdot 10^6$				$\Delta M (KN.M)$		
		E	C	W		E	C	W
17-02	2.2	5	4	1		0.03	0.03	0.01
18-02	2.2	10	59	16		0.06	0.38	0.10
18-02	5.2	-	32	13		-	0.21	0.08
19-02	6.4	-	-	-		-	-	-
20-02	6.4	-	-	-		-	-	-
23-02	8.4	-	-	-		-	-	-
24-02	10.0	-	-	-		-	-	-
25-02	17.0	-	-	-		-	-	-
26-02	18.4	58	47	-		0.37	0-30	-
03-03	38.8	194	81	-		1.24	0.52	-
10-03	65.2	-	66	39		-	0.42	0.25
17-03	88.0	35	59	21		0.22	0.38	0.13
19-03	88.0	45	64	26		0.29	0.41	0.17
9-04	88.0	25	59	16		0.16	0.38	0.10

PIECE OF LAGGING # 4

DATE	DIST. TAIL	$\Delta \varepsilon \cdot 10^6$				$\Delta M (KN.M)$		
		E	C	W		E	C	W
17-02	2.2	5	4	1		0.03	0.03	0.01
18-02	-	-	-	-		-	-	-
18-02	5.2	135	149	126		0.87	0.96	0.81
19-02	6.4	138	167	159		0.88	1.07	1.02
20-02	6.4	-	-	150		-	-	0.96
23-02	8.4	150	185	-215		0.96	1.19	-1.38
24-02	10.0	136	180	-841		0.87	1.15	-5.39
25-02	17.0	-	180	-291		-	1.15	-1.87
26-02	18.4	171	232	182		0.12	1.10	1.17
03-03	38.8	139	190	171		0.89	1.22	1.10
10-03	65.2	158	209	174		1.01	1.34	1.12
17-03	88.0	155	185	149		0.99	1.19	0.01
19-03	88.0	139	190	55		0.89	1.22	0.35
9-04	88.0	115	195	144		0.74	1.25	0.92

TABLE C21 - STEEL LAGGING SL3 AND SL4 - FIELD DATA

PIECE OF LAGGING # 5

DATE	DIST. TAIL	$\Delta \varepsilon 10^6$				$\Delta M (KN.M)$		
		E	C	W		E	C	W
17-02	1.3	-3	4	8		-0.02	0.03	0.05
18-02	1.3	-	-	-		-	-	-
18-02	4.0	-20	-25	-		-0.13	-0.16	-
19-02	5.2	-19	-	-1		0.12	-	-0.01
20-02	5.2	-	-	-		-	-	-
23-02	7.2	-	-24	-5		-	-0.15	-0.03
24-02	8.8	-17	-7	-		-0.11	-0.04	0.03
25-02	15.8	-20	-7	-		-0.13	-0.04	0.06
26-02	17.2	-	-	-		-	-	-
03-03	37.6	-56	-	-63		-0.36	1.19	-0.40
10-03	64.0	-30	-8	-12		-0.19	-0.05	-0.08
17-03	86.8	-45	-32	-20		-0.29	-0.21	-0.13
19-03	86.8	-35	-22	-13		-0.22	-0.14	-0.08
9-04	86.8	-45	-37	-25		-0.29	-0.24	-0.16

PIECE OF LAGGING # 6

DATE	DIST. TAIL	$\Delta \varepsilon 10^6$				$\Delta M (KN.M)$		
		E	C	W		E	C	W
17-02	1.3	-9	-13	-9		0.06	0.08	-0.06
18-02	1.3	31	-8	-9		0.20	-0.05	-0.06
18-02	4.0	94	80	31		0.60	0.51	0.20
19-02	5.2	135	130	82		0.87	0.83	0.53
20-02	5.2	127	165	120		0.81	1.06	0.77
23-02	7.2	126	142	111		0.81	0.91	0.71
24-02	8.8	141	157	118		0.90	1.01	0.76
25-02	15.8	103	147	118		0.66	0.94	0.76
26-02	17.2	151	180	124		0.97	1.15	0.79
03-03	37.6	-	143	119		-	0.92	0.76
10-03	64.0	189	149	-		1.21	0.96	-
17-03	86.8	136	152	123		0.87	0.97	0.79
19-03	86.8	141	162	115		0.90	1.04	0.74
9-04	86.8	121	157	113		0.78	1.01	0.72

TABLE C22 - STEEL LAGGING SL5 AND SL6 - FIELD DATA

PIECE OF LAGGING # 7
 $\Delta \varepsilon \cdot 10^6$

DATE	DIST. TAIL	$\Delta M (KN.M)$			
		E	C	W	
17-02	1.3	0	1	-7	
18-02	1.3	17	60	121	0.04
18-02	4.0	21	-	-	0.78
19-02	5.2	-12	-	-	-
20-02	5.2	25	-	-	-
23-02	7.2	-	-	-	-
24-02	8.8	25	88	21	-
25-02	15.8	20	53	31	0.13
26-02	17.2	20	24	29	0.20
03-03	37.6	-	52	-	0.15
10-03	64.0	41	70	-	0.33
17-03	86.8	25	-	26	0.45
19-03	86.8	37	68	21	-
9-04	86.8	10	78	14	0.17
					0.13
					0.09

PIECE OF LAGGING # 8
 $\Delta \varepsilon \cdot 10^6$

DATE	DIST. TAIL	$\Delta M (KN.M)$			
		E	C	W	
17-02	1.3	-	31	-	-
18-02	1.3	-	-	-	-
18-02	4.0	119	-	48	0.31
19-02	5.2	132	172	50	0.32
20-02	5.2	-	-	-	-
23-02	7.2	100	149	-	-
24-02	8.8	86	159	76	0.96
25-02	15.8	106	159	66	1.02
26-02	17.2	-	171	53	1.02
03-03	37.6	-	151	85	1.10
10-03	64.0	101	141	58	0.97
17-03	86.8	106	131	61	0.90
19-03	86.8	121	131	76	0.84
9-04	86.8	101	106	61	0.84
					0.68

TABLE C23 - STEEL LAGGING SL7 AND SL8 - FIELD DATA

PIECE OF LAGGING # 9
 $\Delta \varepsilon \cdot 10^{-6}$

DATE	DIST. TAIL	$\Delta M (KN.M)$			
		E	C	W	
18-02	2.8	-10	-5	-7	-0.06
19-02	4.0	-2	8	2	-0.01
20-02	4.0	-161	-160	-215	-1.03
23-02	6.0	-4	-2	3	-0.03
24-02	7.6	12	0	3	0.08
25-02	14.8	17	-5	-10	0.11
26-02	16.0	40	19	16	0.26
03-03	36.4	49	13	14	0.31
10-03	62.8	-	1	-5	-
17-03	85.6	-28	-15	-25	-0.18
19-03	85.6	-23	-5	-	-0.15
9-04	85.6	-48	-30	-30	-0.31

PIECE OF LAGGING # 10
 $\Delta \varepsilon \cdot 10^{-6}$

DATE	DIST. TAIL	$\Delta M (KN.M)$			
		E	C	W	
18-02	2.8	136	194	164	0.87
19-02	4.0	139	183	164	0.89
20-02	4.0	-	-27	-64	-
23-02	6.0	109	169	122	0.70
24-02	7.6	110	164	139	0.71
25-02	14.8	120	164	139	0.77
26-02	16.0	-	184	-	-
03-03	36.4	118	190	-	0.76
10-03	62.8	-	183	-	-
17-03	85.6	95	154	139	0.61
19-03	85.6	115	149	144	0.74
9-04	85.6	80	141	139	0.51

TABLE C24 - STEEL LAGGING SL9 AND SL10 - FIELD DATA

DATE	DIST. TAIL	PIECE OF LAGGING # 11 $\Delta \varepsilon (10^{-6})$				$\Delta M (KN.M)$		
		E	C	W		E	C	W
18-02	2.8	32	1	31		0.21	0.01	0.20
19-02	4.0	40	54	42		0.26	0.35	0.27
20-02	4.0	30	-	-		0.19	-	-
23-02	6.0	58	-	27		0.37	-	0.17
24-02	7.6	30	-	35		0.19	-	0.22
25-02	14.8	-	-	34		-	-	0.22
26-02	16.0	37	-	55		0.24	-	0.35
03-03	36.4	4	12	33		0.03	0.08	0.21
10-03	62.8	33	-	-		0.21	-	-
17-03	85.6	25	25	20		0.16	0.16	0.13
19-03	85.6	25	31	25		0.16	0.20	0.16
9-04	85.6	25	30	15		0.16	0.19	0.10

DATE	DIST. TAIL	PIECE OF LAGGING # 12 $\Delta \varepsilon (10^{-6})$				$\Delta M (KN.M)$		
		E	C	W		E	C	W
18-02	2.8	45	48	2		0.29	0.31	0.01
19-02	4.0	66	57	42		0.42	0.37	0.27
20-02	4.0	58	59	-2		0.37	0.38	-0.01
23-02	6.0	73	54	-41		0.47	0.35	-0.26
24-02	7.6	110	90	61		0.71	0.58	0.39
25-02	14.8	95	-30	6		0.61	-0.19	0.04
26-02	16.0	112	120	47		0.72	0.77	0.30
03-03	36.4	89	95	34		0.57	0.61	0.22
10-03	62.8	90	84	63		0.58	0.54	0.40
17-03	85.6	85	110	66		0.54	0.71	0.42
19-03	85.6	90	100	66		0.58	0.64	0.42
9-04	85.6	90	110	76		0.58	0.71	0.49

TABLE C25 - STEEL LAGGING SL11 AND SL12 - FIELD DATA

CONVERGENCE MEASUREMENTS (UNITS mm)

DATE 25/02/81

RING	I	II	III	IV	V	VI	VII
5	4871.18	1996.36	3934.00	3748.66	2115.59	5716.90	5694.70
6	4867.37	2000.65	3987.09	3637.45	2181.02	5727.29	5692.16
7	4907.28	1951.61	3968.87	3620.11	2207.26	5774.10	5685.64
8	4961.00	1924.86	3961.18	3642.81	2173.50	5767.85	5739.08

DATE 03/03/81

RING	I	II	III	IV	V	VI	VII
5	4871.18	1996.28	3934.81	3749.80	2115.74	5717.08	5695.57
6	4867.35	1999.94	3987.54	3638.17	2179.88	5726.83	5692.77
7	4906.39	1951.76	3969.58	3619.90	2207.43	5773.82	5685.53
8	4960.24	1924.30	3962.37	3643.22	2173.22	5767.24	5737.98

DATE 04/03/81

RING	I	II	III	IV	V	VI	VII
5	4870.75	1996.16	3934.56	3749.29	2115.36	5716.90	5694.55
6	4866.99	1999.66	3987.75	3637.94	2179.70	5726.40	5691.70
7	4906.23	1951.33	3969.79	3619.85	2207.13	5773.70	5684.87
8	4959.98	1924.05	3962.73	3642.58	2172.64	5767.19	5737.30

I to VII : Chords defined in Figure 4.34

TABLE C26 - LINING DISPLACEMENTS MEASUREMENTS

D. APPENDIX - SUPPORT COMPRESSIVE STIFFNESS

COMPRESSIVE STIFFNESS = $K_s = \frac{\Delta p/p_o}{\Delta u/u_o}$

$\frac{\Delta p}{\Delta D/D} = \frac{E_s \cdot A_e}{(1 - \nu_s^2) R}$ (EINSTEIN AND SCHWARTZ, 1979)

FOR THE AXISYMMETRIC CASE : $\Delta D = 2 \Delta u$

$\frac{\Delta p}{\Delta u} = \frac{2 E_s A_e}{(1 - \nu_s^2) R D} = K_s \cdot p_o / u_o$

$K_s = \frac{2 E_s A_s u_o}{s (1 - \nu_s^2) R D p_o}$

WHERE :

- p = UNIFORM RADIAL PRESSURE
- p_o = IN SITU FIELD STRESS
- u = RADIAL LINING DISPLACEMENT
- u_o = WALL DISPLACEMENT OF UNLINED TUNNEL (ELASTIC SOIL)
- E_s A_s ν_s = LINER PROP. SEE TABLE 5.1
- s = RIBS SPACING
- A_e = A_s/s
- D = TUNNEL DIAMETER
- R = TUNNEL RADIUS

LRT TUNNELS K_s = 2.62

EXP TUNNEL : K_s = 3.31

Figure D.1 DERIVATION OF THE SUPPORT COMPRESSIVE STIFFNESS

B30313